



LOCAL AGENCY LETTING INFORMATION

CONTENTS

DATE ADDED	COUNTY/CITY	LETTING DATE	PAGE NUMBER
November 19, 2024	Pottawattamie	December 10, 2024	2
November 22, 2024	Dallas	December 11, 2024	3
November 5, 2024	Sac	December 12, 2024	5
November 12, 2024	Winnebago	December 13, 2024	6
November 12, 2024	Iowa	December 13, 2024	8
November 13, 2024	Adair	December 16, 2024	9
December 2, 2024	Adair	December 16, 2024	10
November 19, 2024	Bremer	December 23, 2024	11
December 3, 2024	Bremer	December 23, 2024	12

BULLETIN REPORTING FORM

County:	<u>Pottawattamie County</u>	Project No.:	<u>L-(WS31)--73-78</u>
Proposal Guarantee:	<u>\$5,000.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>12/10/2024</u>	Time of Letting:	<u>10:00 AM</u>
Bid Turn-In Location:	<u>County Engineer</u>	Type of Project:	<u>Bridge Replacement</u>
Contact Phone No.:	<u>712-328-5608</u>	Contact FAX No.:	<u>712-328-4751</u>

Specific Description of Project:

Replacement of existing single span high truss bridge with 120'x24' - 3 span bridge with steel piling, steel beams, and timber deck.

QUANTITY	UNIT	DESCRIPTION
1	LS	REMOVAL OF EXISTING BRIDGE
1	LS	MOBILIZATION
1	EACH	Construct Bridge with County Furnished Materials

Date: 11/19/2024 Local Agency Official: John Rasmussen, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

BULLETIN REPORTING FORM

County:	<u>Dallas County</u>	Project No.:	<u>LFM-C025(NO-1)--7X-25</u>
Proposal Guarantee:	<u>\$250,000.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>12/11/2024</u>	Time of Letting:	<u>10:00 AM</u>
Bid Turn-In Location:	<u>County Engineer</u>	Type of Project:	<u>HMA Paving</u>
Contact Phone No.:	<u>515-993-4289</u>	Contact FAX No.:	<u>515-993-3965</u>

Specific Description of Project:

QUANTITY	UNIT	DESCRIPTION
20859	CY	TOPSOIL, STRIP AND STOCKPILE
2334.8	CY	MODIFIED SUBBASE, PLACE ONLY
3285.28	TON	GRANULAR SHOULDERS, TYPE B
375.5	STA	SHOULDER CONSTRUCTION, EARTH
1752.16	TON	CHOKER STONE BASE
2793.8	TON	MACADAM STONE BASE
4635.2	CY	EXCAVATION, CLASS 13, FOR WIDENING
3604.31	SY	PAVEMENT SCARIFICATION
50500.7	SY	CRACKING AND SEATING OF P.C.C. PAVEMENT
4310.74	TON	HOT MIX ASPHALT MIXTURE INTERLAYER BASE COURSE, 3/8 IN. MIX
5515.47	TON	HOT MIX ASPHALT MIXTURE THIN LIFT SURFACE COURSE, 3/8 IN. MIX
2421.42	TON	HOT MIX ASPHALT HIGH TRAFFIC, BASE COURSE, 3/4 IN. MIX
24393.43	TON	HOT MIX ASPHALT HIGH TRAFFIC, INTERMEDIATE COURSE, 1/2 IN. MIX
1176.68	TON	ASPHALT BINDER, PG 58-28H, HIGH TRAFFIC
366.42	TON	ASPHALT BINDER, PG 58-34E, EXTREMELY HIGH TRAFFIC
468.84	TON	ASPHALT BINDER, PG 64-34E+, EXTREMELY HIGH TRAFFIC, 90% ELASTIC RECOVERY
6728.4	SY	FABRIC REINFORCEMENT
1	LS	HOT MIX ASPHALT PAVEMENT SAMPLES
30067.35	EACH	PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE LABORATORY VOIDS (FORMULA - BY PAY FACTOR)
3067.35	EACH	PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE FIELD VOIDS (FORMULA - BY PAY FACTOR)
4	EACH	RUMBLE STRIP PANEL (HMA SURFACE)
15900.37	EACH	PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA PAVEMENT SMOOTHNESS (BY SCHEDULE)
38346	LF	SUBDRAIN, LONGITUDINAL, (SHOULDER) 4 IN. DIA.
78	EACH	SUBDRAIN OUTLET, 500-10
14367.9	SY	REMOVAL AND CRUSHING OF PAVEMENT
119.62	STA	PAINTED PAVEMENT MARKING, WATERBORNE OR SOLVENT-BASED
375.54	STA	PAINTED PAVEMENT MARKINGS, HIGH-BUILD WATERBORNE
375.54	STA	GROOVES CUT FOR PAVEMENT MARKINGS
12	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
74	EACH	FLAGGERS

10	EACH	PILOT CARS
1	LS	MOBILIZATION
375.6	STA	MILLED SHOULDER RUMBLE STRIPS, HMA SURFACE
542.4	GAL	ASPHALT EMULSION FOR FOG SEAL (SHOULDER RUMBLE STRIPS)
187.8	STA	MILLED CENTERLINE RUMBLE STRIPS, HMA SURFACE
1470.82	TON	MODIFIED SUBBASE, FURNISH AND DELIVER

Date: 11/21/2024 Local Agency Official: Alan Miller, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

BULLETIN REPORTING FORM

County:	<u>Sac County</u>	Project No.:	<u>L-ED-0802--73-81</u>
Proposal Guarantee:	<u>\$12,500.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>12/12/2024</u>	Time of Letting:	<u>02:00 PM</u>
Bid Turn-In Location:	<u>County Engineer</u>	Type of Project:	<u>Box Culverts</u>
Contact Phone No.:	<u>712-662-7687</u>	Contact FAX No.:	<u>712-662-4746</u>

Specific Description of Project:

RCB Culvert New - Single Box on Fox Ave. over Creek, 0.2 miles south of 170th Street

QUANTITY	UNIT	DESCRIPTION
65	TON	SPECIAL BACKFILL
607	CY	EMBANKMENT-IN-PLACE
10	CY	EXCAVATION, CLASS 13, WASTE
97	CY	EXCAVATION, CLASS 10, CHANNEL
39.6	CY	MODIFIED SUBBASE
533.1	TON	GRANULAR SURFACING ON ROAD, CLASS C GRAVEL
1	LS	REMOVAL OF EXISTING BRIDGE
20	CY	GRANULAR BACKFILL
83	CY	EXCAVATION, CLASS 20
48	LF	PRECAST CONCRETE BOX CULVERT, 16 FT. X 6 FT.
2	EACH	PRECAST CONCRETE BOX CULVERT STRAIGHT END SECTION, 16 FT. X 6 FT.
1	EACH	TEMPORARY STREAM DIVERSION
192	SF	PILES, STEEL SHEET
30	TON	REVTMENT, CLASS E
1	LS	CONSTRUCTION SURVEY
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
120	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.

Date: 11/5/2024 Local Agency Official: Nick Buse, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

BULLETIN REPORTING FORM

County:	Winnebago County	Project No.:	Proposal ID: 95-CO95-2025HMA
Proposal Guarantee:	\$125,000.00	DBE or TSB Goal:	
Date of Letting:	12/13/2024	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Engineer	Type of Project:	HMA Resurfacing, HMA Pavement - Grade and New
Contact Phone No.:	641-585-2905	Contact FAX No.:	641-585-2891

Specific Description of Project:

This proposal includes the following project(s):

Section 001: L-ASMUS--73-95

Work Type: HMA Pavement - Grade & New

Location: On 500th St from 30th Ave to 40th Ave AND on 40th Ave from 500th St to 0.4 miles north of 500th St, 1.3 Miles

Road System: Local

Section 002: LFM-R20NORTH--7X-95 (DIV. II ONLY)

Work Type: Hot In-Place Recycling / HMA Resurfacing

Location: On R20, from Hwy 9 to Minnesota State Line, 7.84 Mi.

Road System: Farm to Market

QUANTITY	UNIT	DESCRIPTION
2984	CY	EMBANKMENT-IN-PLACE
2784	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
100	CY	EXCAVATION, CLASS 12, BOULDERS OR ROCK FRAGMENTS
4514	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
5769	CY	COMPACTION WITH MOISTURE CONTROL
3250	CY	MODIFIED SUBBASE
1944	TON	GRANULAR SHOULDERS, TYPE B
201	SY	PAVEMENT SCARIFICATION
65	TON	HOT MIX ASPHALT MIXTURE, WEDGE, LEVELING OR STRENGTHENING COURSE
2240	TON	HOT MIX ASPHALT STANDARD TRAFFIC, BASE COURSE, 3/4 IN. MIX
675	TON	HOT MIX ASPHALT STANDARD TRAFFIC, INTERMEDIATE COURSE, 1/2 IN. MIX
1745	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
284	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
1	LS	HOT MIX ASPHALT PAVEMENT SAMPLES
16014	EACH	PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE LABORATORY VOIDS (FORMULA - BY PAY FACTOR)
16014	EACH	PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE FIELD VOIDS (FORMULA - BY PAY FACTOR)
642	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
465	TON	SURFACING, DRIVEWAY, CLASS A CRUSHED STONE
2	EACH	APRONS, CONCRETE, 15 IN. DIA.
8	EACH	APRONS, CONCRETE, 24 IN. DIA.
2	EACH	APRONS, CONCRETE, 30 IN. DIA.
2	EACH	APRONS, CONCRETE, 36 IN. DIA.
60	LF	CULVERT, 2000D CONCRETE ENTRANCE PIPE, 15 IN. DIA.
128	LF	CULVERT, 2000D CONCRETE ENTRANCE PIPE, 24 IN. DIA.
66	LF	CULVERT, 2000D CONCRETE ENTRANCE PIPE, 30 IN. DIA.
80	LF	CULVERT, 2000D CONCRETE ENTRANCE PIPE, 36 IN. DIA.
60	LF	CULVERT, CONCRETE ROADWAY PIPE, 24 IN. DIA.
2	EACH	APRONS, UNCLASSIFIED, 15 IN. DIA.
16	LF	CULVERT, UNCLASSIFIED ENTRANCE PIPE, 15 IN. DIA.
4	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
		6

1	LS	(LUMP SUM ITEM) SWPPP PLAN MANAGEMENT
7.6	ACRE	MULCHING
7.6	ACRE	SEEDING AND FERTILIZING (RURAL)
150	SQ	SLOPE PROTECTION, WOOD EXCELSIOR MAT
2054	LF	SILT FENCE FOR DITCH CHECKS
1027	LF	REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS
206	LF	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK
30	LF	STABILIZED CONSTRUCTION ENTRANCE, EC-303
625	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.
625	LF	REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE
4	EACH	MOBILIZATIONS, EMERGENCY EROSION CONTROL
9141	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
548	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
1	LS	HOT MIX ASPHALT PAVEMENT SAMPLES
1	LS	TRAFFIC CONTROL
56	EACH	FLAGGERS
30	EACH	PILOT CARS
1	LS	MOBILIZATION

Date: 11/12/2024 Local Agency Official: Scott Meinders, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

BULLETIN REPORTING FORM

County:	<u>Iowa County</u>	Project No.:	<u>LFM-HC2350--7X-48</u>
Proposal Guarantee:	<u>\$0.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>12/13/2024</u>	Time of Letting:	<u>09:00 AM</u>
Bid Turn-In Location:	<u>County Engineer</u>	Type of Project:	<u>Materials & Delivery Only</u>
Contact Phone No.:	<u>319-642-3721</u>	Contact FAX No.:	<u></u>

Specific Description of Project:

Iowa County Is taking Bids for delivery of materials for a precast box culvert. Iowa County crews will install the box.

QUANTITY	UNIT	DESCRIPTION
2	EACH	Precast Concrete Box Culvert 15 Degree Right Ahead Skewed End Section
36	LF	Precast Concrete Box Culvert, 14' x 14'

Date: 11/12/2024 Local Agency Official: Nicholas Amelon, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

BULLETIN REPORTING FORM

County:	Adair County	Project No.:	L-LRCBW12H--73-01
Proposal Guarantee:	\$12,500.00	DBE or TSB Goal:	
Date of Letting:	12/16/2024	Time of Letting:	09:00 AM
Bid Turn-In Location:	County Engineer	Type of Project:	RCB Culvert New - Single Box
Contact Phone No.:	641-743-6111	Contact FAX No.:	

Specific Description of Project:

This project involves replacing an existing metal pipe culvert with a reinforced concrete box culvert along Adair County York Ave. The project will also include the placement of revetment, granular surfacing, and seeding.

QUANTITY	UNIT	DESCRIPTION
516	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
487	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
80.7	CY	GRANULAR MATERIAL FOR BLANKET AND SUBDRAIN
112.3	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
1	LS	REMOVAL OF EXISTING STRUCTURES
736	CY	EXCAVATION, CLASS 20
83	CY	STRUCTURAL CONCRETE (RCB CULVERT)
13423	LB	REINFORCING STEEL
2	EACH	APRONS, METAL, 36 IN. DIA.
40	LF	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 36 IN. DIA.
85	TON	REVETMENT, CLASS E
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
1	LS	REMOVE AND PLUG/CAP EXISTING WATER HYDRANT
0.5	ACRE	MULCHING
0.5	ACRE	NATIVE GRASS SEEDING
300	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.

Date: 11/13/2024 Local Agency Official: Nick Kauffman, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

BULLETIN REPORTING FORM

County: Adair County Project No.: L-LBRIN6S--73-01
 Proposal Guarantee: \$25,000.00 DBE or TSB Goal: _____
 Date of Letting: 12/16/2024 Time of Letting: 09:30 AM
 Bid Turn-In Location: County Engineer Type of Project: Bridge Replacement - Steel Girder
 Contact Phone No.: 641-743-6111 Contact FAX No.: _____

Specific Description of Project:

Project includes removing the existing twin span 74' x 22' bridge and replacing with a single span 80' x 24'-6" steel girder bridge. Bridge materials to be supplied by the Contractor. Project also includes the supply and placement of revetment.

QUANTITY	UNIT	DESCRIPTION
1	LS	REMOVAL OF EXISTING BRIDGE
42.3	CY	STRUCTURAL CONCRETE (BRIDGE)
600	LF	PILES, STEEL, HP 10 X 42
520	TON	REVTMENT, CLASS E
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
1	LS	CONSTRUCT BRIDGE AS PER PLANS
1	LS	STEEL BRIDGE MATERIAL

Date: 11/27/2024 Local Agency Official: Nick Kauffman, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

BULLETIN REPORTING FORM

County:	Bremer County	Project No.:	LFM-L-8-125--7X-09
Proposal Guarantee:	\$50,000.00	DBE or TSB Goal:	
Date of Letting:	12/23/2024	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	HMA CIR/Resurfacing
Contact Phone No.:	319-352-4302	Contact FAX No.:	319-352-4326

Specific Description of Project:

HMA CIR/Resurfacing on C-33 from V-56 to V-62 for 3 miles .

QUANTITY	UNIT	DESCRIPTION
2470	TON	GRANULAR SHOULDERS, TYPE B
3	MILE	CLEANING AND PREPARATION OF BASE
551.4	CY	EXCAVATION, CLASS 13, FOR WIDENING
366.7	TON	PAVEMENT SCARIFICATION
3455	TON	HOT MIX ASPHALT STANDARD TRAFFIC, BASE COURSE, 1/2 IN. MIX
3697	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
429.12	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
1	LS	HOT MIX ASPHALT PAVEMENT SAMPLES
6	EACH	RUMBLE STRIP PANEL (HMA SURFACE)
43234.3	SY	COLD IN-PLACE RECYCLED ASPHALT PAVEMENT
58366.4	GAL	ASPHALT STABILIZING AGENT (STANDARD ASPHALT EMULSION)
1	EACH	FIELD LABORATORY
599.18	STA	PAINTED PAVEMENT MARKING, WATERBORNE OR SOLVENT-BASED
6	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
24	EACH	FLAGGERS
6	EACH	PILOT CARS
1	LS	MOBILIZATION

Date: 11/19/2024 Local Agency Official: Landon Moore, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us

BULLETIN REPORTING FORM

County:	Bremer County	Project No.:	LFM-L-8-125--7X-09
Proposal Guarantee:	\$50,000.00	DBE or TSB Goal:	
Date of Letting:	12/23/2024	Time of Letting:	10:00 AM
Bid Turn-In Location:	County Auditor	Type of Project:	HMA CIR/Resurfacing
Contact Phone No.:	319-352-4302	Contact FAX No.:	319-352-4326

Specific Description of Project:

HMA CIR/Resurfacing on C-33 from V-56 to V-62 for 3 miles .

QUANTITY	UNIT	DESCRIPTION
2470	TON	GRANULAR SHOULDERS, TYPE B
3	MILE	CLEANING AND PREPARATION OF BASE
551.4	CY	EXCAVATION, CLASS 13, FOR WIDENING
366.7	TON	PAVEMENT SCARIFICATION
3455	TON	HOT MIX ASPHALT STANDARD TRAFFIC, BASE COURSE, 1/2 IN. MIX
3697	TON	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT
429.12	TON	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC
1	LS	HOT MIX ASPHALT PAVEMENT SAMPLES
6	EACH	RUMBLE STRIP PANEL (HMA SURFACE)
43234.3	SY	COLD IN-PLACE RECYCLED ASPHALT PAVEMENT
58366.4	GAL	ASPHALT STABILIZING AGENT (STANDARD ASPHALT EMULSION)
1	EACH	FIELD LABORATORY
1	LS	CONSTRUCTION SURVEY
599.18	STA	PAINTED PAVEMENT MARKING, WATERBORNE OR SOLVENT-BASED
6	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
24	EACH	FLAGGERS
6	EACH	PILOT CARS
1	LS	MOBILIZATION

Date: 12/3/2024 Local Agency Official: Landon Moore, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us