

# Jefferson Municipal Airport

## PAVEMENT MANAGEMENT REPORT



### PREPARED BY

Applied Pavement Technology, Inc.  
115 West Main Street, Suite 400  
Urbana, Illinois 61801  
(217) 398-3977  
[www.appliedpavement.com](http://www.appliedpavement.com)

**JULY 2022**



The preparation of this document was financed in part through an Airport Improvement Program grant from the Federal Aviation Administration (Project Number 3-19-0000-028-2021) as provided under Section 505 of the Airport and Airway Improvement Act of 1982, as amended. The contents do not necessarily reflect the DOT's official views or the policy of the FAA. Acceptance of this report by the FAA does not in any way constitute a commitment on the part of the United States to participate in any development depicted therein nor does it indicate the proposed development is environmentally acceptable in accordance with appropriate public laws.

# JEFFERSON MUNICIPAL AIRPORT PAVEMENT MANAGEMENT REPORT

## Prepared For:

Iowa Department of Transportation  
Modal Transportation Bureau – Aviation  
800 Lincoln Way  
Ames, Iowa 50010  
515-239-1691  
<https://iowadot.gov/aviation/>



## Prepared By:

Applied Pavement Technology, Inc.  
115 West Main Street, Suite 400  
Urbana, Illinois 61801  
217-398-3977  
<https://www.appliedpavement.com>



## In Association With:

Robinson Engineering Company  
Consulting Engineers  
819 Second Street NE  
Independence, Iowa 50644  
319-334-7211



## TABLE OF CONTENTS

INTRODUCTION .....	1
PAVEMENT INVENTORY .....	3
PAVEMENT EVALUATION.....	6
Pavement Evaluation Procedure .....	6
Pavement Evaluation Results.....	7
Inspection Comments.....	12
Runway .....	12
Taxiways.....	12
Aprons.....	12
PAVEMENT MAINTENANCE AND REHABILITATION PROGRAM .....	13
Analysis Parameters.....	13
Critical PCIs.....	13
Localized Preventive Maintenance Policies and Unit Costs.....	13
Major Rehabilitation Unit Costs .....	13
Budget and Inflation Rate .....	13
Analysis Approach.....	13
Analysis Results.....	14
General Maintenance Recommendations .....	15
FAA Requirements (Public Law 103-305).....	15
FAA Advisory Circular 150/5830-7B, Appendix A. Pavement Management Program (PMP) .....	16
SUMMARY .....	20

## LIST OF FIGURES

Figure 1. Pavement condition versus cost of repair.....	1
Figure 2. Pavement area by branch use at Jefferson Municipal Airport.....	4
Figure 3. Jefferson Municipal Airport network definition map.....	5
Figure 4. Visual representation of PCI scale on typical pavement surfaces .....	6
Figure 5. PCI versus repair type. ....	7
Figure 6. Pavement area by PCI range at Jefferson Municipal Airport.....	8
Figure 7. Area-weighted PCI by branch use at Jefferson Municipal Airport. ....	8
Figure 8. Jefferson Municipal Airport PCI map. ....	9

## LIST OF TABLES

Table 1. 2021 pavement evaluation results.....	10
Table 2. 5-year M&R program under an unlimited funding analysis scenario. ....	14
Table 3. Pavement inspection report.....	18

## APPENDIXES

Appendix A. Cause of Distress Tables .....	A-1
Appendix B. Inspection Photographs .....	B-1
Appendix C. Inspection Report.....	C-1
Appendix D. Work History Report.....	D-1
Appendix E. Localized Preventive Maintenance Policies and Unit Cost Tables .....	E-1
Appendix F. Year 2022 Localized Preventive Maintenance Details .....	F-1


## INTRODUCTION

Applied Pavement Technology, Inc. (APTech), with assistance from Robinson Engineering Company, updated the Airport Pavement Management System (APMS) for the Iowa Department of Transportation, Modal Transportation Bureau – Aviation (Iowa DOT). The APMS provides a means to monitor the condition of the pavements within the state of Iowa and to proactively plan for their preservation.

As part of this project, pavement conditions at Jefferson Municipal Airport were assessed in November 2021 using the Pavement Condition Index (PCI) procedure. During a PCI inspection, the types, severities, and amounts of distress present in a pavement are quantified. This information is then used to develop a composite index that represents the overall condition of the pavement in numerical terms, ranging from 0 (failed) to 100 (excellent). The PCI provides an overall measure of condition and an indication of the level of work that will be required to maintain or repair a pavement. The distress information also provides insight into what is causing the pavement to deteriorate, which is the first step in selecting the appropriate repair action to correct the problem.

Programmed into an APMS, PCI information is used to determine when preventive maintenance actions (such as crack or joint sealing) are advisable and to identify the most cost-effective time to perform major rehabilitation (such as an overlay or whitetopping). Delaying maintenance and rehabilitation (M&R) until a pavement structure has seriously degraded can cost many times more than if M&R was applied earlier in a pavement's life cycle, as shown in Figure 1. From a safety perspective, pavement distresses, such as cracks and loose debris, may pose risks in terms of the potential for aircraft tire damage and the ability of a pilot to safely control aircraft.

Figure 1. Pavement condition versus cost of repair.



The pavement evaluation results for Jefferson Municipal Airport are presented within this report and can be used by Jefferson Municipal Airport, the Iowa DOT, and the Federal Aviation Administration (FAA) to identify, prioritize, and schedule pavement M&R actions at the airport. In addition to this report, the interactive pavement management data visualization tool IDEA, containing the pavement management information collected during this project, was updated and may be accessed from the Iowa DOT's website (<https://iowadot.gov/aviation>).

## PAVEMENT INVENTORY

The project began with a review of the existing inventory information pertaining to the pavements at Jefferson Municipal Airport. The date of original construction, along with the date of any subsequent rehabilitation; the location of completed work; and the type of work undertaken were gathered. The information was used to update the pavement management database and associated maps as necessary to account for pavement-related work that had been undertaken since the last time the airport was evaluated in 2018.

The pavement network at Jefferson Municipal Airport was then divided into branches, sections, and sample units. A branch is a single entity that serves a distinct function. For example, a runway is considered a branch because it serves a single function (allowing aircraft to take off and land). Taxiways and aprons are also separate branches.


Each branch was further divided into sections. Traditionally, sections are defined as parts of the branch that share common attributes, such as cross-section, date of last construction, traffic level, and performance. Using this approach, if a runway was built in 1968 and then extended in 1984, it would contain two separate sections.

To estimate the overall condition of a pavement section, each section was subdivided into sample units. Portions of these sample units were evaluated during the pavement inspection, and the collected information was extrapolated to predict the overall section condition and quantities of distress.


Approximately 540,000 square feet of pavement were evaluated at Jefferson Municipal Airport, as illustrated in Figure 2. This figure also shows the area-weighted age, in years, of the pavements at the time of the inspection. Figure 3 provides a map that details how the pavement network was divided into management units and identifies the sample units that were evaluated during the pavement inspection at Jefferson Municipal Airport.



Figure 2. Pavement area by branch use at Jefferson Municipal Airport.




# FIGURE 3. NETWORK DEFINITION MAP.



**NETWORK DEFINITION LEGEND**

	BRANCH IDENTIFIER
	SECTION IDENTIFIER
	PCI VALUE
	SECTION BREAK LINE
	SAMPLE UNIT BREAK LINE
	SLAB JOINT
	SAMPLE UNIT NUMBER
	SAMPLE UNIT INSPECTED
	ADDITIONAL SAMPLE UNIT



115 W. Main Street, Suite 400  
Urbana, IL 61801  
Tel: (217) 398-3977  
Fax: (217) 398-4027

AGENCY: Iowa Department of Transportation			
LOCATION: Modal Transportation Bureau - Aviation			
Jefferson Municipal Airport			
Jefferson, Iowa			
PAGE TITLE: Network Definition Map			
PROJECT DATE: SEP. 2021	CREATION DATE: SEP. 2021	PROJECT MANAGER: LJR	JOB NUMBER: 17-020-AM05
DRAWING SCALE: 1"=300'	LAST MODIFIED DATE: JAN. 2022	REVISED BY: MDK	DRAWN BY: DSP
FILENAME: Jefferson.dwg		LAYOUT NAME/NUMBER: NET. DEF.	PAGE NUMBER: 5

## PAVEMENT EVALUATION

### Pavement Evaluation Procedure

APTech inspected the pavements at Jefferson Municipal Airport using the PCI procedure described in:

- FAA Advisory Circular 150/5380-6C, *Guidelines and Procedures for Maintenance of Airport Pavements* ([https://www.faa.gov/documentLibrary/media/Advisory\\_Circular/150-5380-6C.pdf](https://www.faa.gov/documentLibrary/media/Advisory_Circular/150-5380-6C.pdf)).
- FAA Advisory Circular 150/5380-7B, *Airport Pavement Management Program (PMP)* ([https://www.faa.gov/documentLibrary/media/Advisory\\_Circular/150-5380-7B.pdf](https://www.faa.gov/documentLibrary/media/Advisory_Circular/150-5380-7B.pdf)).
- ASTM D5340-20, *Standard Test Method for Airport Pavement Condition Index Surveys*.

The PCI provides a numerical indication of overall pavement condition, as illustrated in Figure 4. The types and amounts of deterioration are used to calculate the PCI of the section. The PCI ranges from a value of 0, which represents a pavement in a failed condition, to a value of 100, which represents a pavement in excellent condition. It is important to note that factors other than overall PCI need to be considered when identifying the appropriate type of repair, including types of distress present and rate of deterioration. Also, since the PCI does not assess the structural integrity or capacity of the pavement structure, further testing may be needed to validate and refine the treatment strategy.

Figure 4. Visual representation of PCI scale on typical pavement surfaces<sup>1</sup>.



<sup>1</sup>Photographs shown are not specific to Jefferson Municipal Airport.

Generally, pavements with relatively high PCIs that are not exhibiting significant load-related distress will benefit from preventive maintenance actions, such as crack sealing or joint resealing. As the PCI drops, the pavements may require major rehabilitation, such as an overlay or whitetopping. In some situations where the PCI has dropped low enough, reconstruction may be the only viable alternative due to the substantial damage to the pavement structure. Figure 5 illustrates how the appropriate repair type varies with the PCI of a pavement section and provides the corresponding colors used for the maps and charts in this report for each range of PCIs.

Figure 5. PCI versus repair type.

PCI Range	Repair
86-100	Preventive Maintenance
71-85	
56-70	
41-55	Major Rehabilitation
26-40	Reconstruction
11-25	
0-10	

The types of distress identified during the PCI inspection provide insight into the cause of pavement deterioration, which in turn helps in selecting a rehabilitation alternative that corrects the cause, thus eliminating or delaying its recurrence. PCI distress types are characterized as load-related (such as alligator cracking on asphalt-surfaced pavements or shattered slabs on portland cement concrete [PCC] pavements), climate/durability-related (such as weathering [a climate-related distress type on asphalt-surfaced pavements] and durability cracking [a durability-related distress type on PCC pavements]), and other (distress types that cannot be attributed solely to load or climate/durability).

Appendix A identifies the distress types considered during a PCI inspection and describes the likely cause of each distress type. It should be noted that a PCI is based on visual signs of pavement deterioration and does not provide a measure of structural capacity.

**Pavement Evaluation Results**

The pavements at Jefferson Municipal Airport were inspected in November 2021. The 2021 area-weighted condition of Jefferson Municipal Airport is 83, with conditions ranging from 73 to 100 (on a scale of 0 [failed] to 100 [excellent]). During the previous pavement inspection in 2018, the area-weighted PCI of the airport was 76.

Figure 6 summarizes the overall condition of the pavements at Jefferson Municipal Airport, and Figure 7 presents area-weighted condition (average PCI adjusted to account for the relative size of the pavement sections) by branch use. Figure 8 is a map that displays the condition of the evaluated pavements. Table 1 summarizes the results of the pavement evaluation. Appendix B presents photographs taken during the PCI inspection, and Appendix C contains detailed information on the distress types observed during the visual survey. Appendix D includes detailed work history information that was collected during the record review process.

Figure 6. Pavement area by PCI range at Jefferson Municipal Airport.




Figure 7. Area-weighted PCI by branch use at Jefferson Municipal Airport.

(Values on chart are area-weighted)





FIGURE 8. PCI MAP.



**LEGEND**

	BRANCH IDENTIFIER
	SECTION IDENTIFIER
	PCI VALUE
	SECTION BREAK LINE

RW927GL-10 (74)

**PAVEMENT CONDITION INDEX**

PCI
86-100
71-85
56-70
41-55
26-40
11-25
0-10

		115 W. Main Street, Suite 400 Urbana, IL 61801 Tel: (217) 398-3977 Fax: (217) 398-4027	
		322 1st Street East Independence, IA 50644 Tel: (319) 334-7211	
AGENCY: Iowa Department of Transportation Modal Transportation Bureau - Aviation			
LOCATION: Jefferson Municipal Airport Jefferson, Iowa			
PAGE TITLE: 2021 Pavement Condition Index Map			
PROJECT DATE: SEP. 2021	CREATION DATE: SEP. 2021	PROJECT MANAGER: LJR	JOB NUMBER: 17-020-AM05
DRAWING SCALE: 1"=300'	LAST MODIFIED DATE: APR. 2022	REVISED BY: DSP	DRAWN BY: DSP
FILENAME: Jefferson.dwg		LAYOUT NAME/NUMBER: PCI	PAGE NUMBER: 9

Table 1. 2021 pavement evaluation results.

Branch	Section	Surface Type	Section Area (sf)	LCD	2021 PCI	% Distress Due to Load	% Distress Due to Climate/Durability	% Distress Due to Other	Type of Distress
A01JE	01	PCC	90,913	6/1/2001	78	54	5	41	ASR, Corner Break, Corner Spalling, Faulting, Joint Spalling, Joint Seal Damage, Large Patch, LTD Cracking, Shattered Slab, Shrinkage Cracking, Small Patch
A01JE	02	PCC	37,530	12/2/2005	86	5	83	12	Corner Break, Faulting, Joint Seal Damage
A01JE	03	PCC	23,296	1/1/1994	73	96	0	4	Corner Break, Corner Spalling, LTD Cracking, Shattered Slab, Shrinkage Cracking
A02JE	01	PCC	20,178	6/1/2001	83	83	0	17	Corner Break, Corner Spalling, Joint Spalling, LTD Cracking, Shrinkage Cracking, Small Patch
A02JE	02	PCC	4,524	7/28/2010	90	19	0	81	Faulting, LTD Cracking
R14JE	01	PCC	222,373	6/3/2001	78	39	46	15	Faulting, Joint Seal Damage, LTD Cracking, Shrinkage Cracking
R14JE	02	PCC	16,783	6/3/2001	81	29	57	14	Corner Break, Corner Spalling, Faulting, Joint Spalling, Joint Seal Damage, LTD Cracking, Shattered Slab
R14JE	03	PCC	17,893	6/3/2001	84	0	70	30	Corner Spalling, Faulting, Joint Spalling, Joint Seal Damage
R14JE	04	PCC	79,507	9/3/2020	100	0	0	0	No Distresses
T01JE	01	PCC	17,845	6/1/2000	89	27	55	18	Corner Break, Faulting, Joint Seal Damage, LTD Cracking
T02JE	01	PCC	9,183	12/2/2005	86	13	83	4	Joint Spalling, Joint Seal Damage, LTD Cracking

Table Notes:

1. See Figure 3 for the location of the branch and section.

Table 1. 2021 pavement evaluation results (continued).

2. Surface Type: AC = asphalt cement concrete; AAC = asphalt overlay on AC; PCC = portland cement concrete; APC = asphalt overlay on PCC.
3. LCD = last construction date.
4. Distress due to load includes distress types that are attributed to a structural deficiency in the pavement, such as alligator cracking or rutting on asphalt-surfaced pavements or shattered slabs on PCC pavements.
5. Distress due to climate or durability includes distress types that are attributed to either the aging of the pavement and the effects of the environment (such as weathering, raveling, or block cracking on asphalt-surfaced pavements) or to a materials-related problem (such as durability cracking or alkali-silica reaction [ASR] on PCC pavements). If materials-related distresses were recorded during the inspection, further laboratory testing is required to definitively determine the type present.
6. Distress due to other refers to distress types that are not attributed to one factor but rather may be caused by a combination of factors.
7. Distress types are defined by ASTM D5340-20. L&T Cracking = Longitudinal and Transverse Cracking; LTD Cracking = Longitudinal, Transverse, and Diagonal Cracking; ASR = Alkali-Silica Reaction.



## Inspection Comments

Jefferson Municipal Airport was inspected on November 16, 2021. There were eleven pavement sections defined during the inspection.

### *Runway*

Runway 14/32 consisted of four sections. Section 01 contained low- and medium-severity faulting and longitudinal, transverse and diagonal (LTD) cracking; medium- and high-severity joint seal damage; and shrinkage cracking. Areas of low-severity corner break, faulting, and shattered slab; medium-severity corner spalling; all severities of joint seal damage; and low- and medium-severity joint spalling and LTD cracking were recorded in Section 02. Section 03 had low-severity corner spalling and faulting, medium- and high-severity joint seal damage, and all severities of joint spalling. Section 04 was in excellent condition with no distress recorded at the time of inspection.

### *Taxiways*

Taxiway 01 connected Runway 14/32 to the apron area and was defined by one section. Medium-severity corner break and joint seal damage and low-severity faulting and LTD cracking were identified in Section 01.

Taxiway 02 connected Apron 01 with Apron 02 and contained one section. Areas of high-severity joint seal damage and low-severity joint spalling and LTD cracking were noted in Section 01.

### *Aprons*

Apron 01 consisted of three sections. Section 01 contained low-severity corner break, LTD cracking, joint seal damage, small patching, large patching, and shattered slab; low- and medium-severity corner spalling and faulting; all severities of joint spalling; and shrinkage cracking. An atypical area with low- and medium-severity alkali-silica reaction (ASR) was inspected as an additional sample unit, according to ASTM D5340-20. The suspected ASR was recorded in accordance with ASTM D5340-20. It should be noted that laboratory testing in the form of petrographic analysis is the only definitive way to validate the presence of ASR; however, the formation of a precipitate is evidence of a reaction consistent with this type of materials-related distress. Low-severity corner break and faulting and high-severity joint seal damage were observed in Section 02. Section 03 had areas of shrinkage cracking and low-severity corner break, corner spalling, LTD cracking, and shattered slab recorded during the inspection.

Apron 02 was defined by two sections. Section 01 contained medium-severity corner break and small patching, low-severity corner spalling, low- and medium-severity joint spalling and LTD cracking, and shrinkage cracking. Low- and medium-severity faulting and low-severity LTD cracking were noted in Section 02.

## PAVEMENT MAINTENANCE AND REHABILITATION PROGRAM

Using the information collected during the pavement inspection, the PAVER pavement management software was used to develop a 5-year M&R program for Jefferson Municipal Airport. In addition, a 1-year plan for localized preventive maintenance (such as crack sealing and patching) was prepared.

### Analysis Parameters

#### *Critical PCIs*

PAVER uses critical PCIs to determine whether localized preventive maintenance or major rehabilitation is the appropriate repair action. Above the critical PCI, localized preventive maintenance activities are recommended. Below the critical PCI, major rehabilitation actions, such as an overlay or reconstruction, are recommended. The Iowa DOT set the critical PCIs at 65 for runways, 60 for taxiways, and 55 for aprons.

#### *Localized Preventive Maintenance Policies and Unit Costs*

Localized preventive maintenance policies were developed for asphalt-surfaced and PCC pavements. These policies, shown in Appendix E, identify the localized preventive maintenance actions that the Iowa DOT considered appropriate to correct for the different distress types and severities. The Iowa DOT provided unit costs for each of the localized preventive maintenance actions included in these policies, and these costs are detailed in Appendix E. Please note that this information is of a general nature for the entire state. The localized preventive maintenance policies and unit costs may require adjustment to reflect specific conditions at Jefferson Municipal Airport.

#### *Major Rehabilitation Unit Costs*

PAVER estimates the cost of major rehabilitation based on the predicted PCI of the pavement section. The Iowa DOT provided the costs for major rehabilitation, and they are presented in Appendix E. If major rehabilitation is recommended in the 5-year program, further engineering investigation will be needed to identify the most appropriate rehabilitation action and to estimate the cost of such work more accurately.

#### *Budget and Inflation Rate*

An unlimited budget with a start date of July 1, 2022 and an inflation rate of 4.0 percent was used during the analysis.

### Analysis Approach

The 5-year M&R program was prepared with the goal of maintaining the pavements above established critical PCIs. During this analysis, major rehabilitation was recommended for pavements in the year they dropped below their critical PCI. For the first year (2022) of the analysis only, a localized preventive maintenance plan was developed for those pavement sections that were above their critical PCI. If major rehabilitation was triggered for a section in 2023 or 2024, then localized preventive maintenance was not recommended for 2022. While localized preventive maintenance should be an annual undertaking at Jefferson Municipal Airport, it is not possible to accurately predict the propagation of cracking and other distress types. Therefore, the airport should budget for maintenance every year and can use the 2022

localized preventive maintenance plan as a baseline for that work. As the pavements age, it can be assumed that the amount of localized preventive maintenance required will increase.

## Analysis Results

A summary of the M&R program for Jefferson Municipal Airport is presented in Table 2. Detailed information on the recommended localized preventive maintenance plan for 2022 is provided in Appendix F.

Table 2. 5-year M&R program under an unlimited funding analysis scenario.

Year	Branch	Section	Surface Type	Type of Repair	Estimated Cost
2022	A01JE	01	PCC	Preventive Maintenance	\$7,101
2022	A01JE	02	PCC	Preventive Maintenance	\$16,524
2022	A01JE	03	PCC	Major Rehabilitation	\$191,538
2022	A02JE	01	PCC	Preventive Maintenance	\$1,362
2022	A02JE	02	PCC	Preventive Maintenance	\$4
2022	R14JE	01	PCC	Preventive Maintenance	\$98,180
2022	R14JE	02	PCC	Preventive Maintenance	\$5,194
2022	R14JE	03	PCC	Preventive Maintenance	\$7,362
2022	T01JE	01	PCC	Preventive Maintenance	\$8,394
2022	T02JE	01	PCC	Preventive Maintenance	\$3,158

**Total Estimated Cost: \$339,000**

### Table Notes:

1. See Figure 3 for the location of the branch and section.
2. Surface Type: AC = asphalt cement concrete; AAC = asphalt overlay on AC; PCC = portland cement concrete; APC = asphalt overlay on PCC.
3. Type of Repair: Major Rehabilitation such as pavement reconstruction or an overlay; Localized Preventive Maintenance such as crack sealing or patching.
4. The estimated costs provided are of a general nature for the entire state and may require adjustment to reflect specific conditions at Jefferson Municipal Airport.

The recommendations made in this report are based on a broad network-level analysis and meant to provide Jefferson Municipal Airport with an indication of the type of pavement-related work required during the next 5 years. Further engineering investigation may be necessary to identify which repair action is most appropriate. In addition, the cost estimates provided are based on overall unit costs for the entire state, and Jefferson Municipal Airport should adjust the plan to reflect local costs.

Because an unlimited budget was used in the analysis, it is possible that the pavement repair program may need to be adjusted to consider economic or operational constraints. The identification of a project need does not necessarily mean that state or federal funding will be available in the year it is indicated. It is important to remember that regardless of the recommendations presented within this report, Jefferson Municipal Airport is responsible for repairing pavements where existing conditions pose a hazard to safe operations.

## General Maintenance Recommendations

In addition to the specific maintenance actions presented in Appendix F, it is recommended that the following strategies be considered for prolonging pavement life:

1. Regularly inspect all safety areas of the airport and document all inspection activity. A sample form that can be used to perform these inspections is provided in Table 3 of this report.
2. Provide a method of tracking all maintenance activities that occur as a result of inspections. These need to be reported to the FAA and the Iowa DOT. This information is used to update the APMS records and is required to remain in compliance with Public Law 103-305 (see the next section of this report for further information on this law).
3. Conduct an aggressive campaign against weed growth through timely herbicide applications and mowing programs of the safety areas. Vegetation growth in pavement cracks is destructive and significantly increases the rate of pavement deterioration.
4. Implement a periodic crack and joint sealing program. Keeping water and debris out of the pavement system by sealing cracks and joints is a proven and cost-effective method of extending the life of the pavement system.
5. Ensure that dirt does not build up along the edges of the pavements. This can create a “bathtub” effect, reducing the ability of water to drain away from the pavement system.
6. Closely monitor the movement of heavy equipment (particularly farming, construction, and fueling equipment) to make sure it is only operating on pavements that are designed to accommodate heavy loads. Failure to restrict heavy equipment to appropriate areas may result in the premature failure of airport pavements.

## FAA Requirements (Public Law 103-305)

Because Jefferson Municipal Airport is in the National Plan of Integrated Airport Systems (NPIAS), the airport sponsor is required to keep the airport in a viable operating condition. This includes maintaining airport pavements in accordance with Public Law 103-305. Public Law 103-305 states that after January 1, 1995, NPIAS airport sponsors must provide assurances or certifications that an airport has implemented an effective airport pavement maintenance management system (PMMS) before the airport will be considered for federal funding of pavement replacement or reconstruction projects. To be in full compliance with the federal law, the PMMS must include the following components at minimum: pavement inventory, pavement inspections, record keeping, information retrieval, and program funding.

This report serves as a complete pavement inventory and detailed inspection. To remain in compliance with the law, Jefferson Municipal Airport will also need to undertake monthly drive-by inspections of pavement conditions and track pavement-related maintenance activities.

FAA Advisory Circular 150/5380-7B provides detailed guidance pertaining to the requirements for an acceptable pavement management program (PMP). Appendix A of the FAA Advisory Circular 150/5380-7B outlines what needs to be included in a PMP to remain in compliance with this law and Grant Assurance #11. The following is a copy of this Appendix, along with instructions for supplementing this report so that all requirements are met. Note that the italicized words are direct quotations from the FAA Advisory Circular.

**FAA Advisory Circular 150/5830-7B, Appendix A. Pavement Management Program (PMP)**

**A-1.0.** *An effective PMP specifies the procedures to follow to assure that proper preventative and remedial pavement maintenance is performed. The program should identify funding or anticipated funding and other resources available to provide remedial and preventive maintenance activities. An airport sponsor may use any format deemed appropriate, but the program needs to, as a minimum, include the following:*

**A-1.1. Pavement Inventory.** *The following must be depicted:*

- a. *Identification of all runways, taxiways, and aprons with pavement broken down into sections each having similar properties.*

The network definition map provided in Figure 3 of this report shows the location of all runways, taxiways, and aprons at Jefferson Municipal Airport. If any new pavements are constructed or any pavement areas are permanently closed, this map must be updated. Project plans should be submitted to the Iowa DOT after project completion.

- b. *Dimensions of pavement sections.*

The dimensions of all runways, taxiways, and aprons are stored in the PAVER database. Appendix C provides information on length, width, and area. In addition, the network definition map (Figure 3) is drawn to scale. Any changes to pavement dimensions must be recorded.

- c. *Type of pavement surface.*

The type of pavement for each section at Jefferson Municipal Airport is listed in Table 1 of this report and is also stored in the PAVER database. Any changes to pavement type (through an overlay or reconstruction) must be recorded.

- d. *Year of construction and/or most recent major rehabilitation.*

Dates for pavement construction, rehabilitation, or reconstruction must be recorded. The current pavement history for Jefferson Municipal Airport is provided in Appendix D of this report.

- e. *Whether AIP [Airport Improvement Program] or PFC [Passenger Facility Charge] funds were used to construct, reconstruct, or repair the pavement.*

Funding sources for all pavement projects should be recorded.

**A-1.2. PMP Pavement Inspection Schedule.** *Airports must perform a detailed inspection of airfield pavements at least once a year for the PMP. If a pavement condition index (PCI) survey is performed, as set forth in ASTM D5340, Standard Test Method for Airport Pavement Condition Index Surveys, the frequency of the detailed inspection by PCI surveys may be extended to three years. Less comprehensive routine daily, weekly, and monthly maintenance inspections required for operations should be addressed.*

This report consists of a detailed inspection that will extend the inspection period to 3 years. It is the airport sponsor's responsibility to perform monthly drive-by inspections. A sample pavement inspection report form is provided in Table 3 of this report.

**A-1.3. Record Keeping.** *The airport must record and keep on file complete information about all detailed inspections and maintenance performed until the pavement system is replaced. The types of distress, their locations, and remedial action, scheduled or performed, must be documented. The minimum information recorded includes:*

- a. *Inspection date*
- b. *Location*
- c. *Distress types*
- d. *Maintenance scheduled or performed*

Items a through c are satisfied by this inspection report. Item d is the responsibility of the airport, as is record keeping of the monthly drive-by inspections.

**A-1.4. Information Retrieval.** *An airport sponsor may use any form of record keeping it deems appropriate so long as the information and records from the pavement survey can generate required reports, as necessary.*

Keep this report, monthly drive-by inspection reports, construction updates, and all records of maintenance activities in a readily accessible location so that they can be easily retrieved as requested by the FAA.

Table 3. Pavement inspection report.

Inspected By: \_\_\_\_\_

Date Inspected: \_\_\_\_\_

<b>Branch</b>	<b>Section</b>	<b>Distress Description/Dimensions/Severity/ Recommended Action</b>	<b>Description of Repair</b>	<b>Date Performed</b>	<b>Cost</b>	<b>Funding Source</b>
A01JE	01					
A01JE	02					
A01JE	03					
A02JE	01					
A02JE	02					
R14JE	01					

Table 3. Pavement inspection report (continued).

Inspected By: \_\_\_\_\_

Date Inspected: \_\_\_\_\_

Branch	Section	Distress Description/Dimensions/Severity/ Recommended Action	Description of Repair	Date Performed	Cost	Funding Source
R14JE	02					
R14JE	03					
R14JE	04					
T01JE	01					
T02JE	01					

Table Notes:

1. See Figure 3 for the location of the branch and section.



---

## SUMMARY

This report documents the results of the pavement evaluation conducted at Jefferson Municipal Airport. A visual inspection of the pavements in 2021 found that the overall condition of the pavement network is a PCI of 83. A 5-year pavement repair program, shown in Table 2, was generated for Jefferson Municipal Airport, which revealed that approximately \$339,000 needs to be expended on M&R. Jefferson Municipal Airport should utilize these study results to assist in planning for future maintenance needs as part of the airport CIP planning process.

## **APPENDIX A**

### **CAUSE OF DISTRESS TABLES**

Table A-1. Cause of pavement distress, asphalt-surfaced pavements.

<b>Distress Type</b>	<b>Probable Cause of Distress</b>
Alligator Cracking	Fatigue failure of the asphalt surface under repeated traffic loading.
Bleeding	Excessive amounts of asphalt cement or tars in the mix or low air void content, or both.
Block Cracking	Shrinkage of the asphalt and daily temperature cycling; it is not load associated.
Corrugation	Traffic action combined with an unstable pavement layer.
Depression	Settlement of the foundation soil or can be “built up” during construction.
Jet-Blast Erosion	Bituminous binder has been burned or carbonized.
Joint Reflection Cracking	Movement of the concrete slab beneath the asphalt surface due to thermal and moisture changes.
L&T Cracking	Cracks may be caused by (1) a poorly constructed paving lane joint, (2) shrinkage of the asphalt surface due to low temperatures or hardening of the asphalt, or (3) reflective cracking caused by cracks in an underlying PCC slab.
Oil Spillage	Deterioration or softening of the pavement surface caused by the spilling of oil, fuel, or other solvents.
Patching	N/A
Polished Aggregate	Repeated traffic applications.
Raveling	Asphalt binder may have hardened significantly, causing coarse aggregate pieces to dislodge.
Rutting	Usually caused by consolidation or lateral movement of the materials due to traffic loads.
Shoving	Where PCC pavements adjoin flexible pavements, PCC “growth” may shove the asphalt pavement.
Slippage Cracking	Low strength surface mix or poor bond between the surface and the next layer of the pavement structure.
Swelling	Usually caused by frost action or by swelling soil.
Weathering	Asphalt binder and/or fine aggregate may wear away as the pavement ages and hardens.

Table A-2. Cause of pavement distress, PCC pavements.

<b>Distress Type</b>	<b>Probable Cause of Distress</b>
ASR	Chemical reaction of alkalis in the portland cement with certain reactive silica minerals. ASR may be accelerated by the use of chemical pavement deicers.
Blowup	Incompressible materials in the joints.
Corner Break	Load repetition combined with loss of support and curling stresses.
Durability Cracking	Concrete's inability to withstand environmental factors such as freeze-thaw cycles.
Faulting	Upheaval or consolidation.
Joint Seal Damage	Stripping of joint sealant, extrusion of joint sealant, weed growth, hardening of the filler (oxidation), loss of bond to the slab edges, or absence of sealant in the joint.
LTD Cracking	Combination of load repetition, curling stresses, and shrinkage stresses.
Patching (Small and Large)	N/A
Popouts	Freeze-thaw action in combination with expansive aggregates.
Pumping	Poor drainage, poor joint sealant.
Scaling	Over finishing of concrete, deicing salts, improper construction, freeze-thaw cycles, and poor aggregate.
Shattered Slab	Load repetition.
Shrinkage Cracking	Setting and curing of the concrete.
Spalling (Joint and Corner)	Excessive stresses at the joint caused by infiltration of incompressible materials or traffic loads; weak concrete at the joint combined with traffic loads.

## **APPENDIX B**

### **INSPECTION PHOTOGRAPHS**

A01JE-01. Overview.



A01JE-01. ASR (Additional Sample Unit No. 12).





A01JE-01. Joint Spalling (Additional Sample Unit No. 12).



A01JE-01. Joint Spalling (Additional Sample Unit No. 18).





A01JE-01. Joint Spalling (Sample Unit No. 13).



A01JE-02. Overview.





A01JE-02. Joint Seal Damage (Sample Unit No. 04).



A01JE-03. Overview.



A01JE-03. Shattered Slab (Sample Unit No. 04).



A02JE-01. Overview.





A02JE-01. LTD Cracking (Sample Unit No. 06).



A02JE-02. Overview.



A02JE-02. Faulting (Sample Unit No. 02).




R14JE-01. Overview.





R14JE-01. LTD Cracking (Sample Unit No. 05).



R14JE-01. LTD Cracking (Sample Unit No. 15).





R14JE-02. Overview.



R14JE-02. Joint Spalling (Sample Unit No. 01).





R14JE-02. Shattered Slab (Sample Unit No. 05).



R14JE-03. Overview.





R14JE-03. Joint Spalling (Sample Unit No. 04).



R14JE-04. Overview (1).





R14JE-04. Overview (2).



R14JE-04. Overview (3).



T01JE-01. Overview.



T01JE-01. LTD Cracking (Sample Unit No. 05).






T02JE-01. Overview.



T02JE-01. Joint Seal Damage (Sample Unit No. 01).



## **APPENDIX C**

### **INSPECTION REPORT**

# RE-INSPECTION REPORT JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 1

## Branch - Section ID: A01JE - 01

Branch Name: APRON 01

Use: APRON

LCD: 6/1/2001

PCI Family: IowaPCCAPNC\_BasicLocal

Surface Type: PCC

Rank: P

Section Area (sf): 90,913.00

Length (ft): 583.00

Width (ft): 183.00

From: HANGERS

To: TAXIWAY 01

Slabs: 582

Section Comments:

Slab Length (ft): 12.50

Slab Width (ft): 12.50

Joint Length (ft): 13,893.35

Last Insp Date: 11/16/2021

Inspection Comments:

PCI: 78

Total Samples: 30

Surveyed: 10

### Sample Number: 02

Sample Type: R

Sample Comments:

Sample PCI: 69

Sample Area (Slabs): 26

63 LINEAR CR	L	12 Slabs
66 SMALL PATCH	L	1 Slabs
72 SHAT. SLAB	L	2 Slabs
75 CORNER SPALL	M	1 Slabs

### Sample Number: 07

Sample Type: R

Sample Comments:

Sample PCI: 70

Sample Area (Slabs): 24

62 CORNER BREAK	L	1 Slabs
63 LINEAR CR	L	7 Slabs
66 SMALL PATCH	L	1 Slabs
67 LARGE PATCH	L	1 Slabs
72 SHAT. SLAB	L	1 Slabs
75 CORNER SPALL	L	1 Slabs

### Sample Number: 12

Sample Type: A

Sample Comments:

Sample PCI: 56

Sample Area (Slabs): 19

63 LINEAR CR	L	1 Slabs
73 SHRINKAGE CR	N	1 Slabs
74 JOINT SPALL	H	2 Slabs
74 JOINT SPALL	M	3 Slabs
76 ASR	L	1 Slabs
76 ASR	M	1 Slabs

# RE-INSPECTION REPORT

## JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 2

### Sample Number: 13

Sample Type: R	Sample Comments:
Sample PCI: 86	
Sample Area (Slabs): 21	
71 FAULTING	L 2 Slabs
74 JOINT SPALL	M 1 Slabs
75 CORNER SPALL	L 1 Slabs

### Sample Number: 15

Sample Type: R	Sample Comments:
Sample PCI: 93	
Sample Area (Slabs): 21	
65 JT SEAL DMG	L 21 Slabs
74 JOINT SPALL	L 2 Slabs
75 CORNER SPALL	L 1 Slabs

### Sample Number: 17

Sample Type: R	Sample Comments:
Sample PCI: 100	
Sample Area (Slabs): 14	
NO DISTRESS	

### Sample Number: 18

Sample Type: A	Sample Comments:
Sample PCI: 66	
Sample Area (Slabs): 21	
62 CORNER BREAK	L 1 Slabs
72 SHAT. SLAB	L 1 Slabs
73 SHRINKAGE CR	N 1 Slabs
74 JOINT SPALL	H 2 Slabs
74 JOINT SPALL	L 1 Slabs
75 CORNER SPALL	L 1 Slabs

### Sample Number: 20

Sample Type: R	Sample Comments:
Sample PCI: 70	
Sample Area (Slabs): 26	
62 CORNER BREAK	L 1 Slabs
63 LINEAR CR	L 9 Slabs
72 SHAT. SLAB	L 2 Slabs
74 JOINT SPALL	L 1 Slabs

### Sample Number: 25

Sample Type: R	Sample Comments:
Sample PCI: 72	
Sample Area (Slabs): 20	
63 LINEAR CR	L 7 Slabs
71 FAULTING	L 1 Slabs
71 FAULTING	M 1 Slabs

# RE-INSPECTION REPORT

## JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 3

### Sample Number: 29

Sample Type: R

Sample Comments:

Sample PCI: 83

Sample Area (Slabs): 20

63 LINEAR CR

L

3 Slabs

74 JOINT SPALL

L

2 Slabs

75 CORNER SPALL

L

1 Slabs

# RE-INSPECTION REPORT

## JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 4

### Branch - Section ID: A01JE - 02

Branch Name: APRON 01

Use: APRON

LCD: 12/2/2005

PCI Family: IowaPCCAPNC\_BasicLocal

Surface Type: PCC

Rank: P

Section Area (sf): 37,530.00

Length (ft): 200.00

Width (ft): 185.00

From: A01JE-01

To: T02JE-01

Slabs: 227

Section Comments:

Slab Length (ft): 12.50

Slab Width (ft): 13.20

Joint Length (ft): 5,455.07

Last Insp Date: 11/16/2021

Inspection Comments:

PCI: 86

Total Samples: 12

Surveyed: 6

#### Sample Number: 001

Sample Type: R

Sample Comments:

Sample PCI: 88

Sample Area (Slabs): 20

65 JT SEAL DMG

H

20 Slabs

#### Sample Number: 004

Sample Type: R

Sample Comments:

Sample PCI: 88

Sample Area (Slabs): 16

65 JT SEAL DMG

H

16 Slabs SEED

#### Sample Number: 005

Sample Type: R

Sample Comments:

Sample PCI: 88

Sample Area (Slabs): 20

65 JT SEAL DMG

H

20 Slabs

#### Sample Number: 008

Sample Type: R

Sample Comments:

Sample PCI: 83

Sample Area (Slabs): 20

65 JT SEAL DMG

H

20 Slabs

71 FAULTING

L

2 Slabs

#### Sample Number: 010

Sample Type: R

Sample Comments:

Sample PCI: 88

Sample Area (Slabs): 16

65 JT SEAL DMG

H

16 Slabs

#### Sample Number: 012

Sample Type: R

Sample Comments:

Sample PCI: 84

Sample Area (Slabs): 22

62 CORNER BREAK

L

1 Slabs

65 JT SEAL DMG

H

22 Slabs





# RE-INSPECTION REPORT JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 6

## Sample Number: 008

Sample Type: R

Sample Comments:

Sample PCI: 57

Sample Area (Slabs): 12

62 CORNER BREAK

L

1 Slabs

63 LINEAR CR

L

2 Slabs

72 SHAT. SLAB

L

3 Slabs

75 CORNER SPALL

L

1 Slabs

# RE-INSPECTION REPORT

## JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 7

### Branch - Section ID: A02JE - 01

Branch Name: APRON 02

Use: APRON

LCD: 6/1/2001

PCI Family: IowaPCCAPNC\_BasicLocal

Surface Type: PCC

Rank: P

Section Area (sf): 20,178.00

Length (ft): 530.00

Width (ft): 25.00

From: HANGER

To: TAXIWAY 01

Slabs: 161

Section Comments:

Slab Length (ft): 12.50

Slab Width (ft): 10.00

Joint Length (ft): 2,786.85

Last Insp Date: 11/16/2021

Inspection Comments:

PCI: 83

Total Samples: 8

Surveyed: 5

#### Sample Number: 02

Sample Type: R

Sample Comments:

Sample PCI: 94

Sample Area (Slabs): 18

74 JOINT SPALL

L

1 Slabs

74 JOINT SPALL

M

1 Slabs

#### Sample Number: 03

Sample Type: R

Sample Comments:

Sample PCI: 97

Sample Area (Slabs): 18

74 JOINT SPALL

L

2 Slabs

#### Sample Number: 05

Sample Type: R

Sample Comments:

Sample PCI: 80

Sample Area (Slabs): 18

63 LINEAR CR

L

3 Slabs

66 SMALL PATCH

M

1 Slabs

73 SHRINKAGE CR

N

1 Slabs

74 JOINT SPALL

L

2 Slabs

#### Sample Number: 06

Sample Type: R

Sample Comments:

Sample PCI: 80

Sample Area (Slabs): 22

63 LINEAR CR

L

11 Slabs

#### Sample Number: 07

Sample Type: R

Sample Comments:

Sample PCI: 70

Sample Area (Slabs): 26

62 CORNER BREAK

M

1 Slabs

63 LINEAR CR

L

9 Slabs

63 LINEAR CR

M

1 Slabs

75 CORNER SPALL

L

1 Slabs

# RE-INSPECTION REPORT

## JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 8

### Branch - Section ID: A02JE - 02

Branch Name: APRON 02

Use: APRON

LCD: 7/28/2010

PCI Family: IowaPCCAPNC\_BasicLocal

Surface Type: PCC

Rank: P

Section Area (sf): 4,524.00

Length (ft): 107.00

Width (ft): 40.00

From: SEE MAP

To: SEE MAP

Slabs: 40

Section Comments: avg slab length

Slab Length (ft): 11.20

Slab Width (ft): 10.00

Joint Length (ft): 700.95

Last Insp Date: 11/16/2021

Inspection Comments:

PCI: 90

Total Samples: 2

Surveyed: 2

#### Sample Number: 01

Sample Type: R

Sample Comments:

Sample PCI: 96

Sample Area (Slabs): 24

63 LINEAR CR

L

1 Slabs

#### Sample Number: 02

Sample Type: R

Sample Comments:

Sample PCI: 81

Sample Area (Slabs): 16

71 FAULTING

L

3 Slabs

71 FAULTING

M

1 Slabs

# RE-INSPECTION REPORT JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 9

## Branch - Section ID: R14JE - 01

Branch Name: RUNWAY 14/32

Use: RUNWAY

LCD: 6/3/2001

PCI Family: IowaPCCRWNC\_BasicLocal

Surface Type: PCC

Rank: P

Section Area (sf): 222,373.00

Length (ft): 3,005.00

Width (ft): 75.00

From: RUNWAY END 14

To: RUNWAY END 32

Slabs: 1,348

Section Comments:

Slab Length (ft): 13.20

Slab Width (ft): 12.50

Joint Length (ft): 31,597.31

Last Insp Date: 11/16/2021

Inspection Comments:

PCI: 78

Total Samples: 58

Surveyed: 8

### Sample Number: 005

Sample Type: R

Sample Comments:

Sample PCI: 83

Sample Area (Slabs): 24

63 LINEAR CR

L

2 Slabs

65 JT SEAL DMG

H

24 Slabs

### Sample Number: 011

Sample Type: R

Sample Comments:

Sample PCI: 64

Sample Area (Slabs): 24

63 LINEAR CR

M

4 Slabs

65 JT SEAL DMG

H

24 Slabs

71 FAULTING

L

3 Slabs

### Sample Number: 015

Sample Type: R

Sample Comments:

Sample PCI: 60

Sample Area (Slabs): 24

63 LINEAR CR

L

1 Slabs

63 LINEAR CR

M

4 Slabs

65 JT SEAL DMG

H

24 Slabs

71 FAULTING

L

2 Slabs

73 SHRINKAGE CR

N

1 Slabs

### Sample Number: 019

Sample Type: R

Sample Comments:

Sample PCI: 67

Sample Area (Slabs): 24

63 LINEAR CR

L

3 Slabs

63 LINEAR CR

M

1 Slabs

65 JT SEAL DMG

H

24 Slabs

71 FAULTING

L

3 Slabs

71 FAULTING

M

1 Slabs

# RE-INSPECTION REPORT

## JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 10

---

### Sample Number: 025

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 24

65 JT SEAL DMG

M

24 Slabs

---

### Sample Number: 035

Sample Type: R

Sample Comments:

Sample PCI: 77

Sample Area (Slabs): 24

63 LINEAR CR

L

3 Slabs

63 LINEAR CR

M

1 Slabs

65 JT SEAL DMG

H

24 Slabs

---

### Sample Number: 044

Sample Type: R

Sample Comments:

Sample PCI: 88

Sample Area (Slabs): 24

65 JT SEAL DMG

H

24 Slabs

---

### Sample Number: 053

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 24

65 JT SEAL DMG

M

24 Slabs

# RE-INSPECTION REPORT JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 11

## Branch - Section ID: R14JE - 02

Branch Name: RUNWAY 14/32

Use: RUNWAY

LCD: 6/3/2001

PCI Family: IowaPCCRWNC\_BasicLocal

Surface Type: PCC

Rank: P

Section Area (sf): 16,783.00

Length (ft): 295.00

Width (ft): 35.00

From: R14JE-01

To: ..

Slabs: 104

Section Comments:

Slab Length (ft): 13.80

Slab Width (ft): 11.66

Joint Length (ft): 2,119.12

Last Insp Date: 11/16/2021

Inspection Comments:

PCI: 81

Total Samples: 5

Surveyed: 4

### Sample Number: 001

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 25

65 JT SEAL DMG	L	25 Slabs
74 JOINT SPALL	L	1 Slabs
75 CORNER SPALL	M	1 Slabs

### Sample Number: 002

Sample Type: R

Sample Comments:

Sample PCI: 86

Sample Area (Slabs): 24

63 LINEAR CR	L	1 Slabs
65 JT SEAL DMG	M	24 Slabs
74 JOINT SPALL	L	2 Slabs

### Sample Number: 004

Sample Type: R

Sample Comments:

Sample PCI: 73

Sample Area (Slabs): 18

62 CORNER BREAK	L	1 Slabs
63 LINEAR CR	L	2 Slabs
65 JT SEAL DMG	H	18 Slabs
71 FAULTING	L	1 Slabs

### Sample Number: 005

Sample Type: R

Sample Comments:

Sample PCI: 67

Sample Area (Slabs): 24

63 LINEAR CR	L	1 Slabs
63 LINEAR CR	M	1 Slabs
65 JT SEAL DMG	H	24 Slabs
71 FAULTING	L	1 Slabs
72 SHAT. SLAB	L	1 Slabs
74 JOINT SPALL	M	1 Slabs



# RE-INSPECTION REPORT JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 12

## Branch - Section ID: R14JE - 03

Branch Name: RUNWAY 14/32

Use: RUNWAY

LCD: 6/3/2001

PCI Family: IowaPCCRWNC\_BasicLocal

Surface Type: PCC

Rank: P

Section Area (sf): 17,893.00

Length (ft): 295.00

Width (ft): 35.00

From: R14JE-01

To: ..

Slabs: 109

Section Comments:

Slab Length (ft): 13.80

Slab Width (ft): 11.90

Joint Length (ft): 2,228.32

Last Insp Date: 11/16/2021

Inspection Comments:

PCI: 84

Total Samples: 5

Surveyed: 4

### Sample Number: 001

Sample Type: R

Sample Comments:

Sample PCI: 88

Sample Area (Slabs): 24

65 JT SEAL DMG

H

24 Slabs

### Sample Number: 002

Sample Type: R

Sample Comments:

Sample PCI: 93

Sample Area (Slabs): 24

65 JT SEAL DMG

M

24 Slabs

### Sample Number: 004

Sample Type: R

Sample Comments:

Sample PCI: 76

Sample Area (Slabs): 21

65 JT SEAL DMG

H

21 Slabs

71 FAULTING

L

2 Slabs

74 JOINT SPALL

L

2 Slabs

74 JOINT SPALL

M

1 Slabs

### Sample Number: 005

Sample Type: R

Sample Comments:

Sample PCI: 77

Sample Area (Slabs): 25

65 JT SEAL DMG

H

25 Slabs

71 FAULTING

L

1 Slabs

74 JOINT SPALL

H

1 Slabs

75 CORNER SPALL

L

1 Slabs

# RE-INSPECTION REPORT

## JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 13

### Branch - Section ID: R14JE - 04

Branch Name: RUNWAY 14/32

Use: RUNWAY

LCD: 9/3/2020

PCI Family: IowaPCCRWNC\_BasicLocal

Surface Type: PCC

Rank: P

Section Area (sf): 79,507.00

Length (ft): 1,065.00

Width (ft): 75.00

From: SEE MAP

To: SEE MAP

Slabs: 578

Section Comments:

Slab Length (ft): 11.00

Slab Width (ft): 12.50

Joint Length (ft): 12,453.72

Last Insp Date: 11/16/2021

Inspection Comments:

PCI: 100

Total Samples: 29

Surveyed: 8

#### Sample Number: 01

Sample Type: R

Sample Comments:

Sample PCI: 100

Sample Area (Slabs): 24

NO DISTRESS

#### Sample Number: 04

Sample Type: R

Sample Comments:

Sample PCI: 100

Sample Area (Slabs): 24

NO DISTRESS

#### Sample Number: 07

Sample Type: R

Sample Comments:

Sample PCI: 100

Sample Area (Slabs): 24

NO DISTRESS

#### Sample Number: 10

Sample Type: R

Sample Comments:

Sample PCI: 100

Sample Area (Slabs): 24

NO DISTRESS

#### Sample Number: 13

Sample Type: R

Sample Comments:

Sample PCI: 100

Sample Area (Slabs): 24

NO DISTRESS

#### Sample Number: 16

Sample Type: R

Sample Comments:

Sample PCI: 100

Sample Area (Slabs): 24

NO DISTRESS

# RE-INSPECTION REPORT

## JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 14

---

### Sample Number: 19

Sample Type: R  
Sample PCI: 100  
Sample Area (Slabs): 27  
NO DISTRESS

Sample Comments:

---

### Sample Number: 26

Sample Type: R  
Sample PCI: 100  
Sample Area (Slabs): 24  
NO DISTRESS

Sample Comments:

# RE-INSPECTION REPORT JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 15

## Branch - Section ID: T01JE - 01

Branch Name: TAXIWAY 01

Use: TAXIWAY

LCD: 6/1/2000 Surface Type: PCC Rank: P Section Area (sf): 17,845.00 Length (ft): 455.00 Width (ft): 35.00 From: APRON 01 To: RUNWAY 14/32 Slabs: 131 Slab Length (ft): 11.70 Slab Width (ft): 11.66 Joint Length (ft): 2,506.58 Last Insp Date: 11/16/2021 PCI: 89 Total Samples: 7 Surveyed: 4	PCI Family: IowaPCCTWNC_Basic           Section Comments:           Inspection Comments:
---	--

### Sample Number: 001

Sample Type: R Sample PCI: 93 Sample Area (Slabs): 21 65 JT SEAL DMG	Sample Comments:    M <span style="float: right;">21 Slabs</span>
---	---

### Sample Number: 002

Sample Type: R Sample PCI: 87 Sample Area (Slabs): 21 65 JT SEAL DMG 71 FAULTING	Sample Comments:    M <span style="float: right;">21 Slabs</span> L <span style="float: right;">2 Slabs</span>
--	---

### Sample Number: 004

Sample Type: R Sample PCI: 93 Sample Area (Slabs): 21 65 JT SEAL DMG	Sample Comments:    M <span style="float: right;">21 Slabs</span>
---	---

### Sample Number: 005

Sample Type: R Sample PCI: 83 Sample Area (Slabs): 23 62 CORNER BREAK 63 LINEAR CR 65 JT SEAL DMG	Sample Comments:    M <span style="float: right;">1 Slabs</span> L <span style="float: right;">1 Slabs</span> M <span style="float: right;">23 Slabs</span>
--	---

# RE-INSPECTION REPORT JEFFERSON MUNICIPAL AIRPORT

Pavement Database: IA 2021

Generate Date: 4/27/2022

Network ID: EFW

Page 16

## Branch - Section ID: T02JE - 01

Branch Name: TAXIWAY 02

Use: TAXIWAY

LCD: 12/2/2005	PCI Family: IowaPCCTWNC_Basic
Surface Type: PCC	
Rank: P	
Section Area (sf): 9,183.00	
Length (ft): 300.00	
Width (ft): 26.00	
From: A01JE-02	
To: A02JE-01	
Slabs: 56	Section Comments: avg
Slab Length (ft): 12.70	
Slab Width (ft): 13.00	
Joint Length (ft): 1,045.65	
Last Insp Date: 11/16/2021	Inspection Comments:
PCI: 86	
Total Samples: 3	
Surveyed: 3	

### Sample Number: 001

Sample Type: R	Sample Comments:
Sample PCI: 88	
Sample Area (Slabs): 18	
65 JT SEAL DMG	H <span style="float: right;">18 Slabs</span>

### Sample Number: 002

Sample Type: R	Sample Comments:
Sample PCI: 88	
Sample Area (Slabs): 20	
65 JT SEAL DMG	H <span style="float: right;">20 Slabs</span>

### Sample Number: 003

Sample Type: R	Sample Comments:
Sample PCI: 81	
Sample Area (Slabs): 18	
63 LINEAR CR	L <span style="float: right;">1 Slabs</span>
65 JT SEAL DMG	H <span style="float: right;">18 Slabs</span>
74 JOINT SPALL	L <span style="float: right;">1 Slabs</span>

## **APPENDIX D**

### **WORK HISTORY REPORT**

# Work History

Pavement Database: IA 2021

## Network: JEFFERSON MUNICIPAL AIRPORT

### Branch - Section ID: A01JE - 01

LCD: 6/1/2001  
 Use: APRON  
 Rank: P  
 Surface: PCC

Length (ft): 583.00  
 Width (ft): 183.00  
 True Area (sf): 90,913.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-01-2020	JS-LC	Joint Seal (Localized)	\$0.00	0.00	False	EST
06-01-2001	CR-PC	Complete Reconstruction - PCC	\$0.00	0.00	True	-
06-01-1986	NC-AC	New Construction - AC	\$0.00	0.00	True	-

### Branch - Section ID: A01JE - 02

LCD: 12/2/2005  
 Use: APRON  
 Rank: P  
 Surface: PCC

Length (ft): 200.00  
 Width (ft): 185.00  
 True Area (sf): 37,530.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
12-02-2005	CR-PC	Complete Reconstruction - PCC	\$136,960.00	5.00	True	5" P501; Total Project Cost: \$169,086
12-01-2005	SB-AG	Subbase - Aggregate	\$0.00	6.00	False	6" P154 ASSUMED; COMPACTED GRANULAR S
06-01-1997	NU-IN	New Construction - Initial	\$0.00	0.00	True	-

### Branch - Section ID: A01JE - 03

LCD: 1/1/1994  
 Use: APRON  
 Rank: P  
 Surface: PCC

Length (ft): 330.00  
 Width (ft): 50.00  
 True Area (sf): 23,296.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-01-2020	JS-LC	Joint Seal (Localized)	\$0.00	0.00	False	EST
01-01-1994	NC-PC	New Construction - PCC	\$0.00	0.00	True	EST. VIA GE

### Branch - Section ID: A02JE - 01

LCD: 6/1/2001  
 Use: APRON  
 Rank: P  
 Surface: PCC

Length (ft): 530.00  
 Width (ft): 25.00  
 True Area (sf): 20,178.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-01-2020	JS-LC	Joint Seal (Localized)	\$0.00	0.00	False	EST
06-01-2001	CR-PC	Complete Reconstruction - PCC	\$0.00	0.00	True	-
06-01-1986	NC-AC	New Construction - AC	\$0.00	0.00	True	-



# Work History

## Pavement Database: IA 2021

**Branch - Section ID: A02JE - 02**

LCD: 7/28/2010  
 Use: APRON  
 Rank: P  
 Surface: PCC

Length (ft): 107.00  
 Width (ft): 40.00  
 True Area (sf): 4,524.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-01-2020	JS-LC	Joint Seal (Localized)	\$0.00	0.00	False	EST
07-28-2010	NC-PC	New Construction - PCC	\$0.00	0.00	True	EST. VIA GE

**Branch - Section ID: R14JE - 01**

LCD: 6/3/2001  
 Use: RUNWAY  
 Rank: P  
 Surface: PCC

Length (ft): 3,005.00  
 Width (ft): 75.00  
 True Area (sf): 222,373.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-03-2001	OL-PU	Overlay - PCC Unbonded	\$0.00	6.00	True	6" P501 PCC (IDOT MOD.)
06-01-1986	OL-AC	Overlay - AC	\$0.00	3.00	True	3" P401 AC OVERLAY
06-02-1962	NC-AC	New Construction - AC	\$0.00	2.00	True	2" P401
06-01-1962	BA-AG	Base Course - Aggregate	\$0.00	8.00	False	8" P209

**Branch - Section ID: R14JE - 02**

LCD: 6/3/2001  
 Use: RUNWAY  
 Rank: P  
 Surface: PCC

Length (ft): 295.00  
 Width (ft): 35.00  
 True Area (sf): 16,783.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-03-2001	CR-PC	Complete Reconstruction - PCC	\$0.00	5.00	True	6" P501 (IDOT MOD.)
06-02-2001	BA-AG	Base Course - Aggregate	\$0.00	6.00	False	6" P209 (ASSUMED)
06-02-1962	NC-AC	New Construction - AC	\$0.00	2.00	True	2" P401 AC (ASSUMED MAT. TYPE)
06-01-1962	BA-AG	Base Course - Aggregate	\$0.00	8.00	False	8" P209 CABG

**Branch - Section ID: R14JE - 03**

LCD: 6/3/2001  
 Use: RUNWAY  
 Rank: P  
 Surface: PCC

Length (ft): 295.00  
 Width (ft): 35.00  
 True Area (sf): 17,893.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
09-01-2021	SL-PC	Slab Replacement - PCC	\$0.00	0.00	False	-
06-03-2001	OL-PU	Overlay - PCC Unbonded	\$0.00	6.00	True	6" P501 PCC (IDOT MOD)
06-02-2001	BA-AG	Base Course - Aggregate	\$0.00	6.00	False	6" P209 (ASSUMED MAT.)
06-02-1962	NC-AC	New Construction - AC	\$0.00	2.00	True	2" P401 AC (ASSUMED MAT. TYPE)
06-01-1962	BA-AG	Base Course - Aggregate	\$0.00	8.00	False	8" P209 CABG

# Work History

Pavement Database: IA 2021

**Branch - Section ID: R14JE - 04**

LCD: 9/3/2020  
 Use: RUNWAY  
 Rank: P  
 Surface: PCC

Length (ft): 1,065.00  
 Width (ft): 75.00  
 True Area (sf): 79,507.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
09-03-2020	NU-IN	New Construction - Initial	\$0.00	6.00	True	6" PCC P-501
09-02-2020	BA-AG	Base Course - Aggregate	\$0.00	6.00	False	6" P-209 AGG BASE
09-01-2020	SG-CO	Subgrade - Compacted	\$0.00	12.00	False	12" SUBGRADE

**Branch - Section ID: T01JE - 01**

LCD: 6/1/2000  
 Use: TAXIWAY  
 Rank: P  
 Surface: PCC

Length (ft): 455.00  
 Width (ft): 35.00  
 True Area (sf): 17,845.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
06-01-2000	CR-PC	Complete Reconstruction - PCC	\$0.00	5.00	True	5" P-501
05-31-2000	BA-AG	Base Course - Aggregate	\$0.00	4.00	False	4" AGG BASE
05-30-2000	SB-AG	Subbase - Aggregate	\$0.00	6.00	False	6" P154 ASSUMED, RECYCLED AC
06-01-1986	NC-AC	New Construction - AC	\$0.00	0.00	True	-

**Branch - Section ID: T02JE - 01**

LCD: 12/2/2005  
 Use: TAXIWAY  
 Rank: P  
 Surface: PCC

Length (ft): 300.00  
 Width (ft): 26.00  
 True Area (sf): 9,183.00

Work Date	Work Code	Work Description	Cost	Thickness (in)	Major MR	Comments
12-02-2005	CR-PC	Complete Reconstruction - PCC	\$32,126.00	5.00	True	5" P501; Total Project Cost: \$169,086
12-01-2005	SB-AG	Subbase - Aggregate	\$0.00	6.00	False	6" P154 ASSUMED, COMPACTED GRANULAR S
06-01-1997	NU-IN	New Construction - Initial	\$0.00	0.00	True	-

## **APPENDIX E**

### **LOCALIZED PREVENTIVE MAINTENANCE POLICIES AND UNIT COST TABLES**

Table E-1. Localized preventive maintenance policy, asphalt-surfaced pavements.

<b>Distress Type</b>	<b>Severity Level</b>	<b>Maintenance Action</b>
Alligator Cracking	Low	Monitor
Alligator Cracking	Medium	Asphalt Patch
Alligator Cracking	High	Asphalt Patch
Bleeding	N/A	Monitor
Block Cracking	Low	Monitor
Block Cracking	Medium	Crack Seal—Asphalt
Block Cracking	High	Crack Seal—Asphalt
Corrugation	Low	Monitor
Corrugation	Medium	Asphalt Patch
Corrugation	High	Asphalt Patch
Depression	Low	Monitor
Depression	Medium	Monitor
Depression	High	Asphalt Patch
Jet-Blast Erosion	N/A	Asphalt Patch
Joint Reflection Cracking	Low	Monitor
Joint Reflection Cracking	Medium	Crack Seal—Asphalt
Joint Reflection Cracking	High	Crack Seal—Asphalt
L&T Cracking	Low	Monitor
L&T Cracking	Medium	Crack Seal—Asphalt
L&T Cracking	High	Crack Seal—Asphalt
Oil Spillage	N/A	Asphalt Patch
Patching	Low	Monitor
Patching	Medium	Asphalt Patch
Patching	High	Asphalt Patch
Polished Aggregate	N/A	Monitor
Raveling	Low	Monitor
Raveling	Medium	Asphalt Patch
Raveling	High	Asphalt Patch
Rutting	Low	Monitor
Rutting	Medium	Monitor
Rutting	High	Asphalt Patch
Shoving	Low	Monitor
Shoving	Medium	Asphalt Patch
Shoving	High	Asphalt Patch
Slippage Cracking	N/A	Asphalt Patch
Swelling	Low	Monitor
Swelling	Medium	Monitor
Swelling	High	Asphalt Patch
Weathering	Low	Monitor
Weathering	Medium	Monitor
Weathering	High	Asphalt Patch

Table E-2. Localized preventive maintenance policy, PCC pavements.

<b>Distress Type</b>	<b>Severity Level</b>	<b>Maintenance Action</b>
ASR	Low	Monitor
ASR	Medium	Slab Replacement
ASR	High	Slab Replacement
Blowup	Low	Slab Replacement
Blowup	Medium	Slab Replacement
Blowup	High	Slab Replacement
Corner Break	Low	Crack Seal—PCC
Corner Break	Medium	Full Depth PCC Patch
Corner Break	High	Full Depth PCC Patch
Durability Cracking	Low	Monitor
Durability Cracking	Medium	Full Depth Patch
Durability Cracking	High	Slab Replacement
Faulting	Low	Monitor
Faulting	Medium	Grinding
Faulting	High	Slab Replacement
Joint Seal Damage	Low	Monitor
Joint Seal Damage	Medium	Joint Seal
Joint Seal Damage	High	Joint Seal
LTD Cracking	Low	Monitor
LTD Cracking	Medium	Crack Seal—PCC
LTD Cracking	High	Slab Replacement
Patching (Small and Large)	Low	Monitor
Patching (Small and Large)	Medium	Full Depth PCC Patch
Patching (Small and Large)	High	Full Depth PCC Patch
Popouts	N/A	Monitor
Pumping	N/A	Monitor
Scaling	Low	Monitor
Scaling	Medium	Partial Depth PCC Patch
Scaling	High	Slab Replacement
Shattered Slab	Low	Crack Seal—PCC
Shattered Slab	Medium	Slab Replacement
Shattered Slab	High	Slab Replacement
Shrinkage Cracking	N/A	Monitor
Spalling (Joint and Corner)	Low	Monitor
Spalling (Joint and Corner)	Medium	Partial Depth PCC Patch
Spalling (Joint and Corner)	High	Partial Depth PCC Patch

Table E-3. 2022 unit costs for preventive maintenance actions.

Maintenance Action	Unit Cost
Asphalt Patch—Asphalt-Surfaced Pavement	\$14.66/sf
Crack Sealing—Asphalt-Surfaced Pavement	\$2.51/lf
Partial Depth PCC Patch—PCC Pavement	\$37.54/sf
Full Depth PCC Patch—PCC Pavement	\$16.76/sf
Crack Sealing—PCC Pavement	\$3.02/lf
Joint Sealing—PCC Pavement	\$3.02/lf
Grinding—PCC Pavement	\$0.36/sf
Slab Replacement—PCC Pavement	\$16.76/sf

Table E-4. 2022 unit costs (per square foot) based on pavement type and PCI ranges.

Pavement Type	PCI Range 0–40	PCI Range 40–50	PCI Range 50–60	PCI Range 60–70	PCI Range 70–80	PCI Range 80–90	PCI Range 90–100
AC	\$10.41	\$4.93	\$4.93	\$4.93	\$0.00	\$0.00	\$0.00
PCC	\$17.38	\$8.22	\$8.22	\$8.22	\$0.00	\$0.00	\$0.00



## **APPENDIX F**

# **YEAR 2022 LOCALIZED PREVENTIVE MAINTENANCE DETAILS**

Table F-1. Year 2022 localized preventive maintenance details.

Branch	Section	Distress Type	Severity	Distress Quantity	Distress Unit	Maintenance Action	Unit Cost	2022 Estimated Cost
A01JE	01	ASR	Medium	1	Slabs	Slab Replacement - PCC	\$16.76	\$2,619
A01JE	01	Corner Break	Low	7	Slabs	Crack Sealing - PCC	\$3.02	\$181
A01JE	01	Corner Spalling	Medium	3	Slabs	Patching - PCC Partial Depth	\$37.54	\$318
A01JE	01	Faulting	Medium	3	Slabs	Grinding (Localized)	\$0.36	\$14
A01JE	01	Joint Spalling	Medium	6	Slabs	Patching - PCC Partial Depth	\$37.54	\$1,491
A01JE	01	Joint Spalling	High	4	Slabs	Patching - PCC Partial Depth	\$37.54	\$1,212
A01JE	01	Shattered Slab	Low	17	Slabs	Crack Sealing - PCC	\$3.02	\$1,265
A01JE	02	Corner Break	Low	2	Slabs	Crack Sealing - PCC	\$3.02	\$49
A01JE	02	Joint Seal Damage	High	227	Slabs	Joint Seal (Localized)	\$3.02	\$16,474
A02JE	01	Corner Break	Medium	2	Slabs	Patching - PCC Full Depth	\$16.76	\$854
A02JE	01	Joint Spalling	Medium	2	Slabs	Patching - PCC Partial Depth	\$37.54	\$383
A02JE	01	LTD Cracking	Medium	2	Slabs	Crack Sealing - PCC	\$3.02	\$54
A02JE	01	Small Patch	Medium	2	Slabs	Patching - PCC Full Depth	\$16.76	\$71
A02JE	02	Faulting	Medium	1	Slabs	Grinding (Localized)	\$0.36	\$4
R14JE	01	Faulting	Medium	7	Slabs	Grinding (Localized)	\$0.36	\$32
R14JE	01	Joint Seal Damage	Medium	337	Slabs	Joint Seal (Localized)	\$3.02	\$23,856
R14JE	01	Joint Seal Damage	High	1,011	Slabs	Joint Seal (Localized)	\$3.02	\$71,568
R14JE	01	LTD Cracking	Medium	70	Slabs	Crack Sealing - PCC	\$3.02	\$2,725
R14JE	02	Corner Break	Low	1	Slabs	Crack Sealing - PCC	\$3.02	\$28

Table F-1. Year 2022 localized preventive maintenance details (continued).

Branch	Section	Distress Type	Severity	Distress Quantity	Distress Unit	Maintenance Action	Unit Cost	2022 Estimated Cost
R14JE	02	Corner Spalling	Medium	1	Slabs	Patching - PCC Partial Depth	\$37.54	\$115
R14JE	02	Joint Seal Damage	Medium	27	Slabs	Joint Seal (Localized)	\$3.02	\$1,688
R14JE	02	Joint Seal Damage	High	48	Slabs	Joint Seal (Localized)	\$3.02	\$2,954
R14JE	02	Joint Spalling	Medium	1	Slabs	Patching - PCC Partial Depth	\$37.54	\$277
R14JE	02	LTD Cracking	Medium	1	Slabs	Crack Sealing - PCC	\$3.02	\$44
R14JE	02	Shattered Slab	Low	1	Slabs	Crack Sealing - PCC	\$3.02	\$88
R14JE	03	Joint Seal Damage	Medium	28	Slabs	Joint Seal (Localized)	\$3.02	\$1,718
R14JE	03	Joint Seal Damage	High	81	Slabs	Joint Seal (Localized)	\$3.02	\$5,011
R14JE	03	Joint Spalling	Medium	1	Slabs	Patching - PCC Partial Depth	\$37.54	\$281
R14JE	03	Joint Spalling	High	1	Slabs	Patching - PCC Partial Depth	\$37.54	\$351
T01JE	01	Corner Break	Medium	2	Slabs	Patching - PCC Full Depth	\$16.76	\$824
T01JE	01	Joint Seal Damage	Medium	131	Slabs	Joint Seal (Localized)	\$3.02	\$7,570
T02JE	01	Joint Seal Damage	High	56	Slabs	Joint Seal (Localized)	\$3.02	\$3,158

## Table Notes:

1. See Figure 3 for the location of the branch and section.
2. Distress types are defined by ASTM D5340-20. L&T Cracking = Longitudinal and Transverse Cracking; LTD Cracking = Longitudinal, Transverse, and Diagonal Cracking; ASR = Alkali-Silica Reaction.
3. The costs provided are of a general nature for the entire state and may require adjustment to reflect specific conditions at Jefferson Municipal Airport.



**PREPARED FOR**

Iowa Department of Transportation  
Modal Transportation Bureau — Aviation  
800 Lincoln Way  
Ames, Iowa 50010  
515-239-1691  
[iowadot.gov/aviation](http://iowadot.gov/aviation)

**JULY 2022**