

LOCAL AGENCY LETTING INFORMATION

CONTENTS

DATE ADDED	COUNTY/CITY	LETTING DATE	PAGE NUMBER
June 8, 2022	Sac	July 14, 2022	2
June 27, 2022	Iowa	July 22, 2022	3
July 1 2022	Johnson	July 26, 2022	4
July 1, 2022	Johnson	July 26, 2022	6
July 5, 2022	Obrien	July 26, 2022	7
July 12, 2022	Scott	July 26, 2022	8



BULLETIN REPORTING FORM

County:	Sac County	Project No.:	L-PCCP23--73-81
Proposal Guarantee:	\$25,000.00	DBE or TSB Goal:	
Date of Letting:	7/14/2022	Time of Letting:	02:00 PM
Bid Turn-In Location:	County Engineer	Type of Project:	PCC Paving
Contact Phone No.:	712-662-7687	Contact FAX No.:	712-662-4746

Specific Description of Project:

Sac County PCC Patching Project on various roads within the county.

QUANTITY	UNIT	DESCRIPTION
132	SY	GRANULAR SUBBASE
150.8	TON	MACADAM STONE BASE
436	LB	REINFORCING STEEL, EPOXY COATED
1	LS	TRAFFIC CONTROL
75	EACH	FLAGGERS
30	EACH	PILOT CARS
8	EACH	CD JOINT ASSEMBLY
1298.1	SY	PATCHES, FULL-DEPTH FINISH, BY AREA
1062.1	SY	PATCHES, FULL-DEPTH FINISH, BY AREA (50 FEET OR GREATER IN LENGTH)
71	EACH	PATCHES, FULL-DEPTH FINISH, BY COUNT
44	LF	PRESSURE RELIEF JOINT, CF
1	LS	MOBILIZATION

Date: 6/8/2022 Local Agency Official: Nick Buse, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



BULLETIN REPORTING FORM

County: Iowa County Project No.: L-HMA MAINTENANCE
 Proposal Guarantee: \$1.00 DBE or TSB Goal: _____
 Date of Letting: 7/22/2022 Time of Letting: 09:00 AM
 Bid Turn-In Location: County Engineer Type of Project: HMA Joint & Crack Sealing
 Contact Phone No.: 319-642-3721 Contact FAX No.: 319-642-7046

Specific Description of Project:

County wide HMA, Joint & Crack Sealing, see plans for details

QUANTITY	UNIT	DESCRIPTION
1	LS	TRAFFIC CONTROL
40	EACH	FLAGGERS
20	EACH	PILOT CARS
1	LS	MOBILIZATION
61.1	MILE	CRACK AND JOINT CLEANING AND SEALING (HMA SURFACES)
15470	LB	SEALER MATERIAL (HMA SURFACES)

Date: 6/27/2022 Local Agency Official: Nicholas Amelon, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



BULLETIN REPORTING FORM

County:	Johnson County	Project No.:	L-N-5-2--73-52
Proposal Guarantee:	\$25,000.00	DBE or TSB Goal:	
Date of Letting:	7/26/2022	Time of Letting:	09:00 AM
Bid Turn-In Location:	Auditor's Office	Type of Project:	Bridge or Culvert
Contact Phone No.:	319-356-6046	Contact FAX No.:	319-339-6133

Specific Description of Project:

Bridge replacement on Half Moon Avenue SW over Deer Creek. A 30'-0" long by 30'-6" wide single span continuous concrete slab bridge with a 15° left ahead skew shall replace the existing 26' long by 20' wide steel stringer bridge with a concrete deck and abutments. Section 5, T79N, R7W, Johnson County, Iowa.

QUANTITY	UNIT	DESCRIPTION
0.22	ACRE	CLEARING AND GRUBBING
531	CY	EXCAVATION, CLASS 10, ROADWAY AND BORROW
452	CY	EXCAVATION, CLASS 13, CHANNEL
87	CY	TOPSOIL, STRIP, SALVAGE AND SPREAD
200	TON	MACADAM STONE BASE
110	TON	GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE
1	LS	REMOVAL OF EXISTING BRIDGE
102	CY	EXCAVATION, CLASS 20
123.1	CY	STRUCTURAL CONCRETE (BRIDGE)
20435	LB	REINFORCING STEEL, EPOXY COATED
60.3	LF	CONCRETE OPEN RAILING, TL-4
1155	LF	PILES, STEEL, HP 10 X 57
60	LF	SUBDRAIN, TILE, 6 IN. DIA.
2	EACH	SUBDRAIN OUTLET, DR-305
625	SY	ENGINEERING FABRIC
780	TON	REVTMENT, CLASS E
4	EACH	OBJECT MARKER, TYPE 3
4	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
0.12	ACRE	MULCHING
0.12	ACRE	SEEDING AND FERTILIZING (RURAL)
0.12	ACRE	STABILIZING CROP - SEEDING AND FERTILIZING
160	LF	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.

Date: 7/1/2022 Local Agency Official: Greg Parker, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



BULLETIN REPORTING FORM

County:	<u>Johnson County</u>	Project No.:	<u>LFM-Bridges-2021--7X-52</u>
Proposal Guarantee:	<u>\$25,000.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>7/26/2022</u>	Time of Letting:	<u>09:00 AM</u>
Bid Turn-In Location:	<u>Auditor's Office</u>	Type of Project:	<u>Bridge or Culvert</u>
Contact Phone No.:	<u>319-356-6046</u>	Contact FAX No.:	<u>319-339-6133</u>

Specific Description of Project:

Bridge Deck Patching and Overlay on Orval Yoder Turnpike SW over Old Mans Creek. The Base Bid includes patching and overlaying the existing bridge deck, as well as placing new approach pavement and repairing the undermined abutments. The Bid Alternate includes painting the existing steel cased piles of the bridge piers. Section 35, T79N, R8W, Johnson County, Iowa.

QUANTITY	UNIT	DESCRIPTION
28	CY	EXCAVATION, CLASS 10, UNSUITABLE OR UNSTABLE MATERIAL
127.5	SY	BRIDGE APPROACH PAVEMENT, AS PER PLAN
40	TON	GRANULAR BACKFILL
566.2	SY	DECK OVERLAY (CLASS HPC-O PCC)
175.4	SY	DECK REPAIR, CLASS A
175.4	SY	GALVANIC PROTECTION SYSTEM
1	LS	BRIDGE CLEANING FOR PAINTING
1	LS	BLAST CLEANING OF STRUCTURAL STEEL
1	LS	CONTAINMENT
1	LS	PAINTING OF STRUCTURAL STEEL

Date: 7/1/2022 Local Agency Official: Greg Parker, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



BULLETIN REPORTING FORM

County:	<u>Obrien County</u>	Project No.:	<u>L-B5127s2--73-71</u>
Proposal Guarantee:	<u>\$25,000.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>7/26/2022</u>	Time of Letting:	<u>10:00 AM</u>
Bid Turn-In Location:	<u>O'Brien County Auditor's Office</u>	Type of Project:	<u>Bridge or Culvert</u>
Contact Phone No.:	<u>712-957-3425</u>	Contact FAX No.:	<u>712-957-4740</u>

Specific Description of Project:

Bridge Replacement with 90'0" x 24'0" CCS located on Redwood Ave. Between 430th St. and 440th St. in O'Brien County, IA

QUANTITY	UNIT	DESCRIPTION
302.070	CY	EMBANKMENT-IN-PLACE
93.690	CY	EXCAVATION, CLASS 10, CHANNEL
1	LS	REMOVAL OF EXISTING BRIDGE
453.570	CY	EXCAVATION, CLASS 20
176.200	CY	STRUCTURAL CONCRETE (BRIDGE)
43299.000	LB	REINFORCING STEEL
202.000	LF	CONCRETE OPEN RAILING, TL-4
500.000	LF	PILES, STEEL, HP 10 X 42
1160.000	LF	PILES, STEEL, HP 10 X 57
232.000	LF	CONCRETE ENCASEMENT OF STEEL H PILES, HP 10 X 57 (P10L TYPE 3)
217.000	SY	ENGINEERING FABRIC
138.000	TON	REVTMENT, CLASS E
4.000	EACH	SAFETY CLOSURE
1.000	LS	TRAFFIC CONTROL
1.000	LS	MOBILIZATION

Date: 7/5/2022 Local Agency Official: Scott Rinehart, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us



BULLETIN REPORTING FORM

County:	<u>Scott County</u>	Project No.:	<u>CST-061-5(149)--4C-82</u>
Proposal Guarantee:	<u>\$37,500.00</u>	DBE or TSB Goal:	<u></u>
Date of Letting:	<u>7/26/2022</u>	Time of Letting:	<u>10:00 AM</u>
Bid Turn-In Location:	<u>950 E. Blackhawk Trail, Eldridge, IA 52742</u>	Type of Project:	<u>PCC Paving</u>
Contact Phone No.:	<u>563-326-8640</u>	Contact FAX No.:	<u>563-328-4173</u>

Specific Description of Project:

Intersections Improvement Project in Scott County, Iowa. Intersections involved: • 110th Avenue (Y-48) at US Highway 61 • 112th Avenue at US Highway 61 • 140th Street Place at 110th Avenue

QUANTITY	UNIT	DESCRIPTION
550	CY	EXCAVATION, CLASS 13, ROADWAY AND BORROW
546.6	SY	PAVED SHOULDER, P.C. CONCRETE, 6 IN.
484.3	SY	STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 7 IN.
2478.8	SY	STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 10 IN.
300.5	SY	MEDIAN, P.C. CONCRETE, 6 IN.
945	LF	SUBDRAIN, PERFORATED PLASTIC PIPE, 4 IN. DIA.
2587	SY	REMOVAL OF PAVEMENT
6	EACH	LOOP DETECTORS (ADDITION OR REPLACEMENT TO AN EXISTING TRAFFIC SIGNAL SYSTEM)
1	LS	CONSTRUCTION SURVEY
405	CY	SPECIAL BACKFILL

Date: 7/12/2022 Local Agency Official: Angela Kersten, County Engineer

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts, at DOT.Contracts@iowadot.us