Change Orders (Contract Modifications)

A Change Order is a written order to a contractor for a change to the intent of the original contract, i.e. an increase or decrease in contract quantities, or changes to the plans or specifications.

Change Orders (Contract Modifications)

- LPA Projects
 - IM 6.000 Att. D Section 2.36Preparation of a Change Order p. 66 to 80 of 106
- Department Projects
 - CM Ch 2 Contract Modificationsp. 2-59 to 70

Change Orders are used to:

- Change authorized quantities of items (increases or decreases)
- Add a new item or material
- Serve as a Source Document for the Office of Finance to enter changes and additions to Progress Vouchers
- Document changes to the contract documents – once signed by all parties are legally binding

- Any change to the original scope or intent of the project.
- Price adjustment to reduce payment for an item below minimum standards.

- Deletion of item with original contract amount more than \$50,000.
- Overruns and underruns more than \$50,000 based on category amount.

- Any overrun/underrun of items that are defined to be paid at contract quantity.
 - –Note: For changes to Plan quantity items, field measurements are required to document the change in quantity!

- Incentive/Disincentive Provisions
- Value Engineering proposals
- Plan Revisions with new and/or changes to contract items.

- Adding items to the Contract
- Changes to the Specifications
- Extensions of Contract Time
- Settlement of Liquidated Damages.

- Less than \$50,000 Value
 - 1. Deletion of an item < \$50,000.00
 - 2. Overruns / Underruns < \$50,000.00

Substantial vs. Non-substantial

- Substantial the project engineer <u>must</u> obtain preapproval from the Administering Bureau
- Non-substantial prepared by the project engineer & approved by the DLSE

Justification Checklist for Change Orders

Some acceptable methods to justify change orders are:

- Original copies of material quotes
- Comparable prices to the "Summary of Awarded Prices"
- Independent cost check of area suppliers

Justification Checklist for Change Orders (continued)

- Equipment Watch (for equipment)
- Invoices Prices for Materials
- Contractor's certified payroll (for labor)
- Davis-Bacon wage determinations (for labor)

Justification Checklist for Change Orders (continued)

- Summary of actual costs
- Similar contracted items on previous projects
- Previous Change Order costs for like items

Examples of Statements on C.O. for Prices

- Agreed price is comparable to item xxxx (a similar item)
- Cost is justifiable based on Rental Rate Blue Book values
- Analysis is included in the project file
- Agreed price is based on invoiced prices and estimated labor cost is comparable to item xxxx (a similar item)

Examples of Statements on C.O. for Prices

- Individual costs have been agreed to based on certified payroll expenses, invoiced rental rate charges, and actual material invoiced
- Summary of analysis is attached (Use for very brief analysis)
- Summary of costs and analysis is included in the project file

Contract Time Adjustment

- <u>Every</u> Change Order must address time considerations.
- Impact on time may be addressed in one of three ways:
 - 1. No change in contract time
 - 2. Contract period will be adjusted by "X" working (or calendar) days
 - 3. Impact on contract time will be reviewed at a later day

OR

Impact on the contract time cannot be determined at this time.

Participating vs. Nonparticipating

- Participating or nonparticipating are applicable to both substantial and nonsubstantial
- The Administering Bureau will review the Federal and State potential participation.



CHANGE ORDER

For Local Public Agency Projects

	No.:		Non-Substant	ial:	
			Substantial:		Administering Office Concurrence Date
Accounting ID No. (5-digit number):		Project Number:			
Contract Work Type:	<u></u>	Local Public Agen	cy:		
Contractor:	#16 ×	Date Prepared:			
You are hereby authorized to make the following A - Description of change to be made:	g changes to the contract docum	nents.			
B - Reason for change:					

C - Settlement for cost(s) of change as follows with items addressed in	n Sections F and/or G:	
D - Justification for cost(s) (See I.M. 3.805, Attachment D, Chapter 2.3	36, for acceptable justification):	
E - Contract time adjustment: No Working Days added	Working Days added:	Unknown at this time
Justification for selection:	<u></u>	

OIOWADOT			Accounting	ID No.(5-digit num	ber):
Form 831240 (01-18)	ntvo et			Change Order	No.:
Items included in co Participating	ntract:		THE DESIGNATION AND USE OF	ions enter as	
ederal- State aid aid	Line Number	Item Description	Unit Price	Quantity .xxx	Amount .xx
000 000 000 000 000	0 100	Add Row Delete Ro	DW TO	TAL	

- Items not	included in c	ontract:					di .
					For deducti	ons enter as	
Partici	pating					.xx"	
Federal	State-	Change	Item Number	Item Description	Unit Price	Quantity	Amount
aid	aid	Number			.XX	.xxx	.XX
					-		7
					.2		
					-		
			Add Row	Delete Row	TO	TAL	
			<i>y</i>				

			<u></u>				
H. Signatures			Accounting ID No.(5-digit number):				
Agreed:				Change Order	No.:		
	Contractor	Date					
Recommended:	Project Engineer	Date					
Approved:	Person in Responsible Charge	Date	Other (optional)	Title	Date		
	Contracting Authority (optional)	Date	Other (optional)	Title	Date		
	lowa DOT Administering Office	Date					
Approval is conting modified project ag	gent upon funds being available under the exis greement.	sting project agreem	ent or upon additional Federal-	aid funds being mad	le available by a		
FHWA Concurrence	Federal Highway Division Administration (if required)	Date					
DISTRIBUTION (aft	er fully executed on LPA projects): Original - Final	nce; Copies - Contrac	tor, Project Engineer, Contracting	Authority, Administeri	ng Office.		
Date distributed: .	Initials:	- .					
		Or					
□ Cianatures							

H. Signatures



Contract Modification

6/26/2018 9:18 AM

FieldManager 5.3a

Contract: 31-0321-041, BRIDGE NEW - STEEL GIRDER

Cont. Mod. Number	Revision Number	Cont. Mod. Date	Net Change	Awarded Contract Amount
1		6/26/2018	\$945.23	\$1,388,040.68
Route		Entered By		
IOWA 32 (C347	55)	Charles Seeland		

Contract Location

NHSX-032-1(41)--3H-31 ** U.S. 61 CONNECTOR ROAD B OVER GRANG

Short Description

Increase/Decrease Items

Description of Changes

Increase Item 0050, Structural Concrete (Bridge)
Decrease Item 0060, High Performance Structural Concrete
Increase Item 0080, Reinforcing Steel, Epoxy Coated

Contract Modification shall have no impact on working days f0or this project.

Increases / Decreases

Project: 31-0321-041, 171219 031 TMC WAIT

Category: 0001, P:DESIGN NO. 1917; 260'-0 X 36'-0 CONTINUOUS WELDED GIRDER B, DGE

Item DescriptionItem CodeProp.Ln.Item TypeUnit Quantity Chg.Unit PriceDollar ValueSTRUCT CONC (BRIDGE)2403-01000100050ORIGINAL CY48.700472.50000\$23,010.75

Reason: Contractor used the wrong mix for the West abutment footing. Used C-4 mix instead of HPC. It will be paid accordingly. 46.1 cubic yards is the plan quantity for the west abutment footing. 2.6 cubic yards is the quantity that was changed due to having to bump the face of the abutment out to maintain the clearance for the reinforcing steel.

Justification of costs: Contract Unit Price.

HIGH PERFORMANCE STRUC CONC 2403-7000210 0060 ORIGINAL CY -43.600 520.00000 \$-22,672.00

Reason: Contractor used the wrong mix for the West abutment footing. Used C-4 mix instead of HPC. It will be paid accordingly. 46.1 cubic yards will be decreased. Item will be increased by 2.5 cubic yards for the face being bumped out to accomodate the reinforcing steel clearance.

Justification of costs: Contract Unit Price.

REINFORC STEEL, EPOXY COATED 2404-7775005 0080 ORIGINAL LB 722.000 0.84000 \$606.48

Reason: When forming the abutment backwall, it was determined that the 5g1 rebar on each abutment was only long enough for half of the roadway and that the 5g2 bars included quantity for only one wing on each abutment. The contractor was given a revised bar listing and the quantity adjustment for each item is provided as shown above.

Justification of costs: Contract Unit Price.

Subtotal for Category 0001: \$945.23

Subtotal for Project 31-0321-041: \$945.23

Contract: 31-0321-041 Cont. Mod.: 1 Page 1 of 2



Iowa Department of Transportation

contract documents.

6/26/2018 9:18 AM

FieldManager 5.3a

When authorized, the contractor agrees to perform the work outlined above in accordance with provisions of the

Doc Express Document Signing History Contract: 31-0321-041 Document: CM 01

Date	Signed By
08/24/2018	Dan Schroeder Jim Schroeder Construction Electronic Signature (Reviewed by Contractor)
08/24/2018	Hugh Holak lowa DOT Electronic Signature (Reviewed by Resident Engineer)
08/24/2018	Doug McDonald lowa DOT Electronic Signature (Reviewed by District Construction Engineer)

lowa Department of Transportation

Contract Modification

8/23/2018 11:01 AM

FieldManager 5.3a

Contract: 31-0321-041, BRIDGE NEW - STEEL GIRDER

Cont. Mod. Number	Revision Number	Cont. Mod. Date	Net Change	Awarded Contract Amount
2		8/23/2018	\$37,980.01	\$1,388,040.68
Route		Entered By		
IOWA 32 (C347	55)	Charles Seeland		

Contract Location

NHSX-032-1(41)--3H-31 ** U.S. 61 CONNECTOR ROAD B OVER GRANG

Short Description

Add Items/Increase Items for reinforcing steel

Description of Changes

Add Item 0425, Extra Transverse Steel, Invoice # 10217

Add Item 0430, Extra Longitudinal Steel, Invoice # 10206

Add Item 0435, Extra Stainless Reinforcing Steel, Invoice # 10242

Increase Item 0080, Reinforcing Steel, Epoxy Coated

Increase Item 0090, Reinforcing Steel, Stainless Steel

Contract Modification will have no impact on working days for this contract.

Increases / Decreases

Project: 31-0321-041, 171219 031 TMC WAIT

Category: 0001, P:DESIGN NO. 1917; 260'-0 X 36'-0 CONTINUOUS WELDED GIRDER B, DGE

Item DescriptionItem CodeProp.Ln.Item TypeUnitQuantity Chg.Unit PriceDollar ValueREINFORC STEEL, EPOXY COATED2404-77750050080ORIGINAL LB35,489.0000.84000\$29,810.76

Reason: There were 552 pieces of # 6 epoxy coated rebar, 40' 7" in length, totaling 33468 lbs., left out of the bar list in the project plans. This is shown on invoice #10206, dated 7-12-2018. There was 2021 lbs. of transverse steel on the skewed bridge ends that were left out of the bar list also. These are shown on Invoice # 10217, dated 7-18-2018. These were both Design errors.

Justification of costs: Contract Unit Price.

REINF STEEL, STAINLESS STEEL 2404-7775009 0090 ORIGINAL LB 743.000 3.15000 \$2,340.45

Reason: Plans called for epoxy coated reinforcing in the top of the wings for the Barrier Rail. This was a design error. Stainless bars are to be used in the rail

Justification of costs: Contract Unit Price.

Subtotal for Category 0001: \$32,151.21

Subtotal for Project 31-0321-041: \$32,151.21

Contract: 31-0321-041 Cont. Mod.: 2 Page 1 of 2

Contract Modification



8/23/2018 11:01 AM

FieldManager 5.3a

New Items

Project: 31-0321-041, 171219 031 TMC

Category: 0001, P:DESIGN NO. 1917; 260'-0 X 36'-0 CONTINUOUS WELDED GIRDER B, DGE

Item Description	Item Code	Prop.Ln.	ItemType	Unit	Proposed Qty.	Unit Price	Dollar Value
('LUMP SUM' ITEM) Extra Transverse	2599-9999010	0425	SUPPLEMENT	TLS	1.000	1,133.58000	\$1,133.58
Steel, Invoice # 10217							

Reason: There was an error in the plan that omitted 2021 lbs. of epoxy reinforcing steel. The cost of the reinforcing steel increased by \$0.3135 and there was a \$500.00 freight cost.

Justification of costs: 2021 lbs. X \$0.3135 = \$633.58. Plus freight cost of \$500.00 equals \$1133.58.

('LUMP SUM' ITEM) Extra Longitudinal 2599-9999010 0430 SUPPLEMENT LS 1.000 3,662.92000 \$3,662.92 Steel, Invoice #10206

Reason: There was an error in the plan that omitted 33,468 lbs. of epoxy reinforcing steel for the deck. The cost of the steel increased by \$0.094 and there was a \$500.00 freight charge.

Justification of costs: 33648 lbs. X \$0.094 = \$3162.92. Plus \$500.00 freight charge equals \$3662.92

('LUMP SUM' ITEM) Extra Stainless 2599-9999010 0435 SUPPLEMENT LS 1.000 1,032.30000 \$1,032.30 reinforc. Invoice #10242

Reason: There was an error in the plan that omitted 743 lbs. of Stainless Reinforcing Steel. The cost of the Reinforcing steel increased by \$1.10 plus a freight charge of \$215.00.

Justification of costs: 743 lbs. X \$1.10 = \$817.30. Plus \$215.00 freight equals \$1032.30.

Subtotal for Category 0001: \$5,828.80

Subtotal for Project 31-0321-041: \$5,828.80

When authorized, the contractor agrees to perform the work outlined above in accordance with provisions of the contract documents.

Doc Express Document Signing History Contract: 31-0321-041 Document: CM 02

Date	Signed By
08/24/2018	Dan Schroeder Jim Schroeder Construction Electronic Signature (Reviewed by Contractor)
08/24/2018	Hugh Holak lowa DOT Electronic Signature (Reviewed by Resident Engineer)
08/24/2018	Doug McDonald lowa DOT Electronic Signature (Reviewed by District Construction Engineer)



Iowa Department of Transportation

Contract Modification

11/14/2018 8:49 AM

FieldManager 5.3a

Contract: 31-0321-041, BRIDGE NEW - STEEL GIRDER

Cont. Mod. Number	Revision Number	Cont. Mod. Date	Net Change	Awarded Contract Amount
3		11/14/2018	\$3,300.00	\$1,388,040.68
Route		Entered By		
IOWA 32 (C347	55)	Charles Seeland		

Contract Location

NHSX-032-1(41)--3H-31 ** U.S. 61 CONNECTOR ROAD B OVER GRANG

Short Description

Add Item for Special Ditch Control, Wood Excelsior Mat

Description of Changes

Add Item 0440, Special Ditch Control, Wood EXcelsior Mat

Contract Modification will have no impact on working days for this contract.



New Items

Project: 31-0321-041, 171219 031 TMC Category: 0002, P:ROADWAY ITEMS

Item Description	Item Code	Prop.Ln.	ItemType	Unit	Proposed Qty.	Unit Price	Dollar Value
SPECIAL DITCH CONTROL,WOOD EXCELSIOR MAT	2601-2640350	0440	SUPPLEMENT	rsq	100.000	33.00000	\$3,300.00

Reason: It was decided to use Wood Excelsior Mat instead of the Turf Reinforced Mat in the ditches leading to the Creek.

Justification of costs: Agreed Unit Price. Price compares favorably when comparing to the (037), Menard's Road project, project being administered by this RCE. Price includes all materials, labor and equipment costs associated with the completion of this work. Also includes the Prime Contractor's markup.

> Subtotal for Category 0002: \$3,300.00

Subtotal for Project 31-0321-041: \$3,300.00

When authorized, the contractor agrees to perform the work outlined above in accordance with provisions of the contract documents.

Doc Express Document Signing History Contract: 31-0321-041 Document: CM 03

Date	Signed By
12/18/2018	Dan Schroeder Jim Schroeder Construction Electronic Signature (Reviewed by Contractor)
12/18/2018	Hugh Holak lowa DOT Electronic Signature (Reviewed by Resident Engineer)
12/18/2018	Doug McDonald lowa DOT Electronic Signature (Reviewed by District Construction Engineer)

lowa Department of Transportation

Contract Modification

11/29/2016 4:11 PM

FieldManager 5.0a

Contract: 44-C044-077, PCC PAVEMENT - GRADE & REPLACE

You are hereby authorized to make the following changes to the contract documents.

Cont. Mod. Number 6	Revision Number	Cont. Mod. Date 11/29/2016	Net Change \$2,080.00	Awarded Contract Amount \$3,849,653.76
Route (C33023)				Entered By Jelen G McCall
Contract Locat HENRY STP-S-		44		

C	10	WA	D	O.	T
	Form	83124	D (1	2-1	5)

CHANGE ORDER

For Local Public Agency Projects

			•		
	No.: 6		Non-Substantia	l:	
			Substantial:	\boxtimes	Administering Office Concurrence Date
Accounting ID No. (5-digit number):33023		Proje	ct Number: STP-S-C044(77)	5E-44	
Kind of Work: PCC Pavement-Grade/Replc		Loca	Public Agency: Henry Count	y	
Contractor: Cedar Valley Corp., LLC		Date	Prepared: 11/29/2016		

Short Description

Non-participating item

Description of Changes

Subdrain incorporated into project was from an unapproved source; however, contracting authority approved placement of subdrain.

Adding an item as non-participating.

A - Description of change to be made:

8003 - Non-participationg Item. Subdrain incorporated into the project was from an unapproved source; however, Contracting Authority approved placement of subdrain.

B - Reason for change:

8003 - Adding an item as non-participating, Item from an unapproved source.

New Items

Project: 44-C044-077, 151215 030 KAM

Category: 0003, CONTRACT ADMINISTRATION (NON-PARTICIPATING ITEMS)

Item Description	Item Code	Prop.Ln.	. ItemType	Unit	Proposed Qty.	Unit Price	Dollar Value
SUBDRAIN, PVC, STD, NON-PERFORATED, 10"	2502-821311	0 0480	SUPPLEMEN	TLF	104.000	20.00000	\$2,080.00

Reason: Item from unapproved source.

Subtotal for Category 0003: \$2,080.00

Subtotal for Project 44-C044-077: \$2,080.00

C - Settlement for cost(s) of change as follows with items addressed in Sections F and/or G:

8003 - 104.000 LF x \$20.00000/LF = \$2,080.00

It is not acceptable to have "Agreed Price". It must be based on something – Bid Prices, Cost, etc.

D - Justification for cost(s) (See I.M. 3.805, Attachment D, Chapter 2.36, for acceptable justification):

8003 - Bid Price for Item 0300, 2502-8213110, Subdrain, PVC, STD, Non-Perforated, 10"

E - Contract time adjustment: No Working Days added Working Days added: Unknown at this time Justification for selection: No change to Working Days as a result of this funding change. Page 1 of 3
Justification for selection: No change to Working Days as a result of this funding change.
Justification for selection: No change to Working Days as a result of this funding change.
Page 1 of 3
Make sure to address Working Days with either: 1. No effect on Working Days. 2. An additional "X" Working Days will be needed to perform this work, or 3. The effect on Working Days is unknown at this time and will be addressed by a future Change Order.



Accounting ID No.(5-digit number):33023

Change Order No.:6

F - Items included in contract:

Participating						I	tions enter as x.xx"	
Federal- aid	State- aid	Line Number	Item Description		Unit Price	Quantity	Amount	
alu	alu	Number				.XX	.XXX	.XX
				Add Row	Delete F	Row TO	DTAL	

New Items

Project: 44-C044-077, 151215 030 KAM

Category: 0003, CONTRACT ADMINISTRATION (NON-PARTICIPATING ITEMS)

Item DescriptionItem CodeProp.Ln.ItemTypeUnitProposed Qty.Unit PriceDollar ValueSUBDRAIN, PVC, STD,
NON-PERFORATED, 10"2502-82131100480SUPPLEMENT LF104.00020.00000\$2,080.00

Reason: Item from unapproved source.

Subtotal for Category 0003: \$2,080.00

Subtotal for Project 44-C044-077: \$2,080.00

G - Items not included in contract:

Participating					ions enter as .xx"	
Federal- aid	State- aid	Change Number	Item Description	Unit Price .xx	Quantity .xxx	Amount .xx
		8003	2502-8213110 Subdrain, PVC,STD, Non-Perforate	\$20.00	104.000	\$2,080.00
			Add Row Delete Row	ТО	TAL	\$2,080.00

Doc Express Document Signing History

Contract: 44-C044-077 Document: CO 06

This document is in the process of being signed by all required signatories using the Doc Express service. Following are the signatures that have occurred so far.

Date	Signed By	
12/05/2016	Tom Bonner Cedar Valley Corp Electronic Signature (Approved by Contractor)	
12/06/2016	Jake Hotchkiss lowa Local Systems Electronic Signature (Recommended by Engineer)	
12/13/2016	Christy VanBuskirk lowa Local Systems Electronic Signature (Approved by Administering Office or designee)	
	(Approved by FHWA (when applicable))	

H. Signatures						
Agreed:	Tom Bonne Contractor	ř	12/05/2016 Date			
Recommended:	Jake Hotchk Project Engineer		12/06/2016 Date			
Approved:	Person in Respo	nsible Charge	Date	Other (optional)	Title	Date
	Contracting Auth	ority (optional)	Date	Other (optional)	Title	Date
	Christy Vani		12/13/2016 Date			
Approval is contine modified project a		ing available under the e	xisting project agreen	nent or upon additional Federal-	aid funds being made	available by a
FHWA Concurrence		ay Division Administratio	n Date			
DISTRIBUTION (aft	ter fully executed on	LPA projects): Original - Fir	nance; Copies - Contra	ctor, Project Engineer, Contracting	Authority, Administering	g Office.
Date distributed:		Initials:				



- Where would you look to find the Accounting ID Number that the Office of Finance needs to identify the Contract that the Change Order is modifying?
 - ➤On the Contract, it can be found on the second page under the Contract Project(s) heading.

- What should you do if the number of working days will need to be adjusted, but at the time that the Change Order is written it is unknown how long the extra work will take?
 - Check the box that says "Unknown at this time" and write in the comments that the working days needed for the work will be addressed in a future Change Order.

- When increasing or decreasing an existing item, what number should be used for the item number?
 - ➤ The item number on the contract of the original item that is being modified?
- When adding new items to a contract, how should the items be numbered?
 - ➤ Consecutively starting with 8001.

- Is it OK to use the statement "Agreed Price" to justify the cost of a new item added to a contract?
 - ➤ No, that is not sufficient
- Why is it not acceptable?
 - Cost of new items must be based on a comparison of similar items or be broken down into actual costs of materials, labor, equipment, etc.

- What is the difference between Participating and Non-Participating?
 - Participating indicates that the change to the contract may be eligible for federal funding. Non-participating items are funded by either state or local funding.
- What should you do if you do not know what the funding source for the change will be?
 - ➤ Contact the district or regional office.

National Pollutant Discharge Elimination System (NPDES)

- All construction projects that disturb greater than or equal to 1 acre of land will require a NPDES permit
 - Storm Water Discharge Associated with Construction Activity
 - Obtained from the Iowa Department of Natural Resources (Iowa DNR).

National Pollutant Discharge Elimination System (NPDES)

- Required by Iowa Code!
- Failure to obtain and fulfill obligations of this permit may have undesirable consequences.

Storm Water Discharge Permit

 The Contracting **Authority must** obtain a Stormwater Discharge Permit (it can not be done by the consultant)



STATE OF IOWA

DEPARTMENT OF NATURAL RESOURCES CHUCK GIPP, DIRECTOR

DEPARTMENT OF NATURAL RESOURCES NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) NOTICE OF GENERAL PERMIT COVERAGE UNDER GENERAL PERMIT NO. 2

STORM WATER DISCHARGE ASSOCIATED WITH CONSTRUCTION ACTIVITY

This notice of general permit coverage for a storm water discharge associated with construction activity is issued pursuant to the authority of section 402 (b) of the Clean Water Act (U.S.C. 1342(b)), Iowa Code 455B.174, and subrule 567--64.4(2), Iowa Administrative Code. A Notice of Intent has been filed with the Iowa Department of Natural Resources that this storm water discharge complies with the terms and conditions of NPDES General Permit No. 2. Authorization is hereby issued to discharge storm water associated with industrial activity as defined in Part VIII of the Iowa Department of Natural Resources NPDES General Permit No. 2 in accordance with the terms and conditions set forth in the permit.

Owner: HENRY COUNTY SECONDARY ROADS

PO BOX 655

MOUNT PLEASANT IA 52641

(319)385-0762

Permit Coverage Issued To:

HENRY COUNTY SECONDARY ROADS, 220TH ST. IMPROVEMENTS; PROJECT STP-S-CO44(77)--5E-44 - CONSTRUCTION

SITE IS ON 220TH ST. (COUNTY RD. H38), BEGINNING AT THE

INTERSECTION WITH 200TH ST. AND RACINE AVE. AND PROCEEDING

WEST APPROX. 6 MILES

in MOUNT PLEASANT, HENRY COUNTY

located at

1/4 Section	Section	Township	Range
NE, NW, SE, SW-1, NE, SE-2, NE, NW-2, 3, 4, 5, 6, SE, SW-31, 32, 33, 34	35	71N, 72N	6W, 5W

Coverage Provided Through:

4/1/2017

NPDES Permit Discharge Authorization Number:

28387 - 28130

Discharge Authorization Date:

4/1/2016

Project Description: CONSTRUCTION OF ROADWAY IMPROVEMENTS INCLUDING REMOVAL, GRADING AND PORTLAND CEMENT CONCRETE (PCC) PAVEMENT 43.0 ACRES

Public Notice

 A public Notice of Intent must be published in local paper and proof of publication must be submitted with the permit application

AFFIDAVIT OF PUBLICATION

STATE OF IOWA } ss

Mathew W. Bryant being first duly swom on eath deposes and says that he is Publisher of the Mt. Pleasant News, and that he has knowledge of the facts herein alleged, and is the publisher of the Mt. Pleasant News, a weekly newspaper published in the city of Mt. Pleasant, Henry County, Iowa and that the Notice, a copy of which is hereto attached, was published for _____ consecutive days, in said Mt. Pleasant News ____ time ____ each day, the 1st insertion occuring the _____ day of ______ and insertion the _____ day of ______ 2016, the 2nd insertion the _____ day of ______ 2016, the 3nd linsertion the _____ day of ______ 2016.

Signed and dated this _____ day of ______ A.D. 2016

Printer's Legal Fee \$ / 6.70

Subscribed and swom to by Mathew W. Bryant Before me this 24^{+h}day of <u>Fabruary</u>, 2016

Notary Public .



LOIS DIANA LARSON Commission Number 787068 My Commission Expires November 18, 2017

PUBLIC NOTICE

PUBLIC NOTICE OF STORM WATER DISCHARGE

Herry County plans to submit a Notice of Intent to the lowe Department of Natural Rissources to be covered under the NPDES General Permit No. 2 "Storm Water Discharge Associated with Industrial Activity for Construction Activities."

The storm water discharge will be fer grading and pawerent replacement of ZXXh Street in Section 1 and 2 of 1-71N R-6W. Section 2, 3, 4, 5 and 6 of 1-71N, R-6W, and Sections 31, 32, 33, 34 and 35 of 1-72N, R-6W, Henry County.

Storm witter will be discharged from one point source with approximately 43 screet decharging to Big Creek.

Comments may be submitted to the Storm Water Discharge Coordinator, Iowas Department of Natural Resources, Environmental Protection Division, 502 E. Shi Street, Des Nortes, As 50019-0001. The public may review Notice of Inpert from 8.00 s.m. to 430 p.m., Monday Shrough Pricky, at the above address affer it had been received by the department.

Published in the Mt. Pleasant News Februany 26, 2016

> RECEIVED FEB 2 9 2016

Henry County Engineer

Address Environmental Impacts

- If there is a
 Stormwater
 Discharge Permit the
 Prime Contractor
 must be a co permittee to the
 permit.
- Sent with the Contract.

Cedar Valley Corp., LLC. Bid Order: 108

Contract No.: 44-C044-077 Letting: 15Dec2015

This certification must be signed by an Officer of the Company and returned along with the signed contract to the Contracting Authority:

the BOARD OF SUPERVISORS OF HENRY COUNTY

STORM WATER DISCHARGE ASSOCIATED WITH INDUSTRIAL ACTIVITY FOR CONSTRUCTION ACTIVITIES.

Certification Statement

For the projects which include a Storm Water Pollution Prevention Plan (PPP) on the contract shown above:

"I certify under penalty of law that I understand the terms and conditions of the general (or individual, if applicable) National Pollutant Discharge Elimination System (NPDES) permit that authorizes the storm water discharges associated with industrial activity from the construction site as part of this certification.

Further, by my signature, I understand that I am becoming a co-permittee, along with the owner(s) and other contractors and subcontractors signing such certifications, to the Iowa Department of Natural Resources NPDES General Permit No. 2 for "Storm Water Discharge Associated with Industrial Activity for Construction Activities" (or individual NPDES permit, if applicable) at the identified site. As a co-permittee, I understand that I, and my company, are legally required under the Clean Water Act and the Code of Iowa, to ensure compliance with the terms and conditions of the storm water pollution prevention plan developed under this NPDES permit and the terms of this NPDES permit."

Name Stephen R. Jackson
Type, Stamp or Print Legibly

Title President

Cedar Valley Corp., LLC. Phone: (319) 235-9537

2637 Wagner Road (UPS 50703)

PO Box 1740

Waterloo, IA 50704-1740

ed By Maha Date 1-7-16

Address Environmental Impacts

- Any subcontractors
 who will be doing
 work that could
 impact site runoff
 will need to sign on
 as co-permittees.
- C.M. Appendix 10-2

PURINGSUZ ISWA (USPUG)



owa Department of Transportation

CO-PERMITTEE CERTIFICATION STATEMENT

Project No.:
County: Proposal ID No.:
Prime Contractor:
Subcontractor:
Address:
Telephone No.:
certify under penalty of law that I understand the terms and conditions of the general National Pollutant Elimination System (NPDES) permit that authorizes the storm water discharges associated with industrial activity from the construction site as part of this certification.
Further, by my signature, I understand that I am becoming a co-permittee, along with the bwner(s) and other contractors and subcontractors signing such certifications, to the lowa Department of Natural Resources NPDES General Permit No. 2 for Storm Water Discharge Associated with Industrial Activity for Construction Activities at the identified site. As a co-permittee, I understand that I, and my company, are legally required under the Clean Water Act and the Code of Iowa, to ensure compliance with the terms and conditions of the storm water pollution prevention plan developed under this NPDES permit and the terms of this NPDES permit.
* Signature:
Title:

 Certification Statement shall be signed as follows: Corporation – president or vice-president Partnership – general partner Proprietorship - proprietor

Co-Permittee Certification Statement

- It is the responsibility of the Contractor to obtain Co-Permittee Statements.
- These documents are to be submitted at the Pre-construction Conference.

Rockette Trucking & Construction, LLC.

Subcontractor: ROCKETTE TRUCKING & CONSTRUC Subcontractor Vendor ID: RO111

Address: 16553 EAST MISSION Division of Labor Registration: Y

STRAWBERRY POINT, IA 52076-8090 Telephone No.: (563)933-2035

Line No. Item Description	Quantity	Unit Price	"A"	\$ Amount	Partial Item
0050 GRANULAR SHLD, TYPE	5,373.00	\$21.70000	\$116,594.1	\$116,594.10	N
0110 SURF, DRIVEWAY, CL A	469.000	\$22.70000	\$10,646.30	\$10,646.30	N
0380 MOBILIZATION	1.000	\$6,000.000	\$6,000.000	\$6,000.00	Y

Rockette Trucking & Construction , LLC.

Form 830215wd (09-08)



CO-PERMITTEE CERTIFICATION STATEMENT

Project No.: SIP-S-C04	4(77)36-44
County: Henry	Proposal ID No.: 44-C044-077
Prime Contractor: Ceda	r Valley Corp., LLC.
Subcontractor: Rockett	e Trucking & Construction, LTD.
Address: 16553 East Mi	ssion Road, Strawberry Point, IA 52076
Telephone No.: 563-93	3-2094

I certify under penalty of law that I understand the terms and conditions of the general National Pollutant Elimination System (NPDES) permit that authorizes the storm water discharges associated with industrial activity from the construction site as part of this certification.

Further, by my signature, I understand that I am becoming a co-permittee, along with the owner(s) and other contractors and subcontractors signing such certifications, to the Iowa Department of Natural Resources NPDES General Permit No. 2 for Storm Water Discharge Associated with Industrial Activity for Construction Activities at the identified site. As a co-permittee, I understand that I, and my company, are legally required under the Clean Water Act and the Code of Iowa, to ensure compliance with the terms and conditions of the storm water pollution prevention plan developed under this NPDES permit and the terms of this NPDES permit.

* Signature	: Conni Ross	Stejio	
Title:	PRESIDENT		
Date:	2-8-16	,	

 Certification Statement shall be signed as follows: Corporation – president or vice-president Partnership – general partner Proprietorship - proprietor

Peterson Contractors, Inc.

Subcontractor: PETERSON CONTRACTORS INC. Subcontractor Vendor ID: PE320

Address: 104 BLACK HAWK Division of Labor Registration: Y

P.O. BOX A

REINBECK, IA 50669-0155 Telephone No.: (319)345-2713

Line No.	Item Description	Quantity	Unit Price	"A"	\$ Amount	Partial Item
0010	EXCAVATION, CL 10, R	14,763.0	\$6.30000	\$0.00000	\$93,006.90	N
0020	TOPSOIL, STRIP, SALV	1,855.00	\$5.00000	\$0.00000	\$9,275.00	N
0030	SUBGRADE STABIL MAT'	94,004.5	\$1.20000	\$0.00000	\$112,805.40	N
0040	MODIFIED SUBBASE, PL	22,026.0	\$4.25000	\$0.00000	\$93,610.50	N
0060	SHLD FINISH, EARTH	650.800	\$67.00000	\$0.00000	\$43,603.60	N
0120	RMVL OF EXIST STRUCT	1.000	\$18,000.00	\$0.00000	\$18,000.00	N
0130	GRANULAR BACKFILL	2,396.00	\$20.00000	\$0.00000	\$47,920.00	N
0140	EXCAVATION, CL 20, R	5,083.00	\$5.00000	\$0.00000	\$25,415.00	N
0150	APRON, CONC, 24"	4.000	\$900.00000	\$0.00000	\$3,600.00	N
0160	APRON, CONC, 30"	8.000	\$925.00000	\$0.00000	\$7,400.00	N
0170	APRON, CONC, 36"	14.000	\$1,600.000	\$0.00000	\$22,400.00	N
0180	APRON, CONC, 42"	2.000	\$1,800.000	\$0.00000	\$3,600.00	N
0190	APRON, CONC, 60"	2.000	\$3,100.000	\$0.00000	\$6,200.00	N
0200	APRON, CONC, 78"	2.000	\$4,250.000	\$0.00000	\$8,500.00	N

Peterson Contractors, Inc.

Subcontractor: PETERSON CONTRACTORS INC. Subcontractor Vendor ID: PE320

Address: 104 BLACK HAWK Division of Labor Registration: Y

P.O. BOX A

REINBECK, IA 50669-0155 Telephone No.: (319)345-2713

```
0210 CULV, CONC RDWY PIPE
                         110.000 $60.00000 $0.00000
                                                            $6,600.00 N
                         252.000
                                  $70.00000
                                                            $17,640.00 N
0220 CULV, CONC RDWY PIPE
                                             $0.00000
0230 CULV, CONC RDWY PIPE
                         488.000
                                  $98.00000
                                             $0.00000
                                                            $47,824.00 N
                         84.000 $115.00000
                                              $0.00000
                                                             $9,660.00 N
0240 CULV, CONC RDWY PIPE
                         84.000 $190.00000
                                                            $15,960.00 N
0250 CULV, CONC RDWY PIPE
                                             $0.00000
                                                            $39,000.00 N
0260 CULV, CONC RDWY PIPE
                         120.000 $325.00000
                                             $0.00000
0270 CULV, CMP ENT, 15"
                         50.000 $40.00000
                                              $0.00000
                                                            $2,000.00 N
                         100.000 $15.00000
                                             $0.00000
                                                             $1,500.00 N
0280 SUBDRAIN, PVC, STD,
                         100.000 $17.50000
                                             $0.00000
                                                             $1,750.00 N
0290 SUBDRAIN, PVC, STD,
                         100.000 $20.00000
                                                             $2,000.00 N
0300 SUBDRAIN, PVC, STD,
                                             $0.00000
0310 FLOWABLE MORTAR
                          959.000 $110.00000
                                             $0.00000
                                                           $105,490.00 N
                         183.000 $5.00000
                                                               $915.00 N
0320 ENGINEER FABRIC
                                              $0.00000
                          149.000 $40.00000
                                                             $5,960.00 N
0330 REVETMENT, CLASS E
                                             $0.00000
                         79,707.2 $4.00000
                                             $0.00000
                                                           $318,828.80 Y
0340 RMVL+CRUSH OF PAV'T
                                                            $36,000.00 Y
0380 MOBILIZATION
                            1.000 $36,000.00
                                              $0.00000
```

Form 830215wd (09-98)



lowa Department of Transportation

CO-PERMITTEE CERTIFICATION STATEMENT

Project No.: STP-S-C044(77)5E-44	
County: Henry	Proposal ID No.: 44-C044-077
Prime Contractor: Cedar Valley Corp., LLC	1
Subcontractor: Peterson Contractors, Inc.	
Address: 104 Blackhawk Street, PO Box A,	Reinbeck, IA 50669
Telephone No.: 319-345-2713	

I certify under penalty of law that I understand the terms and conditions of the general National Pollutant Elimination System (NPDES) permit that authorizes the storm water discharges associated with industrial activity from the construction site as part of this certification.

Further, by my signature, I understand that I am becoming a co-permittee, along with the owner(s) and other contractors and subcontractors signing such certifications, to the lowa Department of Natural Resources NPDES General Permit No. 2 for Storm Water Discharge Associated with Industrial Activity for Construction Activities at the identified site. As a co-permittee, I understand that I, and my company, are legally required under the Clean Water Act and the Code of Iowa, to ensure compliance with the terms and conditions of the storm water pollution prevention plan developed under this NPDES permit and the terms of this NPDES permit.

Signature:	and Q. Goterson	
Title:	president	
Date:	21000	

 Certification Statement shall be signed as follows: Corporation – president or vice-president Partnership – general partner Proprietorship - proprietor

Peterson
Contractors,
Inc.

Iowa Plains Signing, Inc.

Subcontractor: IOWA PLAINS SIGNING, INC. Subcontractor Vendor ID: IO250

Address: HWY 210 W Division of Labor Registration: N

P.O. BOX 654

SLATER, IA 50244-0654 Telephone No.: (515)685-3536

Line No. Item Description	Quantity	Unit Price	"A"	\$ Amount	Partial Item
0350 SAFETY CLOSURE	14.000	\$50.00000	\$0.00000	\$700.00	N
0360 PAINTED PAV'T MARK,	841.990	\$14.55000	\$0.00000	\$12,250.95	N
0370 TRAFFIC CONTROL	1.000	\$15,911.00	\$0.00000	\$15,911.00	N
Signature (Prime Contract	or)	Totals:	\$0.00 (a)	\$28,861.95	

lowa Plains Signing, Inc.

Form \$30215wd (09-09)



lowa Department of Transportation

CO-PERMITTEE CERTIFICATION STATEMENT

Project No.: STP-S-C044(77)5E-44	
County: Henry	Proposal ID No.: 44-C044-077
Prime Contractor: Cedar Valley Corp., I	LC.
Subcontractor: Iowa Plains Signing, Inc	in the second se
Address: 1110 W. 6th Avenue, P.O. Box	654, Slater IA 50244-0654
Telephone No.: 515-685-3536	

I certify under penalty of law that I understand the terms and conditions of the general National Pollutant Elimination System (NPDES) permit that authorizes the storm water discharges associated with industrial activity from the construction site as part of this certification.

Further, by my signature, I understand that I am becoming a co-permittee, along with the owner(s) and other contractors and subcontractors signing such certifications, to the Iowa Department of Natural Resources NPDES General Permit No. 2 for Storm Water Discharge Associated with Industrial Activity for Construction Activities at the identified site. As a co-permittee, I understand that I, and my company, are legally required under the Clean Water Act and the Code of Iowa, to ensure compliance with the terms and conditions of the storm water pollution prevention plan developed under this NPDES permit and the terms of this NPDES permit.

Signature:

Title:

Date: 3-/3-/6

 Certification Statement shall be signed as follows: Corporation – president or vice-president Partnership – general partner Proprietorship - proprietor

Country Landscapes, Inc.

Subcontractor: COUNTRY LANDSCAPES, INC. Subcontractor Vendor ID: CO825

Address: 56985 LINCOLN HIGHW Division of Labor Registration: Y

AMES, IA 50010-0000 Telephone No.: (515)232-6864

Line No.	Item Description	Quantity	Unit Price	"A"	\$ Amount	Partial Item
0380	MOBILIZATION	1.000	\$2,500.000	\$0.00000	\$2,500.00	Y
0390	MULCH	17.300	\$625.00000	\$0.00000	\$10,812.50	N
0400	SEED+FERTILIZE (RURA	17.300	\$650.00000	\$0.00000	\$11,245.00	N
0410	SILT FENCE	270.000	\$2.00000	\$0.00000	\$540.00	N
0420	SILT FENCE-DITCH CHE	330.000	\$2.50000	\$0.00000	\$825.00	N
0430	MAINT OF SILT FENC/S	300.000	\$0.25000	\$0.00000	\$75.00	N
0440	PERIMETER+SLOPE SEDI	260.000	\$3.25000	\$0.00000	\$845.00	N
0450	MOBILIZATION, EROSIO	1.000	\$500.00000	\$0.00000	\$500.00	N

Form 830215wid (09-08)

owa Department of Transportation

CO-PERMITTEE CERTIFICATION STATEMENT

Project No.: STP-S-C044(77)5E-44	
County: Henry	Proposal ID No.: _44-C044-077
Prime Contractor: Cedar Valley Corp., LLC	
Subcontractor: Country Landscapes, Inc.	
Address: 56985 Lincoln Highway, Ames, IA	50010
Telephone No.: 515-232-6864	

I certify under penalty of law that I understand the terms and conditions of the general National Pollutant Elimination System (NPDES) permit that authorizes the storm water discharges associated with industrial activity from the construction site as part of this certification.

Further, by my signature, I understand that I am becoming a co-permittee, along with the owner(s) and other contractors and subcontractors signing such certifications, to the lowa Department of Natural Resources NPDES General Permit No. 2 for Storm Water Discharge Associated with Industrial Activity for Construction Activities at the identified site. As a co-permittee, I understand that I, and my company, are legally required under the Clean Water Act and the Code of Iowa, to ensure compliance with the terms and conditions of the storm water pollution prevention plan developed under this NPDES permit and the terms of this NPDES permit.

Signati	ire: Settle K
Title:	Field Superintendent
Date:	2-29-2016

 Certification Statement shall be signed as follows: Corporation – president or vice-president Partnership – general partner Proprietorship - proprietor

Country
Landscapes,
Inc

Pollution Prevention Plan Storm Water Site Inspections

- Inspections required at least once every 7 days.
- Inspections are conducted jointly with a representative of both the contracting authority and the contractor AND both must sign the inspection form.
- Any deficiencies must be corrected within 3 days

Pollution Prevention Plan Storm Water Site Inspections

- Erosion control measures and inspections must be maintained through winter shut down.
- Prime Contractor must be prepared to install erosion control features if Subcontractor is not available.



STORM WATER SITE INSPECTION

Storm	Water
Si	te
Inspe	ection

nspection Date and Time:	
Project Number:	County:
DNR Authorization Number: IA	
Inspection Made By:	Title:
Comments and Observations:	
Deficiencies Found and Additions Required (Include Specific Locations):	
Contractor Notification (Name, Notification Date, and Time of Notification):	
Date of Corrective Action (Within 3 Days of Inspection) and Corrective Acti	on Performed:
certify under penalty of law that this document and all attachments were prepared under my direction or signalfied personnel properly gathered and evaluated the information submitted. Based on my inquiry of the directly responsible for gathering the information, the information submitted is, to the best of my knowledge significant penalties for submitting false information, including the possibility of fine and imprisonment for knowledge.	e person or persons who manage the system, or those persons and belief, true, accurate, and complete. I am aware that there are
Inspector's Signature:	Date:
Contractor's Signature:	Date:



STORM WATER SITE INSPECTION

Inspection Date and Time:	_
Project Number:	County:
DNR Authorization Number: IA	"
Inspection Made By:	
 Provide station ranges of areas inspected. Include types of erosion & sediment control measures (ESCM' dams, etc.). Note any ESCM's that were installed or areas where stabilization has o In lieu of listing all locations, you may include a reference to s from a field book. Record any areas where land disturbing activities have been to Every effort should be made to access all areas of the site, esp if you are unable to access some areas, then record these located to Document suspension of inspections and reason for suspension performed under another project/contract (e.g. if inspections covered under the grading project – note the suspension on the Document the station range if ceasing inspections on only in the station of the station of the station of the suspension on only in the station of the station of the station of the suspension on only inspections on only inspections. 	as been completed since previous inspection. specific IDR's or include a photocopy of notes temporarily or permanently suspended. becially critical areas (discharge points). However, ations. ion here, such as when inspections will be s began on a culvert project but will then be the last culvert inspection report).

Deficiencies Found and Additions Required (Include Specific Locations): Include any new ESCM's that are needed or existing ESCM's that require continuous may include station and Lt., Rt. or Med. o Information needs to be specific enough so deficiency could be located.				
 Note areas where stabilization is required. Document any locations of needed housekeeping items, such as off-site tracking that needs to be cleaned up. Include any issues of permit non-compliance, such as visible off-site sediment discharge. 				
Contractor Notification (Name, Notification Date, and Time of Notification):				
Types of Notification include direct, email, phone, fax, or written order.				
Date of Corrective Action (Within 3 Days of Inspection) and Corrective Action Performed:				
 If this section is filled in after date of signature below, then date this section. 				
I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.				
Inspector's Signature:	Date:			
Contractor's Signature:	Date:			



STORM WATER SITE INSPECTION

HENRY
Issist. to the Eng.
alled

Deficiencies Found and Additions Required (Include Specific Locations):
Contractor Notification (Name, Notification Date, and Time of Notification):
Date of Corrective Action (Within 3 Days of Inspection) and Corrective Action Performed:
I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.
Inspector's Signature: May My Date: 4/7/16
Contractor's Signature: Date: 4 7 16



STORM WATER SITE INSPECTION

Project Number: STP-S-CO44(77)5E-44	County: HENRY
Inspection Made By: Woyd M' Tutyr	Title: Assist to the Eng.
Dale Harrish was IDOT was on site identify site receion control No rain events	ing delicienties with
IVE PAIN QUEKTS	

Deficiencies Found and Additions Required (Include Specific Locations): Existing silt fences do not extend for enough, ditch checks are needed at all ditch locations leaving project site Exected silt fence areds to meet standards		
Contractor Notification (Name, Notification Date, and Time of Notification): Cedar Valley was notified Tom Bouner 4-15-16 8:00 any		
Date of Corrective Action (Within 3 Days of Inspection) and Corrective Action Performed: 4-19-16 Country Landscapes was fixing deficiencies 4-20-16 Constey Landscapes fixing deficiencies in 4/21/16		
I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.		
Inspector's Signature: Contractor's Signature: Date: 4-14-16 Date: 4-14-16		



STORM WATER SITE INSPECTION

Inspection Date and Time: 4-21-16		
Project Number: STP-S-CO44(77)5E-44	County: HENRY	
DNR Authorization Number: IA 28387 - 28130		
Inspection Made By: Lloyd McIntyre	Title: Assist to the Eng.	
Comments and Observations: Rainfall Wednesday April 20, 2016 Trace - 0.02		
Updated erosion control measures look	good	
Late Afternoon rains 2:30 pm - 4:00 pm approximately 0.06		

Deficiencies Found and Additions Required (Include Specific Locations):
Contractor Notification (Name, Notification Date, and Time of Notification):
Date of Corrective Action (Within 3 Days of Inspection) and Corrective Action Performed:
I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.
Inspector's Signature: Alex Date: 4-21-16
Contractor's Signature: Date: 421 (c

Form 830214 07-14



STORM WATER SITE INSPECTION

Inspections Made At Least Once Every Seven Calendar Days

Inspection Date and Time; JULY 8, 2016 @ 2:30pm	
Project Number: STP-S-CO44(77)5E-44	County: Henry
DNR Authorization Number: IA 28387 28130	
Inspection Made By: Lloyd McIntyre	Title: Assistant to the Eng.
Comments and Observations:	
Seturday July 2, 2016 - 0.02"	
Sunday July 3, 2016 - 0.06"	
Vednesday July 6, 2016 - 0.78"	
Thursday July 7, 2016 - 1,25"	
rosion Control measures are functioning properly	

Deficiencies Found and Additions Required (Include Specific Locations):
No deficiencies found or additions required at this time.
Contractor Notification (Name, Notification Date, and Time of Notification):
Date of Corrective Action (Within 3 Days of Inspection) and Corrective Action Performed:
certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. Date: 7 - 8 - 16
Contractor's Signature: Date: 7-8-76 Date: 7/8/16

Notice of Discontinuation

After 70% of the permanent seeding has been established a Notice of Discontinuation is submitted.

NOTICE OF DISCONTINUATION



OF A STORM WATER DISCHARGE COVERED UNDER IOWA NPDES GENERAL PERMIT NO. 2 FOR CONSTRUCTION ACTIVITIES

Name of the owner or facility to which the storm water discharge general permit coverage was issued. Herry County Secundary Roads				
		County: Hen	4	
List the complete permit authorizate authorization sheet.	tion number for the discha	rge. This number is provided	on the bottom of the	
		ia - <u>28387 </u>	28/30	
List the date the construction site re	eached final stabilization a	us defined on the back of this	form. 15/16	
The following certification must be back side).	e signed in accordance wi	th the signatory requirements	of the general permit (see	
I certify under penalty of law that of erosion and sediment control meass that by submitting this Notice of I with industrial activity for construct No. 2 and that discharging polluta States is unlawful under the Clean	ures have been removed on Discontinuation, I am no stion activities by Iowa De onts from storm water asso	or will be removed at an appro- longer authorized to dischar- partment of Natural Resource ociated with industrial activity	operate time. I understand ge storm water associated as NPDES General Permit by to waters of the United	
I further certify under penalty of a supervision in accordance with a sy the information submitted. Based of directly responsible for gathering to belief, true, accurate, and complete including the possibility of fine and	ystem designed to assure to on my inquiry of the perso the information, the infor I am aware that there ar	hat qualified personnel proper on or persons who manage the mation submitted is, to the b e significant penalties for sub	rly gathered and evaluated e system, or those persons est of my knowledge and	
Jako Hotch Kiss	Name (print)	Henry County &	AGINEEZTIILE	
Jr IL	Signature	Henry County &	Date	
	Storm Water Coordinat Department of Natural 502 E. 9th Street Des Moines, IA 50319-	Resources		

542-8115

(over)

CM 7.10 Permanent Erosion Control

- Urban & Rural seeding:
 - March 1 to May 31
 - August 10 to September 30
- Native & Wetland Grass seeding
 - April 1 to June 30
 - Effective April 14, 2014 letting:
 - April 1 to May 31 and
 - November 1 to unsuitable conditions or frost
- Wildflower seeding:
 - April 15 to June 30

CM 7.10 Permanent Erosion Control

 Seeding date extension notices will be posted on the Office of Construction and Materials website at:

http://www/iowadot.gov/Construction_Materials/earthwork.html

CM 7.30 Mulch


- All permanent seeding with prepared seedbeds are required to be mulched.
- The mulch shall be "blown" and "tucked in" as soon after seeding as possible.
- Weight tickets are required for all mulch.
- All mulch shall be Certified Noxious Weed Seed Free Mulch as certified by the Iowa Crop Improvement Assoc. (ICIA).

http://www.iowacrop.org/Week Free.htm


CM 7.42 Mobilization for Erosion Control

- Article 2602.03, L
 - Mobilizations, Erosion Control, applies to projects not identified as erosion control or landscaping and contain a Storm Water Pollution Prevention Plan (SWPPP).

Should Mobilizations for Erosion Control apply to the project?



Is an Erosion Control Implementation Plan (ECIP) required?



Article 2602.03, L. Mobilizations, Erosion Control

- Only one mobilization will be paid for each stage of work described in the ECIP.
- Additional mobilizations not outlined in the ECIP must be approved by the Engineer.
- Payment for mobilization to correct items not properly installed will not be approved.

Article 2602.03, L. Mobilizations, Erosion Control

- Mobilize within 72 hours of a written order.
- Complete work within 7 calendar days of a written order.
- Failure to mobilize and complete work within such time period, will result in a deduction of \$750.00 per calendar day.

Article 2602.03, M. Mobilizations, Emergency Erosion Control

- Emergency work requires immediate mobilization ... followed by immediate installation of temporary erosion control measures.
- Mobilize ... within eight hours of Engineer's written order to install temporary erosion control items on an emergency basis.
- Failure to mobilize within eight hours of written order, will result in a deduction of \$1500.00 per calendar day.

Article 2602.03, M. Mobilizations, Emergency Erosion Control

- The form 830214 contains the following questions:
 - Can Correction Action(s) be made within 72
 hours after inspection? If no document why it
 is impracticable. Note: The permit requires
 Corrective Action be completed within 7 calendar
 days of the inspection.
 - Date of corrective action (start within 3 days of inspection) ...

Article 2602.0, B. Payment for Mobilizations

- Mobilizations, Erosion Control
 - The quantity will be paid for at the unit price of \$500.00 each for Mobilizations, Erosion Control
- Mobilizations, Emergency Erosion Control
 - The quantity will be paid for at the unit price of \$1000.00 each for Mobilizations, Emergency Erosion Control

Country Landscapes, Inc.

Subcontractor: COUNTRY LANDSCAPES, INC. Subcontractor Vendor ID: CO825

Address: 56985 LINCOLN HIGHW Division of Labor Registration: Y

AMES, IA 50010-0000 Telephone No.: (515)232-6864

Line No.	Item Description	Quantity	Unit Price	"A"	\$ Amount	Partial Item
0380	MOBILIZATION	1.000	\$2,500.000	\$0.00000	\$2,500.00	Y
0390	MULCH	17.300	\$625.00000	\$0.00000	\$10,812.50	N
0400	SEED+FERTILIZE (RURA	17.300	\$650.00000	\$0.00000	\$11,245.00	N
0410	SILT FENCE	270.000	\$2.00000	\$0.00000	\$540.00	N
0420	SILT FENCE-DITCH CHE	330.000	\$2.50000	\$0.00000	\$825.00	N
0430	MAINT OF SILT FENC/S	300.000	\$0.25000	\$0.00000	\$75.00	N
0440	PERIMETER+SLOPE SEDI	260.000	\$3.25000	\$0.00000	\$845.00	N
	MOBILIZATION, EROSIO	1.000	\$500.00000	\$0.00000	\$500.00	N

Erosion Control Implementation Plan (ECIP) Worksheet

Project No.:		
County:		
Type of Work:		
Prime Contractor:		
Water Pollution Control Manager (WPCM):		
-	□ ЕСТ	☐ ESC Basics
Phone:		
Erosion Control Tec	hnician (ECT) and Certificat	ion Number (unless satisfied by WPCM):

Additional ESC Basic	cs Trained Individual(s) and Company:
Subcontractor respo	nsible for installation & maintenance of erosion/sediment controls:
Name:	
Company:	
Address:	
Phone:	

Description of intended schedule and sequence of major land disturbing and erosion/sediment control activities (include number of mobilizations if required by specification): Include staging and maintenance, method for winter shutdown and removal of temporary measures (if required for the project). Describe any additional measures that are needed due to late season work. Describe measures necessary to control erosion based on your schedule or sequence of operations. Explain how you plan to implement erosion control plan in stages. Indicate measures that must be in place before grading begins. Based on your staging, are there areas where additional erosion control beyond that shown in the plans is anticipated? If so, provide information.

Other:
Describe dewatering methods and locations. What controls will be used at the outlet?
Provide information regarding location and protection of stockpiles.
•
Updates:
Update ECIP to address changes in the order of operations or staging, weather changes, or any other changes required to comply with permit requirements.
Update ECIP to address changes in the number of mobilizations.

ECIP UPDATE CHECKLIST

	Install	Maintain	Remove	Location(s) and Schedule
Silt Fence				
Silt Fence Ditch Check				
Perimeter & Slope Sediment Control Device				
Rock				
Silt Basin				
Stabilizing Seeding & Mulching				
Permanent Seeding & Mulching				
Other:				
Other:				

CM 7.43 Erosion & Sediment Control Training & Certification

- The Contractor is required to have an Erosion & Sediment Control Basics trained individual onsite daily during construction activities (may be subcontractor).
 - Document in the daily diary
- On projects where there is a NPDES storm water permit, the Contractor is required to have an Erosion Control Technician on staff.
 - Effective April 15, 2014 letting

CM 7.43 Erosion & Sediment Control Training & Certification

- Additional information can be obtained at <u>http://iowadot.gov/Construction Materials/eart hwork/ESControl training.html</u>
- A list of Erosion Control Technicians can be found at:
 - http://iowadot.gov/training/ttcp/cert.tech.pdf
- A list of Erosion Control Basics training technicians can be found at:
 - http://iowadot.gov/training/ttcp/Erosion%20Control%20Basic.pdf

- Contractor must designate a Water Pollution
 Control Manager (WPCM) prior to initiating
 any construction activities.
 - Must be Iowa DOT Erosion & Sediment Control Basics (ESC Basics) web-based trained or hold a current Erosion Control (ECT) certification
- Point of contact for Contracting Authority regarding storm water compliance.

- Visit the Project no less than once per week during construction activities.
 - When the Contractor is not mobilized onsite, the Contractor may delegate this responsibility to a subcontractor.

- Maintain an ESC Basics training individual that will be onsite daily during construction activities.
 - Responsible for coordinating all erosion and sediment control operations.
 - The Contractor may subcontract this responsibility.

- Maintain an ESC Basics training individual that will be onsite daily during construction activities.
 - Responsible for coordinating all erosion and sediment control operations.
 - The Contractor may subcontract this responsibility.

- ESC Basics trained individual (can be the WPMC) that shall not be subcontracted include:
 - Attend required storm water inspections with the Contracting Authority.
 - Prepare required initial Erosion Control Implementation Plan (ECIP) submittal and ECIP updates.
 - Attend construction progress meetings to discuss erosion and sediment control issues.



This is to certify that

THOMAS C BONNER

has successfully met the testing requirements and is recognized as a

Certified Erosion Control Technician

Program Director

12/31/18

EC921

Expiration Date

Certificate No.



- How often must Storm Water Site Inspections be performed?
 - ➤Once every seven calendar days.
- If there are deficiencies found during a Storm Water Site Inspection, by the Permit what time frame is allowed for corrections?
 - ➤ Permit requires correction actions be completed within seven calendar days following inspection.

- Which subcontractors need to have signed Co-Permit Certification Statements on file?
 - Any subcontractors performing work that could either have potential for erosion or that are performing work to prevent erosion from happening.
- What form is completed once soil disturbing activities are completed and at least 70% of permanent seeding has been established?
 - ➤ Notice of Discontinuation

- What are the normal periods (dates) for permanent urban and rural seeding?
 - ➤ March 1 to May 31 and August 10 to September 30.
- What are the normal periods (dates) for permanent urban and rural seeding?
 - April 1 to May 31 and November 1 until ground conditions are unsuitable for seeding due to moisture or frost.

 If there is a major rain event that causes the erosion control measures to fail (an emergency event) and the contractor is notified to come to the site and make corrections, what is the cost for that mobilization to occur?

>\$1000.00

- If the contractor fails to respond within eight hours of the Engineer's written order to install temporary erosion control items for an emergency event, what action will be taken?
 - Failure to mobilize within eight hours of written order, will result in a deduction of \$1500.00 per calendar day.

- Who is the point of contact for Contracting Authority regarding storm water compliance?
 - The Contractor's Water Pollution Control Manager (WPCM).