



**SPECIAL PROVISIONS
FOR
EXCAVATION FOR STRUCTURES IN LEVEE CRITICAL AREA**

**Pottawattamie County
IM-NHS-029-3(102)48--03-78**

**Effective Date
December 16, 2014**

THE STANDARD SPECIFICATIONS, SERIES 2012, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

120218.01 DESCRIPTION.

The work under this contract is located adjacent to federally constructed levees along the Mosquito Creek and Missouri River. As such, no improvement shall be passed over, under, or through the levees, improved channels or floodways, nor shall any excavation or construction be permitted within the limits of the levees other than the construction under this contract and these special provisions without prior approval of the U.S. Army Corps of Engineers (USACE). The limits of the levee critical area are 300 feet riverward and 500 feet landward of the levee. The following construction elements fall within these limits: Storm Sewer construction and removals, sanitary construction and removals, bridge foundation removals.

120218.02 WORK ZONE REQUIREMENTS.

Areas within these limits disturbed by excavation, other intrusions or disturbances of the soil shall be restored as described in this special provision. Any excavation within the levee critical area limits that is not directly related to bridge foundation removal, storm sewer construction or removal, or sanitary sewer construction or removal shall not commence without prior approval of the Engineer and the USACE.

120218.03 CONSTRUCTION.

A. Storm Sewer Construction and Removals.

Storm Sewer construction and removals shall be completed within the levee critical area as per the contract documents. Storm Sewer construction and removals within the levee critical area limits shall be by open excavation as follows:

- Open excavation shall consist of 2 Horizontal:1 Vertical side slopes.
- Disturbed soils shall be excavated, sorted by soil type, classified and stockpiled.
- Backfill shall be placed in the excavation as it was encountered in the initial excavation.

B. Sanitary Sewer Construction and Removals.

Sanitary Sewer construction and removals shall be completed within the levee critical area as per the contract documents. Storm Sewer construction and removals within the levee critical area limits shall be by open excavation as follows:

- Open excavation shall consist of 2 Horizontal:1 Vertical side slopes.
- Disturbed soils shall be excavated, sorted by soil type, classified and stockpiled.
- Backfill shall be placed in the excavation as it was encountered in the initial excavation.

C. Bridge Structure Removal.

Bridge structure removal shall be completed within the levee critical area as per the contract documents. As such, no excavation or penetration of the existing ground beyond the limits as per the contract documents will be permitted. Excavations for removal shall be by open excavation as follows:

- Open excavation shall consist of 3 Horizontal:1 Vertical side slopes within the levee section and 2 Horizontal:1 Vertical side slopes within the levee critical area.
- Excavated soils shall be sorted by soil type, classified and stockpiled.
- The sand backfill shall be placed in the excavation as they were encountered in the initial excavation.
- The clay backfill shall be placed in the excavation as they were encountered in the initial excavation.
- All backfill within the levee section shall consist of lean clay, as defined below.

D. Materials.

1. If borrow is needed to complete the backfill, it shall be comprised of lean clay (CL). Lean clay shall consist of cohesive materials having at least 50% passing the U.S. Standard 200 mesh sieve size, a Plasticity Index of 10 or greater, and falling between the "U" line and the "A" line on Figure 4 in ASTM D 2487 – Standard Tests for Classifications of Soils for Engineering Purposes, and a Liquid Limit less than 50.
2. Moisture and density control of the backfill shall be based on the standard Proctor compaction test (Materials I.M. 309). Cohesive materials shall be compacted to a density of at least 95% of the maximum dry density and be within -1% to +4% of the optimum moisture content at the time compactive effort is applied, which may require the addition of water or aeration of materials. Non-cohesive materials shall be placed in a moist condition and compacted with approved equipment to a density of at least 95% of the maximum dry density. Sampling backfill shall be in accordance with Materials I.M. 312. Testing of the backfill shall be performed for each 2 vertical feet of fill at a maximum horizontal spacing of 200 feet.

E. Quality Control Program.

1. Provide and maintain a Quality Control Program for construction of backfill. This is defined as process control sampling, testing, and inspection as described in Materials I.M. 540 for construction of embankments with moisture and density control.
2. Provide a Quality Control Technician who is responsible for all process control sampling, testing, and inspection. The Quality Control Technician shall obtain Soils Technician certification through the Iowa DOT Technical Training and Certification Program (TTCP).
3. Provide a laboratory facility and necessary calibrated equipment to perform required tests.
4. Notify the Engineer when a moisture content falls outside specified control limits or density falls below required minimum. If a moisture content falls outside control limits, fill material in this area will be considered unacceptable for compaction. Perform corrective action(s) to bring uncompacted fill material within control limits. If material has been compacted, disk it, bring to within control limits, and re-compact. When project has a density requirement, if an in-place density does not meet the requirements, compacted fill material in this area will be considered unacceptable. Perform corrective action(s) to material to meet density

requirements. Compensation will not be allowed for delays resulting from moistening, diskings, or re-compacting.

120218.04 METHOD OF MEASUREMENT.

Measurements for Storm Sewer Construction will be as specified in the pay item Storm Sewer Gravity Main, Reinforced Concrete Pipe (RCP), 3750D (Class V), 48 In. and Storm Sewer Gravity Main with Casing Pipe, Trenched, Reinforced Concrete Pipe (RCP), 2000D (Class III), 48 in.

120218.05 BASIS OF PAYMENT.

- A. All costs associated with the excavation and backfilling with moisture and density control for Storm Sewer Construction shall be included in the price bid for Storm Sewer Gravity Main, Reinforced Concrete Pipe (RCP), 3750D (Class V), 48 In. and Storm Sewer Gravity Main with Casing Pipe, Trenched, Reinforced Concrete Pipe (RCP), 2000D (Class III), 48 in.
- B. Payment is full compensation for furnishing a Quality Control Technician, sampling and testing, process control inspection, drying material, furnishing and applying water, controlling moisture content of the materials, and compacting the materials, as specified.