



**SPECIAL PROVISIONS
FOR
TEMPORARY TRAFFIC SIGNALS**

**Scott County
IM-NHS-074-1(206)5--03-82**

**Effective Date
October 16, 2018**

THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

150439.01 DESCRIPTION.

This work shall consist of all labor, materials, and equipment necessary to install traffic signal coordination equipment for the temporary traffic signal at the intersection of Mississippi Boulevard and 14th Street and the existing traffic signal at the intersection of US 67 (Grant Street) and the I-74 Westbound Ramps.

150439.02 MATERIALS AND METHOD OF CONSTRUCTION.

- A.** The contractor shall be responsible for installing the proposed interconnect equipment necessary for the communication and coordination of the two traffic signals.
- B.** The contractor shall make modifications or additions to the existing controller at the intersection of US 67 and the I-74 westbound ramps to facilitate this coordination. This may include the installation of a radio antenna on an existing mast arm structure or utility pole structures in accordance with the manufacturer's recommended practices.
- C.** All materials and installation locations must be presented to and approved by the Engineer prior to the installation of the temporary traffic signal interconnect.

150439.03 METHOD OF MEASUREMENT AND BASIS OF PAYMENT.

This work will not be paid for separately, but shall be included in the contract unit price for Each for Temporary Traffic Signals. The price shall be payment in full for all labor, equipment, and materials required to furnish, install, and test the operation described above.