



**SPECIAL PROVISIONS  
FOR  
INTEGRAL THIN VENEER BRICK FOR STRUCTURAL CONCRETE**

**Poweshiek County  
IM-NHS-080-5(355)183--03-79**

**Effective Date  
January 22, 2020**

**THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.**

**150601.01 DESCRIPTION.**

This specification describes the requirements for using integral thin veneer brick and a compatible form liner gasket system for installation within forms for vertical cast-in-place structural concrete.

**150601.02 MATERIALS.**

**A. Manufacturers.**

1. Thin Veneer Brick Form Liner Gasket System Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Scott System, Inc.
  - b. Architectural Polymers
  - c. United Wall Systems
  - d. Other manufacturers submitted to the Iowa DOT, Bridges and Structures Bureau for review and approval.
  
2. Thin Veneer Brick Unit Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Metro Brick by Ironrock Capital
  - b. Summitville Tile Co.
  - c. Feldhaus Thin Brick
  - d. Endicott Clay Products Co.
  - e. Röben Tonbaustoffe
  - f. Other manufacturers submitted to the Iowa DOT, Bridges and Structures Bureau for review and approval.

**B. Thin Veneer Brick Form Liner Gasket Materials.**

1. Single or multi-use template system for vertical poured concrete walls. Modular templates formed of styrene plastic or polyurethane to securely surround individual thin veneer brick units, having factory-applied face wax or other bond breaker.
2. Maximum variation from indicated nominal dimensions of brick cavities:
  - a. Length:  $\pm 1/32$  inch.
  - b. Height:  $\pm 1/32$  inch.
  - c. Depth:  $\pm 1/32$  inch.
3. Maximum variation from square, measured diagonally across non-adjacent corners:  $\pm 1/16$  inch.
4. Coursing: soldier course as indicated in the plans.

**C. Thin Veneer Brick Units.**

1. Exterior grade thin brick shall meet the requirements of ASTM C 1088, Type TBX (Select). When the allowable thin brick unit tolerance values indicated by the thin veneer brick form liner gasket system manufacturer's recommendations are different than those specified for Type TBX, the more stringent of the two tolerance requirements shall apply.
2. Size: Normal (modular) 2 1/4 inches high by 7 5/8 inches wide by 9/16 to 3/4 inch thick.
3. Color and Texture: As indicated in the plans, and subject to approval of submitted samples. All thin veneer brick used in the Project shall be from a single production run to ensure color and texture uniformity. Corner bricks (if used) shall match normal bricks in both color and texture.
4. Bond Breaker: Thin veneer brick units shall have factory-applied face wax or other bond breaker to prevent grout staining of the brick faces. Bond breaker shall be approved for use with the form liner gasket system by the form liner manufacturer.
5. Additional Furnish-Only Thin Bricks: Include 40 additional thin veneer brick units from the same production run as the furnished and installed units for future patching operations. 20 units shall be normal modular bricks, and 20 shall be corner bricks. All bricks provided shall be the red-brown color specified in the plans. Deliver materials in manufacturer's unopened packaging to a site as directed by the Engineer.

**D. Accessories.**

1. Plastic or foam bricks for tie hole locations (if needed), sized to securely fit form liner gasket and to create voids of appropriate dimensions for installation of grouted patch brick units following stripping of forms.
2. Epoxy grout in accordance with manufacturer's recommendations for the setting of patch bricks into defects and tie hole voids. Epoxy grout shall be non-leaching.
3. Other accessories as recommended by the manufacturer.

**E. Quality Assurance.**

1. Manufacturer Qualifications: Firm(s) experienced in manufacturing thin veneer brick form liner gaskets and thin veneer brick units similar to those indicated for this project and with a record of successful in-service performance, as well as sufficient production capacity to manufacture required units.

2. Source Limitations for Form Liner Gaskets: Obtain form liner gaskets through one source from a single manufacturer.
3. Source Limitations for Thin Veneer Brick Materials: Obtain thin veneer brick units through one source from a single manufacturer, and from a single production run for the entire Project to ensure color and texture uniformity.

**F. Product Delivery, Storage and Handling.**

1. Do not use damaged products. Do not install products not bearing product trade name and manufacturer's name.
2. Store all installation materials in manufacturer's unopened packaging in a dry storage area, with ambient temperature between 30°F and 120°F until installation. Protect all materials from exposure to sun, rain, dirt and dust until installation.
3. Do not top load or otherwise crush form liners in their packages.

**150601.03 CONSTRUCTION.**

**A. Submittals.**

The following shall be submitted to the Engineer for approval.

1. Product Data: Manufacturer's data sheets on each product to be used including:
  - a. Preparation instructions and recommendations.
  - b. Storage and handling requirements and recommendations.
  - c. Installation methods.
  - d. Cleaning methods following form removal.
  - e. Patching methods.
2. Shop Drawings: Submit elevation drawings and details that indicate:
  - a. Horizontal and vertical brick coursing.
  - b. Alignment of brick coursing to adjacent construction.
  - c. Corner details (if required).
  - d. Construction joints.
  - e. Brick color and texture.
  - f. Special conditions.
3. Selection Samples: For each finish product specified, one complete set of samples, representative of full range of color and finish for each brick type. Include a written submittal document with the manufacturer and supplier names, brick color name(s) or number(s), and brick finish type(s) listed.
4. Verification Samples: For each finish product specified, two samples, representative of selected range of color and finish for each brick type. Include form liner sample and bond breaker sample applied to full size thin veneer brick, representing bond breaker to be used. Include a written submittal document with the manufacturer and supplier names, brick color name(s) or number(s), and brick finish type(s) listed.

**B. Mockups.**

Construct mockups meeting the following requirements.

**1. Mockup.**

Construct a mockup with the dimensions and features shown in the plans. Mockup is to be located near the jobsite but shall not become part of the final construction. Use construction methods identical to those intended for final production. Demonstrate brick

void epoxy grout patching method on the mockup. No production thin veneer brick work shall proceed until approval of the mockup by the Engineer. Rebuild mockup as required to produce acceptable work.

**2. Mockup Removal.**

Upon completion of the project, the mockup shall become the property of the Contractor and shall be removed from the site.

**C. Forming.**

1. Do not begin installation until concrete forms have been properly prepared.
2. If form ties are necessary within the brick zones indicated in the plans, coordinate location of ties with the form liner gasket system. Ties shall be located only within brick cavities of liner. Adjust position of ties, not form liner, as necessary to avoid conflicts with liner.
3. Coordinate installation of form liner gasket system with installation of required form inserts, rustication strips, construction joints, etc. as shown in the plans.

**D. Installation of Form Liner Gasket System.**

1. Thoroughly clean form surfaces prior to installation.
2. Prepare, install, and finish form liner gasket system in accordance with manufacturer's recommendations, and with guidance from the manufacturer's on-site representative.

**E. Installation of Thin Veneer Brick Units.**

1. Clean brick pockets free of all foreign material prior to setting thin bricks. Take special care not to damage the form liner gasket system during cleaning.
2. Install thin brick units in accordance with form liner gasket system manufacturers written instructions and with guidance from manufacturer's on-site representative.
3. When more than one color or texture brick is used to create a single color brick field with variations, mix the different thin brick units prior to installing into gaskets so that color or texture differences are randomly patterned in the finished surface.
4. Ensure that all thin brick units are securely held in form liner gasket system.
5. Remove and replace any individual form liner gasket module that does not securely hold the thin veneer brick. Remove and replace any individual form liner gasket module if the thin brick unit falls out of it for any reason. Remove and replace any individual form liner gasket module if the thin brick is purposely removed from it for any reason.
6. If allowed by the manufacturer, glue may be used to aid in securing thin veneer bricks in place within the form liner gasket system. Use only approved glue as recommended by the manufacturer, and only with guidance from the manufacturer's on-site representative.

**F. Installation Tolerances.**

1. Maximum variation in alignment of horizontal or vertical mortar joints: 1/4 inch in 10 feet, non-cumulative.
2. Maximum offset in plane of adjacent form liner units: 1/16 inch.

3. Maximum misalignment between adjacent form liner units: 3/64 inch.

#### **G. Loading of Forms.**

Load forms with concrete according to the Standard Specifications and the following:

1. Do not drop concrete directly upon thin veneer brick during loading of vertical concrete forms.
2. Do not touch thin veneer brick with internal vibrators (stingers).
3. Do not externally vibrate forms or strike the outside of forms with heavy objects.
4. Take particular care to ensure consolidation of concrete into all joint spaces between thin bricks.

#### **H. Stripping and Cleaning.**

1. Remove the form liner gaskets immediately following stripping of the concrete forms. If approved by the form liner gasket system manufacturer, power washing may be used to aid removal of the gaskets from the brick surfaces.
2. Immediately following form stripping and form liner removal, commence power washing of brick surfaces in accordance with the manufacturer's recommendations and with guidance from the manufacturer's on site representative. Use water pressure and temperature recommended by the manufacturer. Washing operations shall remove all concrete mortar leakage, thin veneer brick face wax or bond breaker, and any remaining form liner gasket components.
3. Do not re-use single-use brick gaskets on the project. Do not re-use any multi-use brick gaskets that are warped, cracked, torn, folded, crushed, or show other signs of damage. Replace any gaskets as directed by the Engineer.

#### **I. Patching.**

1. Clean and prepare defects, including form tie voids and lost brick zones, if any, in accordance with manufacturer's recommendations, and with guidance from the manufacturer's on site representative. Concrete in any areas from which brick dropped out of form liner gasket prior to or during concrete pour must be carefully chipped out to create a pocket similar to an intentional block-out and prepared for patch brick installation. Do not damage surrounding brick or concrete during preparation of brick pocket.
2. Securely grout thin veneer bricks into voids using epoxy grout in accordance with manufacturer's recommendations, and with guidance from the manufacturer's on site representative. Tool and finish patched brick grout to blend with surrounding grout lines. Immediately clean any mortar from brick faces before staining can occur.
3. Patch brick installation tolerances:
  - a. Maximum offset of patch brick face to plane of adjacent brick faces: 1/16 inch.
  - b. Maximum misalignment of patch brick relative to adjacent bricks: 1/16 inch.
  - c. Maximum variation in mortar joints surrounding patch brick: 1/16 inch.

#### **150601.04 METHOD OF MEASUREMENT.**

The work of furnishing and installing Integral Thin Veneer Brick will be based on plan quantities in square feet and will not be measured.

**150601.05 BASIS OF PAYMENT.**

For the number of square feet of Integral Thin Veneer Brick shown in the plans, the Contractor will be paid the contract unit price per square foot. Payment for Integral Thin Veneer Brick shall be full compensation for all materials, labor, tools, equipment, testing, inspection, services, accessories, and incidentals necessary to perform the work of this section. Payment for Integral Thin Veneer Brick shall also include the furnishing of additional thin brick units (if required) for future patching operations.