



**SPECIAL PROVISIONS  
FOR  
SITE REMOVALS, SALVAGING AND REINSTALLATIONS**

**Clayton County  
STPN-076-1(16)--2J-22**

**Effective Date  
November 16, 2021**

**THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.**

**150772.01 DESCRIPTION.**

This work consists of general site removals to allow for replacement and/or installation of new infrastructure improvements. This section includes the furnishing of all labor, materials, permits, tools, equipment, and all work and services necessary or incidental to the removal, salvaging and/or reinstallation of existing miscellaneous items and materials located within the project area not covered under other project line items.

**150772.02 MATERIALS.**

**A. Removal materials includes:**

1. Concrete Steps
2. Vertical Face Sidewalk
3. Concrete Light Bases

**B. Removal and reinstall materials include:**

1. Street Signs
2. Street Light Pole & Luminaire
3. Decorative Clock
4. Decorative Steel Railing

**C. Salvage material includes the existing brick pavers.**

**150772.03 CONSTRUCTION.**

**A. General.**

Removal of all items shall follow approved recycling and/or disposal methods for respective materials and items. Contractor shall be responsible for obtaining all permits and paying all fees associated with disposal of items and materials under this section.

**B. Removal of Concrete Steps.**

Remove and dispose of concrete steps at locations designated on the plans.

**C. Removal of Vertical Face Sidewalk.**

Remove and dispose of vertical face sidewalk at locations designated on the plans. Removal of decorative steel railing shall occur prior to sidewalk removal to protect railing.

**D. Removal of Concrete Light Bases.**

1. Remove and dispose of concrete light pole bases at locations designated on the plans. Removal of light poles and luminaires shall occur prior to concrete base removal. Protect wiring until the construction of new concrete base.

2. Concrete bases that are not removed shall be reused.

**E. Removal and Reinstallation of Street Signs.**

1. Existing signs shall be removed and re-installed at locations designated on the plans to allow for staging during construction.

2. The signs to be removed and reinstalled shall be done so as to utilize the same signs and post without damaging. The installation of the signs shall be done in-kind as is currently provided. Any defective or damaged material shall be replaced by the Contractor at no additional expense.

**F. Removal and Reinstallation of Streetlight Poles & Luminaires.**

1. Existing streetlight poles and luminaires shall be removed and reinstalled at locations designated on the plans.

2. Reinstall streetlight pole and luminaires in the same exact locations they were located prior to construction. Prior to removal, the streetlight poles shall be labeled, and the location recorded. Coordinate closely with the Contracting Authority during the recording and removal process.

3. Coordinate with the Contracting Authority regarding the storage location of the streetlight pole and luminaires during construction. Any defective or damaged streetlight components shall be replaced by the Contractor at no additional expense.

4. It is the responsibility of the Contractor to rewire and anchor the light pole to the new or existing concrete bases after construction is complete.

**G. Removal and Reinstallation of Decorative Clock.**

The existing decorative clock shall be removed and reinstalled at the location designated on the plans. Protect the existing concrete base during removal and construction.

**H. Removal and Reinstallation of Decorative Steel Railing.**

The existing decorative steel railing shall be removed and reinstalled at the locations designated on the plans. Coordinate with the Contracting Authority regarding the storage location of the steel railing during construction.

**I. Salvage of Existing Brick Pavers.**

There is a layer of brick pavers underneath certain portions of the existing IA-76 pavement. Salvage any pavers encountered during the pavement removal process. Coordinate with the Contracting Authority to determine location to haul and store the salvaged brick pavers. The Contracting Authority maintains salvage rights to all material, as indicated by Engineer.

**150772.04 METHOD OF MEASUREMENT.****A. Removal of Concrete Steps.**

Removal of the existing concrete steps shall be measured in square yards.

**B. Removal of Vertical Face Sidewalk.**

Removal of vertical face sidewalk shall be measured in linear feet.

**C. Removal of Concrete Light Bases.**

Each light base removed shall be counted.

**D. Removal and Reinstallation of Street Signs.**

Each street sign removed and reinstalled shall be counted.

**E. Removal and Reinstallation of Streetlight Poles & Luminaires.**

Each streetlight pole and luminaire removed and reinstalled shall be counted.

**F. Removal and Reinstallation of Decorative Clock.**

Each decorative clock removed and reinstalled shall be counted.

**G. Removal and Reinstallation of Decorative Steel Railing.**

Removal and reinstallation of decorative steel railing shall be measured in linear feet.

**H. Salvage of Existing Brick Pavers.**

Salvage of brick pavers shall be measured in square yards.

**150772.05 BASIS OF PAYMENT.**

For all items listed below, payment is full compensation for furnishing all tools, equipment, labor, and materials for completion of the work as specified in the contract documents.

**A. Removal of Concrete Steps.**

Payment will be the contract unit price per square yard of existing concrete steps removed.

**B. Removal of Vertical Face Sidewalk.**

Payment will be the contract unit price per linear foot of vertical face sidewalk removed.

**C. Removal of Concrete Light Bases.**

Payment will be made at the contract unit price for each concrete base removed.

**D. Removal and Reinstallation of Street Signs.**

Payment will be made at the contract unit price for each street sign removed and reinstalled.

**E. Removal and Reinstallation of Streetlight Poles & Luminaires.**

Payment will be made at the contract unit price for each streetlight pole & luminaire removed and reinstalled. Payment includes the labeling and recording of location, hauling and storing, wiring and anchoring to reinstall.

**F. Removal and Reinstallation of Decorative Clock.**

Payment will be made at the contract unit price for each decorative clock removed and reinstalled. Payment includes hauling and storing, wiring and anchoring to reinstall.

**G. Removal and Reinstallation of Decorative Steel Railing.**

Payment will be made at the contract unit price per linear foot. Payment is full compensation for removal, hauling to storage location, materials and equipment required for reinstalling and anchoring the railing.

**H. Salvage of Existing Brick Pavers.**

Payment will be made at the contract unit price square yard. Payment is full compensation for salvaging and hauling to storage location.