



**SPECIAL PROVISIONS
FOR
ITS INFRASTRUCTURE INSTALLTION**

**Polk County
ITS-035-4(298)95--25-77**

**Effective Date
July 19, 2022**

THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

150869.01 DESCRIPTION.

A. Related Specifications and Standards.

The work as detailed on the contract documents shall be completed in accordance with the contract documents and the documents listed below.

- NEC, latest edition adopted by the State of Iowa.
- Telecommunications Industry Association/Electronic Industries Association (TIA/EIA) latest editions.

B. Contractor Submissions.

1. Material List.

Complete and submit one electronic pdf file of the materials list to the Engineer within 14 calendar days after award of the project contract. Include the name of the materials, supplier and catalog number of each item listed.

2. Construction Schedule.

- Within 30 days after award of contract or before the construction kickoff meeting, submit to the Engineer one electronic pdf file of the detailed construction schedule including dates of commencement for each major work item, duration of each major work item and completion of each major work item on each segment of the proposed construction.
- Major items of work to be included on the schedule shall include, but is not limited to the following:
 - Duration of material procurement
 - Installation of conduit, handholes, and fiber optic cable
 - Duration of fiber testing and submission of test reports
- The construction schedule shall comply with Section 1108 of the Standard Specifications. In addition to limitations of operations in Article 1108.03 of the Standard Specifications, do not perform work that may result in an unplanned network disruption during the ICN moratorium. Request moratorium dates from ICN within 14 calendar days after award of the project contract.

- d. Coordinate with the ICN Network Operations Center (NOC) to schedule all splicing work.
- e. Upon acceptance of the schedule, adhere to these dates as proposed unless modified with the approval of the Engineer.
- f. Submittal and approval of the proposed construction schedule by the Engineer is required before construction activities can commence.

3. Shop Drawings.

- a. Before any items are ordered or installation is started, submit the following list of shop drawings for approval according to Article 1105.03 of the Standard Specifications:
 - 1) Handholes
 - 2) Fiber Markers
 - 3) Test Stations
 - 4) Ground Rods
 - 5) Exothermic Welding Kit
 - 6) HDPE Conduit
 - 7) Conduit Splice Kit
 - 8) 1C No. 10 AWG Tracer Wire
 - 9) Tracer Wire Splice Kit
 - 10) 12 SM Dielectric Fiber Optic Cable
 - 11) Duct Plugs
 - 12) OTDR Meter with Calibration Certificate from Manufacturer within last year
- b. The Engineer will review the shop drawings/catalog cuts for the purpose of assuring general conformance with the project design concept and contract documents. The Engineer will provide approval or rejection of shop drawings within 14 calendar days of the submission. Re-submit the shop drawings for approval within 7 days of the Engineer's rejection.
- c. Provide written notice of any deviations from the requirements of the contract documents or Special Provisions.
- d. Engineer's approval of shop drawings/catalog cuts does not relieve the Contractor of responsibility for providing satisfactory materials complying with the contract documents. Errors not detected during review do not authorize the Contractor to proceed in error.
- e. Order all materials requiring production lead time greater than 4 weeks within 7 calendar days of receiving the approved shop drawing(s). Submit to the Engineer proof of material purchase order in electronic PDF format.

4. Warranty.

- a. Transfer all required standard materials warranties on the date of final acceptance to the Iowa DOT.
- b. Warranty periods shall not commence prior to final acceptance of the work and shall remain in effect until at least 1 year after the final acceptance for all cables and equipment furnished and installed for this project.

C. Disruption to Existing Fiber Networks.

1. Planned Work Near Existing Fiber Networks.

- a. Ensure continuous operation of the existing fiber networks and systems during construction of the project. Repair to Engineer's satisfaction and at no cost to Iowa DOT, any damage caused to the existing fiber networks and systems during the life of the project.
- b. Do not work on splicing, disconnecting and/or in any way disrupting normal operation of the existing fiber networks or systems without approval from all affected parties. Parties include the Iowa DOT, the Iowa Communications Network (ICN), and other local agencies. Provide a written request to the Iowa DOT and the respective parties for approval at least 10 calendar days before work is done near an existing fiber network or equipment. Submit a copy of the written request to the Iowa DOT in all cases. In addition to the written request, submit the work plan and schedule for approval by the Engineer. The work plan shall include all fiber strands and the parties possibly affected. Restore the disrupted system upon completion of the work within the allowable working hours as noted in the contract

documents. Remain on site until Iowa DOT and/or ICN notifies that the disrupted systems are fully operational. Failure to restore disrupted systems and equipment within the allowable working hours will constitute an unplanned disruption.

2. Allowable Working Hours.

Disruptions to the existing systems shall only occur between midnight and 6:00 AM on working days unless otherwise approved by the Engineer.

3. Unplanned Disruption.

- a. Apply Article 1107.15 of the Standard Specifications and the following:
- b. In the event of an unplanned disruption, simultaneously notify the Iowa DOT and the affected party's representative. The notice shall include the type of facility damaged and the extent of the damage. Immediately stop all work in progress and expend all efforts to restore the disrupted system(s) and/or correct the problem causing the disruption.
- c. Remain on site until the Iowa DOT and ICN confirms that the disrupted systems are fully operational. Unplanned disruptions will result in the assessment of liquidated damages.
- d. The Contractor will not be granted an extension of time for delays caused by repairing disrupted systems.
- e. Correct any unplanned disruptions caused by the Contractor at no additional cost to Iowa DOT. If not repaired in a timely manner, any costs incurred by the Iowa DOT to restore the disruption will be charged to the Contractor.

D. As-Built Documentation.

1. General.

- a. Maintain written records of daily construction progress, areas worked, and quantities installed to aid in the completeness of as-constructed documentation.
- b. Provide as-built documentation package with the following:
 - 1) Documentation of fiber cable sequentials at building entrances, cabinets, and in/out of handholes.
 - 2) Master record set of plans (maintained throughout construction) documenting any deviations from the design shown in the original contract documents.

2. GPS Data Recording Staking Assistance.

- a. The Engineer will be responsible for collecting GPS data of all installations including, but not limited to conduit routing and handholes.
- b. Coordinate and assist the Engineer in this effort by staking, flagging or otherwise locating all installed features until such time that the GPS data can be collected.

150869.02 MATERIALS.

A. General.

1. Provide any items, equipment, or materials not specifically addressed in the contract documents but required to provide a complete and functional installation. The level of quality shall be consistent with other specified items. All miscellaneous electrical equipment and materials shall be listed for its specific application.
2. Stake all handholes and proposed conduit alignment per coordinates provided in the contract documents a minimum of 1 week prior to construction and for approval by the Engineer. The Engineer will authorize any changes in location in writing before performing the installation. No additional compensation will be provided for additional work associated with or resulting from unauthorized changes to the contract documents.

B. ITS Construction Survey.

1. General.

ITS construction survey includes personnel, equipment, and supplies required for fiber optic line and ITS construction surveying and staking necessary for construction of the project as shown in the contract documents.

2. Documentation.

Format the survey work documentation in a manner acceptable to the Engineer. Ensure documentation is sufficient to prove means and methods used to transfer design intent to construction stakes. Check tie-ins with existing roadways, structures, and utilities prior to staking; notify the Engineer if discrepancies are found.

3. Qualifications.

Perform ITS construction survey directly by or under responsible charge of a Professional Land Surveyor licensed in the State of Iowa.

4. Lath.

Provide wood lath that is approximately 3/8 inch thick by 1 1/2 inches wide by 48 inches long.

5. Survey Equipment.

Utilize survey equipment with a level of accuracy that will result in less than 6 inches of error horizontally.

C. High Density Polyethylene Conduit.

1. High Density Polyethylene (HDPE) conduit shall be smooth wall ORANGE in color.
2. Comply with ASTM F 2160 (conduit) and ASTM D 3350 (HDPE material), minimum SDR 13.5 or 11 as specified in the contract documents.
3. Sequential foot markings printed on HDPE.
4. Continuous reel or straight pieces to minimize splicing.
5. For dissimilar conduit connections provide an adhesive compatible with both materials.

D. Handholes.

1. General.

- a. Supply handholes constructed of epoxy or polyester resin mortar with woven glass fiber reinforcement and an appropriate aggregate dimensioned as indicated in the contract documents.
- b. Handhole materials shall not support combustion when tested in accordance with "Standard Test Method for Rate of Burning and/or Extent and Time of Burning of Plastics in a Horizontal Position" ASTM D-635.
- c. Water absorption shall not exceed two percent of the original weight of material under test conditions per "Standard Test Method for Water Absorption of Plastics" ASTM D-570.
- d. The handhole shall be functional without failure throughout a temperature range of -50°F to +170°F.
- e. The handhole walls shall not deflect more than 0.24 inches per foot of length of box when installed and subject to an ASTM C-857 TIER 22 load.
- f. Handholes shall meet or exceed ANSI/SCTE 77 "Specification for Underground Enclosure Integrity" requirements.
- g. Handhole lid strength shall be tested to 33,750 pounds (Tier 22).
- h. Handhole lids shall be labeled as indicated in the contract documents or as directed by the Engineer.

2. Test Stations.

- a. Test Stations shall be 78 inch triangular flexible orange plastic marker with five separate access terminals, isolation lever, and set screw to hold terminal concealment cap on.
- b. Test stations shall be orange in color with a black cap.
- c. Place Engineer approved custom warning decals on all sides.

3. Fiber Marker.

- a. Supply triangular post markers orange in color with an orange cap.
- b. Markers shall be 78 inch, polyester resin with reinforcing fibers, and remain flexible from -40°F to +140°F. Place custom warning decals on all sides, the Engineer will provide prior approval of decals.

E. Wire & Cable.

1. Grounding/Bonding.

Comply with Article 4189.01 of the Standard Specifications

2. Tracer Wire.

- a. Single conductor copper clad steel, No. 10 AWG with orange colored jacket.
- b. Use a Tracer-Lock Connector (#TL-LUG-SS) or approved equivalent on all mainline and lateral connections.

3. Fiber Optic Cable

- a. The 96 strand armored fiber optic cable for this project will be provided by the Iowa DOT. This fiber cable can be picked up from the Iowa DOT Ames Central Complex. Contact Jason Dale (515-239-1995) to make arrangements to pick up the fiber cable.
- b. Supply the 12 strand dielectric fiber optic cable.

c. General.

- 1) The cable shall meet the latest applicable standard specifications by ANSI, EIA and TIA for the single-mode fiber cable of the size specified per the contract documents.
- 2) Provide all fiber-optic cable for installation.
- 3) Provide the Engineer the manufacturer's production test provided with the spool.
- 4) Provide the Engineer with documentation of wasted cable.
- 5) The buffer tubes shall be compatible with standard hardware and shall have 12 fibers per tube, the fibers shall not adhere to the inside of the buffer tube, each fiber shall be distinguishable by means of color coding in accordance with TIA/EIA-598-B "Optical Fiber Cable Color Coding" and be colored with ultraviolet (UV) curable ink.
- 6) The cable core shall be water blocked with dry water blocking materials to improve access and handling of individual tubes.
- 7) The cables shall be designed for point-to-point applications as well as mid-span access and provide a high-level of protection for fiber installed in the outside plant environment.
- 8) The optical fiber shall be fully capable of handling existing and legacy single-mode applications which traditionally operate in the 1310 nm and 1550 nm regions and shall also be designed to operate the full-spectrum from 1260 nm to 1625 nm for optical transmission.
- 9) The optical fiber shall be designed to provide optimum performance from 1260 nm to 1625 nm intended for 16 channel Course Wavelength Division Multiplexing applications.
- 10) The optical fiber glass shall be manufactured by a United States of America based manufacturing company. Corning, OFS, or Prysmian/Draka.
- 11) The MDPE jacket material shall be as defined by ASTM D1248, Type II, Class C, Category 4 and Grades J4, E7 and E8.
- 12) The jacket or sheath shall be free of holes, splits, and blisters.
- 13) Cable jackets shall be marked with the manufacturer's name, month, and year of manufacturer, sequential foot markings, the symbol for communication cable as required by Section 350G of the National Electrical Safety Code (NESC), fiber count, and fiber type. The actual length of the cable shall be within -0/+1% of the length

markings. The print color shall be white, with the exception that cable jackets containing one or more coextruded white stripes, which shall be printed in light blue. The height of the marking shall be approximately 2.5 mm.

- 14) The maximum pulling tension shall be 600 pounds during installation (short term) and 200 pounds installed (long term).
 - 15) The shipping, storage, and operating temperature range of the cable shall be -40°C to +70°C. The installation temperature range of the cable shall be -30°C to +70°C.
- d. **Single-Mode, Fiber-Optic OSP Cable – Dielectric Loose Tube.**
- 1) Fiber-optic, single-mode, graded loose tube dielectric cable constructed with industry standard 2.5 mm buffer tubes stranded around a central strength member.
 - 2) Single-mode, dispersion-unshifted fiber meeting ITUT G.652D requirements.
 - 3) Cables shall be sheathed with medium density polyethylene (MDPE). The minimum nominal jacket thickness shall be 1.3 mm. Jacketing material shall be applied directly over cable core and water swellable tape. The polyethylene shall contain carbon black to provide ultraviolet light protection and shall not promote the growth of fungus.
 - 4) The cable jacket shall contain no metal elements and shall be of a consistent thickness.

150869.03 CONSTRUCTION.

A. General Responsibilities.

1. Stake all handholes and proposed conduit alignment per coordinates provided in the contract documents, a minimum of 1 week prior to construction for approval by the Engineer. The Engineer will authorize any changes in location in writing before performing the installation. No additional compensation will be provided for additional work associated with or resulting from unauthorized changes to the contract documents.
2. Take figured dimensions on the plans as correct but check before starting construction. Bring any errors, omissions, or discrepancies to the attention of the Engineer and the Iowa DOT's decision thereon will be final. Correction of errors or omissions on the drawings or specifications may be made by the Iowa DOT when such correction is necessary for the proper execution of the work.
3. Coordinate work with the Engineer. The Engineer will assist in the coordination and scheduling of work. Assign a responsible staff member that will work with the Engineer on decisions regarding order of work and scheduling as needed throughout the duration of this project.
4. Provide the Engineer any requests to perform work during the dates of special events a minimum of 5 calendar days prior to the event. The decision of the Engineer regarding the request will be final.
5. Comply with any special provisions and limitations identified in the contract documents.

B. Material and Equipment Storage and Construction Site Access.

1. Secure a designated material storage area for this project. Any request to store material in the right-of-way in order to complete the current work activity will be approved by the Engineer.
2. Construction equipment may be stored within the right-of-way during non-working hours if it is outside of the roadway preferred clear zone, as far from the traveled way as practical and as approved by the Engineer. Do not store equipment at the toe of any roadway slope.
3. No worker vehicles will be allowed to park in or access a job site directly from an Interstate or Freeway facility. Access to the job site for both workers and materials shall only be via interchanges or intersecting roadways unless otherwise approved by the Engineer. Park worker vehicles off-site or at a location acceptable to the Engineer.

4. Do not leave open holes or mounds of dirt unprotected during non-working hours.

C. ITS Construction Survey.

1. Apply Section 2526 of the Standard Specifications for ROW staking.
2. Place stakes at the following locations and label with item being staked:
 - Handholes.
 - Conduit and/or cable alignment direction changes.
 - Transitions from plow to bore or bore to plow.
 - At locations requiring specific depths to avoid existing or future facilities.
 - A minimum of 25 feet apart along critical conduit locations where contract documents specify depth greater than standard and trenchless (bored) installation methods as described in Section 2553 of the Standard Specifications.
 - A minimum of 100 feet apart along plowed conduit and non-critical bored conduit (bore areas where no minimum depth is called out in plans other than the typical minimum depth noted in the General Notes of the plan set).
 - At other locations as noted within the contract documents.
3. On stakes marking bore locations, label with required minimum conduit depth below existing grade.

D. Finishing Activities.

Upon completion of the work at each project area, thoroughly clean the site and restore it to a condition at least equal to that existing prior to construction. Project area is defined as the approximate area disturbed during a normal week of work. During and after completion, employ appropriate measures for erosion control, where applicable. Seed and fertilize work areas upon completion of work in accordance with the contract documents.

E. Conduit.

1. General.

- a. Follow all general guidelines covering the construction of buried conduit.
- b. Install conduit by plowing, jacking, pushing, boring, or other approved methods within the public right-of-way and in a manner that minimizes atypical damage from construction operations.
- c. The minimum bending radius of HDPE conduit shall be the larger of 20 times the outside diameter or the HDPE manufacturer's recommendations for minimum bending radius.
- d. Open trench installation is only permitted within 25 feet of any handhole, structure, or other similar improvements, and any other requested locations approved by the Engineer.
- e. At the discretion of the Engineer, verify the integrity of the conduit structure in a manner acceptable to the Engineer.
- f. Tunneling under the pavement or water jetting shall not be permitted.
- g. No excavations are permitted to cross any roadways or any other paved or other similarly improved areas. At these locations, install conduits by boring method unless otherwise directed or approved in writing by the Engineer. Where indicated in the contract documents and at all roadway and stream crossings, install conduit sections with external protection as specified herein.
- h. No direct-buried cable is allowed.
- i. Unless otherwise indicated in the contract documents, installation of Schedule 40 PVC conduit or approved alternative is allowed only in open trench runs or when approved by the Engineer.
- j. Seal all conduit openings using duct plugs or as directed by the Engineer, at all conduit openings at the junction boxes, handholes, and building entrances.
- k. Thread and cap all rigid steel conduit ends with standard conduit caps until wiring is installed. Before wiring is installed, replace caps with threaded insulating bushing in accordance with Article 2523.03, N of the Standard Specifications.

2. Installation Clearances.

- a. Depth of all bores shall be a minimum of 48 inches unless otherwise specified in the contract documents.
- b. Maintain the typical offsets from referenced locations as shown in the contract documents.
- c. Maintain the minimum depth throughout the length of all conduit installations.
- d. Maintain a minimum of 2 feet of separation when underground conduits parallel an existing facility.
- e. Maintain a minimum of 2 feet vertical separation when crossing existing utilities.

3. Conduit Splicing.

- a. Install conduit with minimal splices between handholes and structures as shown on contract documents.
- b. All mechanically joined conduit splices shall use compression couplings designed for underground placement and blown-in fiber installation.
- c. Butt fusion welding and solvent welding of conduits will not be allowed.
- d. All conduit splices shall be designed to be watertight to 200 psi.
- e. Conduit splicing is incidental to the connected items of work.

4. Facilities Protection.

- a. Protect and maintain the conduit throughout construction and until final acceptance.
- b. To avoid possible damage to buried conduit from exposure to traffic, livestock and other hazards, complete trenching of laterals, trenching around culverts, construction of aerial inserts and similar operations as soon as practicable behind all segment installations.
- c. If more than 48 hours lag is expected behind a segment installation, install additional protective measures acceptable to the Engineer.

5. Backfilling.

- a. Apply Section 2552 of the Standard Specifications and the following:
- b. Backfill trenches and other excavations in lifts of 6 inches or less in compacted depth. Compact each layer thoroughly before placing subsequent layers.
- c. Remove all cinders, broken concrete, or other hard or abrasive materials in the backfill material before commencing backfilling operations.
- d. Remove and dispose of surplus and unsuitable materials upon completion of the backfilling operations in the area.
- e. Place and carefully hand tamp backfill under and around the structures in lifts not to exceed 4 inches in loose thickness. Use a suitably sized mechanical tamper for all areas inaccessible to rollers.
- f. Perform operations in a manner that minimizes soil erosion and employs appropriate storm water pollution prevention measures during all construction operations.
- g. Maintain work areas in a neat, clean, and orderly condition at all times.
- h. Upon completion of conduit/cable placing operations and any other work in an area, remove all debris, materials, tools, and equipment from the area and restore the disturbed area(s) to original or better condition within 24 hours or as soon as practicable as determined by the Engineer. Backfill all excavations and grade all disturbed areas during the restoration process.
- i. Remove and dispose of rock and debris excavated and remaining after backfilling as directed by the Engineer.

6. Surface Restoration.

- a. Replace or reconstruct features removed as a part of the work, such as sidewalks, driveways, curbs, roadway pavement, unpaved areas, or any other items.
- b. Immediately repair or replace any unauthorized disturbance or damage. Replace improved landscaping, lawns, scrubs, and hedge removed or damaged during construction in a manner acceptable to the Engineer. Re-sod damaged lawns using like grasses.
- c. Complete restoration according to the applicable sections of the Standard Specifications.

7. Multiple Duct Installation.

Install multiple ducts, in continuity, at locations indicated in the contract documents unless authorized in writing by the Engineer.

8. Plowing.

- a. Use equipment and construction methods subject to the approval of the Engineer that cause minimal displacement of the soil.
- b. Furnish competent supervision at all times at the site of plowing operations to assure compliance with the contract documents.
- c. The equipment shall be capable of extending the plow in order to maintain the required minimum depths under all terrain conditions.
- d. The reel carrier shall be of adequate size and be configured so that the reel sizes being used can be safely handled.
- e. Avoid damaging any paved surfaces, ditches, or other similar surface features. Immediately repair any damage to such features to the satisfaction of the Engineer.
- f. Perform plowing in accordance with standard industry practices using a prime mover with hydrostatic type steering and a vibratory plow. The design of the plowshare shall be such that the buried conduit passing through the plow shall not bind and shall not be bent in a radius less than 20 times the outside diameter of the conduit and maintains the structural integrity of the conduit. The feed chute shall have a removable gate for the purpose of inspection and to allow the conduit to be removed from or inserted into the feed chute at any intermediate point between splice locations. The conduit path inside the feed chute shall have low friction surfaces and be free of burrs and sharp edges to prevent damage to the conduit as it passes through. Smooth any welds before use. Internal guide rollers shall not be used. Exercise care during the plowing operation to avoid conduit damage. Feed the conduit into the ground through the plow loose and at no tension.
- g. Excavate as needed start and finish pits and pits at points of intersection in advance of plowing. Expose ends of casings and crossings of foreign utilities before the start of plowing operations for a conduit segment. Exercise care in the use of trenching and excavating tools and equipment to avoid damaging installed and intersecting conduits or other facilities.
- h. Restore plow furrowed areas to conform to the surrounding terrain using a rubber-tired tractor or heavy truck or a vibratory roller having a weight of 3 tons and a drum width between 4 and 6 feet or by other suitable means approved by the Iowa DOT.

9. Conduit in Trench.

- a. Use equipment and construction methods subject to the approval of the Engineer that cause minimal displacement of the soil.
- b. Excavate open trench straight as practicable. Shape the trench to be smooth, free from any sharp edges, and clear of debris and loose rock. Excavate only gradual grade changes.
- c. Do not leave trenches unattended at any time or open during non-working hours unless approved in writing by the Engineer. Install barriers or other protective measures to prevent livestock or persons from falling into an open trench when appropriate.
- d. Notify the Engineer immediately if solid rock is encountered at any location. Excavate rock trenches using a rock saw or other suitable equipment. The excavation, backfill, and road crossings in solid rock areas shall conform to the requirements stated above unless specifically exempted in this section.
- e. Rock excavation will be considered extra work and will be paid per Article 1109.03, B of the Standard Specifications. Obtain approval from the Engineer before commencing any rock excavation.

10. Trenchless Conduit Installation.

- a. Use equipment and construction methods subject to the approval of the Engineer that cause minimal displacement of the soil.

- b. Bore all crossings beneath roadways, streets, other paved surfaces, railroads, or other structure in accordance with requirements and regulations of the authority having jurisdiction and as directed in the contract documents.
- c. Limit bore hole sizes to the outside diameter of the conduit being placed.
- d. Locate bore pits a minimum of 2 feet from the edge of pavement or shoulder unless otherwise directed by the Engineer.

F. Handholes.

1. Install the type and size of handholes at the locations indicated in the contract documents.
2. Set top of all handholes level and flush with the pavement or soil grade.
3. Install coarse aggregate bedding below the handhole as identified in the contract documents.
4. Conduit shall enter the handhole from the bottom and extend conduit ends between 4 and 6 inches above the aggregate bedding.
5. Side penetrations of the handholes are not permitted.
6. Terminate each tracer wire run in test stations at ITS Handhole, 48 inch by 30 inch by 36 inch locations.
7. Install ground rods at all ITS Handholes, 48 inch by 30 inch by 36 inch and as indicated in the contract documents.
8. Seal all conduit openings using duct plugs, or as directed by the Engineer, at all conduit openings at the handholes after cable installation.
9. Rodent proof all handholes to the satisfaction of the Engineer.
10. Conduit entrance into junction boxes shall be through slip holes. Fasten conduit to the box using sealing type locknuts.
11. Place suitable backfill material according to Section 2552 of the Standard Specifications. Backfill is incidental to each handhole being installed and will not be paid for separately.

G. Wire and Cable.

1. General.

- a. All installations and connections shall comply with the contract documents and all generally accepted codes and standards.
- b. The Engineer will resolve all conflicts.

2. Grounding/Bonding.

- a. Ground all installations as indicated in the contract documents.
- b. Installation of grounds is incidental to the cost of the connected items of work.
- c. Ground all installations in accordance with the requirements of NEC. Supply and install additional grounding rods and equipment as necessary to satisfy such requirements at no additional cost to the Contracting Authority.

3. Tracer Wire.

- a. Install, splice, and test for continuity tracer wire in all conduit installations as indicated on the contract documents.
- b. Where new tracer wire is installed:
 - Splice tracer wire only in handholes to form a continuous network using splice kits listed for wet locations.

- Leave 50 foot coil of tracer wire in all 48 inch by 30 inch by 36 inch handholes to be terminated at the test station.
- Test all tracer wire for continuity, with approval by the Engineer, prior to final acceptance.
- c. Labeling Requirement
 - Place tags on all tracer wire identifying the direction of the tracer wire at every test station.
 - Tracer wire tags shall be self-laminating polyester material.
 - Tracer wire tags shall have black text with a white background.
 - Tracer wire tags shall be Panduit part number S075X150YAJ or approved equal.

4. Fiber-Optic Cable.

a. General.

- 1) Remove fiber-optic cable from the reel in a manner acceptable to the Manufacturer and Engineer.
- 2) Do not twist or bend the fiber-optic cable in excess of the limits recommended by the manufacturer.
- 3) As the cable is fed into the duct and conduit system, use a manufacturer approved water-based cable lubricant for all fiber-optic cable installations.
- 4) Protect at all times all proposed cables, cable ends, and any exposed portions of fiber-optic cable from damage including water intrusion.
- 5) Replace in kind any existing pull tape or tracer wire that is used as a pull rope for fiber-optic cable installation. The cost of any tracer wire or pull tape replacement shall be subsidiary to the fiber-optic cable installation.

b. Fiber-Optic Cable Testing.

- 1) Visually inspect fiber-optic cable prior to installation. Report any defects to Engineer.
- 2) Pre-installation (on-reel), test all strands of fiber (uni-directional) with an Optical Time Domain Reflectometer (OTDR) at 1310 nm and 1550 nm to verify attenuation, continuity and length of the cable. Measured length by the OTDR shall match manufacturer cable foot markings plus manufacturer provided helicity. Perform all tests in the presence of the Engineer and provide the Engineer with up to two copies of any software required for viewing electronic files of the OTDR traces. Fiber test results submitted to the Engineer that exceed the max attenuation loss specification will be identified as Out of Specification.
- 3) Test all strands of fiber per the contract documents with an OTDR at 1310 nm and 1550 nm to verify attenuation, continuity, and length of the cable. Measured length by the OTDR shall match manufacturer cable foot markings plus manufacturer provided helicity. Measured post installation length shall match pre-installation (on-reel) length +/- 50 feet for each strand. Perform all tests in the presence of the Engineer and provide the Engineer with up to two copies of any software required for viewing electronic files of the OTDR traces. Fiber test results submitted to the Engineer that exceed the max attenuation loss specification will be identified as Out of Specification.
- 4) The fiber-optic cable is to have a maximum attenuation of 0.4 dB/km at 1310 nm and 0.3 dB/km at 1550 nm when measured with an OTDR. Fiber test results submitted to the Engineer that exceed the max attenuation loss specification will be identified as Out of Specification.
- 5) Replace, as directed by the Engineer, any defect discovered during final acceptance at no additional cost to the Iowa DOT. Consider a defect to be any cable with an OTDR measured length that differs from the actual cable footage, excluding manufacturer's helicity.
- 6) All test equipment shall be factory certified within the last year. Provide copies of the certification 10 days prior to testing.
- 7) Record test results on a form supplied by the Contractor, with data compiled in PDF format through the meter manufacturer's software. No additional alteration using software beyond the meter manufacturer's software will be allowed. Submit test results in a format approved by the Engineer. Hand completed test forms on each fiber over

to the Engineer. Provide native test (electronic version) with no alterations and meter software for viewing of fiber traces. At a minimum, show the following:

- Cable and fiber identification (as approved by Iowa DOT).
- Operator Name.
- Date and Time.
- Setup and test parameters including wavelength, pulse width, range, scale and ambient temperature.
- Test results for OTDR test in both directions for total fiber trace, splice loss/gain (dB), connector loss (dB), all events greater than 0.05 dB, measured length from cable markings and total length from OTDR.
- Test results for attenuation test including measured cable length (cable marking), total length (from OTDR test), number of splices (from as-built) and total link end-to-end attenuation in each direction and the bidirectional average.

- 8) OTDR testing shall use a launch and receiving cable. Each cable shall be a minimum 3290 feet, or greater than the dead zone for the OTDR used for this test, whichever is larger.

c. Fiber-Optic Cable Installation

- 1) Use a suitable cable feeding method between the cable reel and the face of the duct and conduit to protect the cable and guide it into the duct.
- 2) Use dynamometers and breakaway pulling swings to ensure that the pulling line tension does not exceed 600 pounds.
- 3) The mechanical stress placed on a cable during installation shall not be such that the cable is twisted or stretched. Attach a pulling eye and swivel to the cable to prevent the cable from twisting.
- 4) Do not force cables around sharp corners and take precautions during installation to prevent the cable from being kinked or crushed.
- 5) Minimum bending radius during installation shall not be less than 20 times the outside diameter of the cable or as recommended by the manufacturer, whichever is greater.
- 6) Hand assist the pulling of the cable.
- 7) Iowa DOT approved installation methods include pulling, high air speed blowing, air-assist, push/pull installation, and air blown cable. Installation shall comply with all manufacturers' recommendations for cable installation including pulling tensions, bending radii, and methods, including use of rollers.
- 8) Carefully inspect the cable for jacket defects. If defects are noticed, immediately stop the pulling operation and notify the Engineer. The Engineer will make a determination of acceptability or will reject the cable.
- 9) Install the fiber cable in continuous runs as marked in the contract documents. End of reel splices or butt splices not shown in the contract documents will be pre-approved by the Engineer and are incidental to the cost of the installation of the cable. If approved, perform the end of reel or butt splices in existing splice vaults as shown in the contract documents. The cost associated with the end of reel or butt splices including splice closures, storage baskets, splice trays, protective sleeves, and all accessories shall be included in their respective items and shall not result in additional cost to Iowa DOT.
- 10) No splices are allowed unless indicated in the contract documents or approved by the Engineer.
- 11) Seal all conduit openings using duct plugs or as directed by the Engineer, at all conduit openings at the junction boxes and handholes after cable installation.

d. Facilities Protection.

- 1) In the event it is suspected that cable damage has occurred prior to final acceptance, test the cable with an OTDR within 72 hours after notification and submit a copy of the OTDR test to the Engineer upon completion.
- 2) Replace or repair, as directed by the Engineer, any damage occurring before final acceptance at no additional cost to the Iowa DOT. Perform any repairs or replacements as soon as reasonably possible unless otherwise approved by the Engineer.

- 3) Repair or replace any defect in the installed cable at no additional cost to the Iowa DOT. Consider a defect to be any condition resulting in a negative or adverse effect on current or future operations of the completed fiber-optic communication system as determined by the Engineer.
 - 4) Repair or replace any existing wiring that is damaged during fiber-optic cable installation, as directed by the Engineer, at no additional cost to the Iowa DOT.
- e. Slack Coils.**
- 1) Leave sufficient slack at each end of the cable to allow proper cable splicing and termination. The minimum slack amount shall be as follows or as indicated in the contract documents:
 - ITS Handhole, 24 inch by 36 inch by 36 inch – 100 feet
 - ITS Handhole, 48 inch by 30 inch by 36 inch – 150 feet
 - 2) Neatly coil slack cable in handholes. Bind the slack coils at a minimum of three points around the coil perimeter.
 - 3) Secure and support cables at intervals not exceeding 30 inches and not more than 6 inches from cabinets, boxes, fittings, outlets, racks, frames and terminals.
 - 4) For storage purposes, the minimum bending radius shall not be less than ten times the outside diameter of the cable or as recommended by the manufacturer, whichever is greater.
- f. Cable Identification.**
- 1) Place tags on all fiber-optic cable identifying the owner and direction of the cable.
 - 2) Tags shall be used to label fiber optic cable in every cabinet, handhole, and building termination.
 - 3) Tags shall be self-laminating rigid vinyl material.
 - 4) Tags shall clearly identify where each individual cable run originated and where it ends (handhole to handhole, handhole to cabinet, handhole to building, etc.). Include mileposts for handholes.
 - 5) Handwritten tags are not allowed.
 - 6) Tags shall use indelible ink or etching which does not fade in sunlight, or in buried or underground applications.
 - 7) Tags shall be of a material that does not become brittle or deteriorate for a period of 20 years due to moisture, sunlight, soil minerals, chemicals or other environmental elements.
 - 8) Engineer shall approve tag content before installation.
 - 9) For joint fiber installations with Department of Transportation and other agency (or entity) use, where the fiber will be owned by the other agency (or entity), install typical identifiers and/or markings for that fiber.

150869.04 METHOD OF MEASUREMENT.

A. ITS Construction Survey.

Lump sum item; no measurement will be made.

B. HDPE Conduit.

Linear feet shown in the contract documents.

C. Handholes.

By count.

D. Remove/Relocate Handholes.

By count.

E. Test Stations.

By count.

F. Fiber Markers.

By count.

G. Wire and Cable.

Linear feet shown in the contract documents.

H. Fiber-Optic Cable.

Linear feet shown in the contract documents.

I. Install Fiber-Optic Cable.

Linear feet shown in the contract documents.

J. Remove Fiber-Optic Cable.

Linear feet shown in the contract documents.

150869.05 BASIS OF PAYMENT.

A. ITS Construction Survey.

Payment will be at the lump sum price for ITS Construction Survey. Payment is full compensation for staking and re-staking.

B. HDPE Conduit.

1. Per linear foot.

2. Payment is full compensation for:

- a. The furnishing and installation of all conduits per the contract documents.
- b. Including all surface excavations or surface preparation work, repair or restoration of any disturbed areas to pre-construction conditions, proper water/moisture drainage materials.
- c. Conduit mounting on new or existing infrastructure.
- d. Furnishing all materials, labor, equipment, and other incidental items necessary to meet the requirements of the contract documents.

C. Handholes.

1. Each.

2. Payment is full compensation for:

- a. The furnishing and installation of all handholes.
- b. Including all surface excavations, repair or restoration of any nearby areas, concrete, proper water/moisture drainage materials, all necessary electric grounding materials and installation.
- c. Furnishing and installing all test stations at ITS Handhole, 48 inch by 30 inch by 36 inch locations.
- d. Furnishing all materials, labor, equipment, and other incidental items necessary to meet the requirements of the contract documents.

D. Remove/Relocate Handholes.

1. Each.

2. Payment is full compensation for:

- a. The removal or relocation of handholes noted in the contract documents.
- b. Including all surface excavations, repair or restoration of any nearby areas, concrete, proper water/moisture drainage materials.
- c. Disposal of old handholes that are not specified to be re-used.
- d. Furnishing all materials, labor, equipment, and other incidental items necessary to meet the requirements of the contract documents.

E. Test Stations.

1. Each.
2. Payment is full compensation for:
 - a. The furnishing and installation of all test stations.
 - b. Furnishing all materials, labor, equipment, and other incidental items necessary to meet the requirements of the contract documents.

F. Fiber Markers.

1. Each.
2. Payment is full compensation for:
 - a. The furnishing and installation of all fiber markers.
 - b. Furnishing all materials, labor, equipment, and other incidental items necessary to meet the requirements of the contract documents.

G. Wire and Cable.

1. Per linear foot.
2. Payment is full compensation for:
 - a. The furnishing and installation of all wire and cable.
 - b. Including the proper installation of the wire and cable into existing conduit and new conduit systems, supply and installation of splices and connectors, and slack, coiled, or stored wire or cables.
 - c. Furnishing all materials, labor, equipment, and other incidental items necessary to meet the requirements of the contract documents.
 - d. Prior to final acceptance, meet with the Engineer to demonstrate the locate system is working properly throughout the entire locate system.

H. Fiber-Optic Cable.

1. Per linear foot.
2. Payment is full compensation for:
 - a. The furnishing, testing, and installation of all cables and wire per the contract documents.
 - b. Furnishing all materials, labor, tools, consumable items and other incidental items necessary to meet the requirements of the contract documents.

I. Install Fiber-Optic Cable.

1. Per linear foot.
2. Payment is full compensation for:
 - a. The installation and testing of all fiber optic cables per the contract documents.
 - b. Furnishing all materials, labor, tools, consumable items and other incidental items necessary to meet the requirements of the contract documents.

J. Remove Fiber-Optic Cable.

1. Per linear foot.
2. Payment is full compensation for:
 - a. The removal of all fiber optic cable from existing conduits as noted in the contract documents.
 - b. Spooling the fiber optic cable and transporting to a location as requested by the Engineer.

- c. Furnishing all materials, labor, tools, consumable items and other incidental items necessary to meet the requirements of the contract documents.

ADDITIONAL ATTACHMENTS**Equipment and Materials List for Submittal Requirements.**

DESCRIPTION	MANUFACTURER	CATALOG NUMBER
ITS HANDHOLE, 24"x36"x36"		
ITS HANDHOLE, 48"x30"x36"		
TEST STATION		
FIBER MARKER		
GROUND ROD		
EXOTHERMIC WELDING KIT		
HDPE CONDUIT		
CONDUIT SPLICE KIT		
DUCT PLUGS		
1C No. 10 TRACER WIRE		
TRACER WIRE SPLICE KIT		
No. 6 AWG COPPER CABLE		
12 SM DIELECTRIC FIBER OPTIC CABLE		
OTDR METER (WITH CALIBRATION INFORMATION)		

Iowa DOT PROJECT NO. ITS-035-4(298)95--25-77