



**SPECIAL PROVISIONS
FOR
RECTANGULAR RAPID FLASH BEACON SYSTEM**

**Dubuque County
HDP-C031(110)--6B-31**

**Effective Date
April 19, 2022**

THE STANDARD SPECIFICATIONS, SERIES 2021, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

156220.01 DESCRIPTION

- A.** This section covers the furnishing of all labor, materials, tools, equipment and performances of all work and services necessary or incidental for the installation of the pedestrian-activated rectangular rapid flash beacon (RRFB) systems as indicated in the contract documents.
- B.** This work shall consist of furnishing and installing the solar-powered flashing beacon assembly complete with RRFBs, solar panel, battery pack with charger, LED driver, and wireless communications equipment, attached to a breakaway post or other approved mounting system as shown in the plans and as specified by the Engineer.

156220.02 MATERIALS

A. General System Requirements

- 1. All materials furnished, assembled, fabricated, or installed shall be corrosion resistant. All mounting hardware shall be Type 304 stainless steel.
- 2. All components shall be manufactured and assembled as a complete system rated for 24 hour/7 day a week/365 days a year operation.
- 3. The entire system shall have a minimum 3 year warranty.

B. Rectangular Rapid Flashing Beacons

- 1. The Contractor shall furnish and install two direction RRFB units mounted to the post as indicated on the plans. The RRFB housing shall be minimum 1/8 inch thick aluminum.
- 2. Each RRFB unit shall satisfy the MUTCD - *Interim Approval for Optional Use of Pedestrian-Actuated Rectangular Rapid-Flashing Beacons at Uncontrolled marked Crosswalks (IA-21)*,

dated March 20, 2018, and the 2009 edition of the MUTCD, including the unit size, mounting location, flash rate, and operational parameters.

C. Solar-assisted Battery-powered System

1. The solar-powered system shall be an easy to install, fully self-contained, weather, corrosion, and vandal-resistant unit with a premium grade UV-resistant head. The system shall be power autonomous without the need for an external power supply. The system shall have an operating temperature range of -35°F to 140°F.
2. The batteries shall be sealed, maintenance free, field-replaceable and rated best-in-class. The battery pack shall have a minimum rated lifespan of 3 years.
3. The solar engine shall be the high-efficiency type and rated for 20 watts. The system shall have the capacity to operate the beacons continuously for 30 days without solar charging and have automatic light control to provide useful light during extreme conditions that prevent charging over an extended period of time.

D. Wireless Communication System

1. At each crosswalk, all installed solar powered flashing beacon assemblies must communicate wirelessly using an unlicensed radio band so as to simultaneously commence operation of their alternating rapid flashing indications and cease operation simultaneously. The communication equipment shall comply with FCC requirements and the vendor representative shall field test the equipment prior to placing the units in operation to demonstrate the RRFBs ability to achieve proper operation under the requirements IA-21. The wireless communications of one RRFB installation shall not interfere with, or cause unintended operation of, RRFBs at nearby intersections.
2. The system shall have push-button activation. Each flashing beacon unit shall have one pedestrian pushbutton meeting ADA requirements.

E. Pole and Concrete Footing

The flashing beacon assembly shall be installed and mounted as indicated in the plans, using a concrete footing meeting the requirements of the Standard Specifications and the plans. The footing shall include a 2 inch PVC conduit that stubs-out from the side of the footing as detailed per the plans. A galvanized steel traffic signal post meeting the requirements of the Standard Specifications, of the diameter and length recommended by the RRFB manufacturer, up to a maximum length of 18 feet, shall be used to support the flashing beacon assembly hardware. All posts shall be steel and hot dipped galvanized.

F. Pedestrian Pushbutton Stations

1. The Accessible Pedestrian Signal (APS) shall be an audible-tactile pedestrian signal system and shall consist of all electronic control equipment, mounting hardware, push buttons and signs designed to provide both a pushbutton with a raised, vibrating tactile arrow on the button as well as a variety of audible indications for differing pedestrian signal functions.
2. The APS shall meet the following requirements:
 - a. 2009 MUTCD, Chapter 4E – Pedestrian Control Features.
 - b. NEMA TS 2 Section 2.1 requirements for Temperature and Humidity, Transient Voltage Protection and Mechanical Shock and Vibration.
 - c. IEC 61000-4-4; 4-5 Transient Suppression requirements.
 - d. FCC Title 47, Part 15, Class A, Electronic Noise requirements.
3. The APS pushbutton enclosure shall meet the NEMA 250 – Type 4X enclosure requirement.

4. The APS pushbutton stations shall be POLARA Model-X (XAV2E-LED) or approved equals.
5. Upon installation the APS shall have the following functional requirements:
 - a. The APS shall be programmable and adjustable. Programming and adjustments shall be made using a laptop computer or vendor supplied programmer. No additional hardware or equipment shall be required. The APS shall be fully compatible with the three latest versions of the Windows operating platform. The programmable features shall be:
 - 1) Push-button locator tone.
 - 2) Audible push-button informational message upon pushbutton activation that says "yellow lights are flashing". This message shall be spoken twice.
 - 3) Audible crossing beacon.
 - 4) Vibrating tactile arrow.
 - 5) Independent minimum and maximum volume limits for the Locator Tone, Walk and Audible Beacons features.
 - b. All audible features shall emanate from the pedestrian pushbutton housing. The APS shall utilize digital audio technology, having a minimum 12 bit sample at a 16k Hz sample rate. Total harmonic distortion shall be less than 3% at 75 decibels. The APS shall provide independent ambient sound adjustment for the Locator Tone feature. The APS shall allow for Locator Tone volume to be set below the ambient noise level. The system shall have, at a minimum, three programmable locator tones. All sound levels shall adjust automatically utilizing an internally mounted, interval ambient sensing microphone, in accordance with the MUTCD.
 - c. The APS shall monitor the Walk condition for conflict operation. As a standalone unit, the APS shall disable the Walk functionality should a conflict be detected.
 - d. The APS system shall log cumulative call data. The data shall be date and time stamped, and shall be accessible via laptop.
 - e. The system shall have a programmable Extended Push Activation feature with the ability to extend the Walk time and provide an informational audible message. Activation shall be programmable from one to six seconds.
 - f. The system shall provide a programmable audible Wait message when the button is pushed. The message shall only announce once per actuation.
6. The APS manufacturer must provide the required voice messages in each button. Additionally, the APS manufacturer must supply backup copies of the voice messages to Dubuque County.
7. The appropriate Braille message shall be added to the pedestrian information sign.

G. Signage

1. All signs shall meet MUTCD requirements. Signs to be installed as part of the RRFB assembly and required mounting hardware shall be considered incidental to this item.
2. TAPCO Rectangular Rapid Flash Beacon: RRFB-XL2 has met the above specification and shall be used or approved equal.

156220.03 CONSTRUCTION

A. Construction Requirements

1. The solar powered flashing beacon assembly and system shall be installed in strict accordance with the manufacturer's recommendations, applicable portions of the Standard Specifications, as shown on the Plans, and as directed by the Engineer.

2. Mounting of the hardware to the foundation shall be in accordance with the Standard Specifications modified herein and shall follow all manufacturer recommendations. The traffic signal post and pedestal base shall be installed on the foundation in accordance with the manufacturer recommendations.
3. The beacons and solar engine shall be attached to the structure using rigid galvanized steel conduit, stainless steel straps, manufacturer recommended mounting brackets, and U-bolts.
4. The beacons shall be installed as shown on the Plans. The final elevation and location of the beacons must be approved by the Engineer prior to beginning work.
5. The solar panel shall be installed at the highest point on the assembly structure, or as directed by the Engineer, and away from the travelled way. The solar engine shall be installed at a 45 degree angle facing the equator (due south) with full unobstructed solar exposure for optimum performance of the system, or as recommended by the manufacturer and directed by the Engineer.

B. Inspection

The Contractor shall inspect all the electrical equipment and shall notify the Engineer in writing before the equipment is installed if the equipment appears to be deficient in fit, form or function.

C. Coordination

It shall be the sole responsibility of the Contractor to coordinate among suppliers and contractors providing equipment for the project.

156220.04 METHOD OF MEASUREMENT

By Each

156220.05 BASIS OF PAYMENT

- A. This item will be paid at the contract unit price for each Solar-Powered Flashing Beacon Assembly. All labor, materials, and equipment necessary for installation of a functioning pedestrian-activated flashing beacon assembly will not be paid for separately, but shall be considered incidental to this item.
- B. Each unit includes, but is not limited to the following:
 - Programming Software Kit
 - Wireless Communication System
 - LED Light Bars
 - Solar Panels
 - APS Pushbuttons with MUTCD R10-25 signs
 - Remote Pushbutton Pedestals
 - 13 foot Pole Kit with J-Bolts for Concrete Installation
 - Concrete Footings (1 foot diameter by 3.5 feet deep) – for pushbutton pedestals
 - Concrete Footings (2 foot diameter by 3 feet deep) – for RRFB poles
 - 36 inch Pedestrian Crossing Signs (MUTCD W11-2, fluorescent yellow-green)
 - 24 inch by 12inch Down Arrow Right Signs (MUTCD W16-7P, fluorescent yellow-green)
 - 24 inch by 12 inch Down Arrow Left Signs (MUTCD W16-7P, fluorescent yellow-green)
 - Back to Back Sign Mounting Brackets
 - Wiring, conduit, and other miscellaneous brackets and mounting hardware