



**SPECIAL PROVISIONS
FOR
PEDESTRIAN COUNTER**

**Linn County
TAP-U-1187(799)--8I-57**

**Effective Date
September 21, 2021**

THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

157162.01 DESCRIPTION.

This section covers the furnishing and installation of pedestrian counter system as indicated on the drawings or as specified herein. This item includes all labor, materials, tools, equipment and performance of all work and services necessary or incidental for the installation of the pedestrian counter.

157162.02 MATERIALS.

A. Pedestrian Counter.

Pedestrian counter shall be Eco Counter MULTI Urban with 15 foot range and direction detection and with Bluetooth data transmission capabilities.

B. Post and Mounting System.

The post and mounting system shall be manufacturers recommended post and mounting system.

157162.03 CONSTRUCTION.

Construct to the dimensions and location as shown in the contract documents and according to the manufacturer's recommendations.

157162.04 METHOD OF MEASUREMENT.

Each Pedestrian Counter shall be counted.

157162.05 BASIS OF PAYMENT.

Payment will be contract unit price for each Pedestrian Counter. Payment is full compensation for furnishing all parts, hardware, and other materials needed, and for labor, equipment, and materials necessary to install a fully functioning pedestrian counter.