



**SPECIAL PROVISIONS
FOR
RIGID FOAM INSULATION BOARD**

**Linn County
TAP-U-1187(799)--8I-57**

**Effective Date
September 21, 2021**

THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

157193.01 DESCRIPTION.

This section covers the furnishing and installation of rigid foam insulation board as indicated on the drawings or as specified herein. This item includes all labor, materials, tools, equipment and performance of all work and services necessary or incidental for the installation of the rigid foam insulation board.

157193.02 MATERIALS.

Rigid Foam Insulation Board shall be 4 feet in width by 2 inches thick.

157193.03 CONSTRUCTION.

Install rigid foam insulation board at locations identified in the contract documents, and in accordance with the detail included in the plan set.

157193.04 METHOD OF MEASUREMENT.

Rigid Foam Insulation Board shall be measured in square feet. Where multiple 2 inch thick rigid foam insulation boards are specified to be stacked to provide greater than 2 inch thickness of insulation the area of each 2 inch thick rigid foam insulation board shall be measured.

157193.05 BASIS OF PAYMENT.

Payment will be contract unit price per square foot of Rigid Foam Insulation Board. Payment is full compensation for furnishing, placing, and compacting designated fill material both below and above and for furnishing and installing Rigid Foam Insulation Board.